

jc660 U.S. PTO  
05/03/99

A

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

**INVENTOR:** Tony M. Pearce  
**DOCKET:** 5039 P  
**TITLE:** IMPROVED CUSHIONING DEVICES, GELATINOUS  
ELASTOMER MATERIALS AND DEVICES MADE  
THEREFROM  
**ASSIGNEE:** TekSource, LC

jc618 U.S. PTO  
09/30/97  
05/03/99

Assistant Commissioner for Patents  
Washington, DC 20231

**COVER LETTER**

Honorable Assistant Commissioner:

Enclosed please find a utility patent application, assignment, statements of small entity status, declaration of inventor and fee. Please record the assignment.



Daniel McCarthy  
Reg. No. 36,600  
McCarthy & Sadler, LC  
39 Exchange Place, Suite 100  
Salt Lake City, Utah 84111  
(801) 323-9399

09/30/97 05/03/99

**IN THE UNITED STATES PATENT AND TRADEMARK OFFICE**

**INVENTOR:** Tony M. Pearce

**ASSIGNEE:** TekSource, LC

**DOCKET:** 5039 PRV

**TITLE:** **IMPROVED CUSHIONING DEVICES, GELATINOUS  
ELASTOMER MATERIALS AND DEVICES MADE  
THEREFROM**

Assistant Commissioner for Patents  
Washington, DC 20231

**VERIFIED STATEMENT (DECLARATION)  
CLAIMING SMALL ENTITY STATUS**

**--INDEPENDENT INVENTOR--  
(37 CFR 1.9(c) and (f) and 1.27(b))**

As the below named inventor, I hereby declare that I qualify as independent inventor as defined in 37 CFR 1.9(c) for purposes of paying reduced fees under section 41(a) and (b) of Title 35, United States Code, to the Patent and Trademark Office with regard to the invention entitled

**IMPROVED CUSHIONING DEVICES, GELATINOUS  
ELASTOMER MATERIALS AND DEVICES MADE  
THEREFROM**

described in the specification filed herewith.

I have not assigned, granted, conveyed or licensed and are under no obligation under contract or law to assign, grant, convey or license any rights in the invention to any person who could not be classified as an independent inventor under 37 CFR 1.9(c) if that person had made the invention, or to any concern which would not qualify as a small business concern under 37 CFR 1.9(d) or a nonprofit organization under 37 CFR 1.9(e).

I acknowledge the duty to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the due date on which status as a small entity is no longer appropriate. (37 CFR 1.28(b)).

*Tony Pearce*  
Signature of Inventor

5/3/99  
Date

5/3/99

Date \_\_\_\_\_

**IN THE UNITED STATES PATENT AND TRADEMARK OFFICE**

**INVENTOR:** Tony M. Pearce

**ASSIGNEE:** TekSource, LC

**DOCKET:** 5039 PRV

**TITLE:** **IMPROVED CUSHIONING DEVICES, GELATINOUS  
ELASTOMER MATERIALS AND DEVICES MADE  
THEREFROM**

Assistant Commissioner for Patents  
Washington, DC 20231

**VERIFIED STATEMENT (DECLARATION)  
CLAIMING SMALL ENTITY STATUS**

**--SMALL BUSINESS CONCERN--  
(37 CFR 1.9(f) and 1.27(c))**

I hereby declare that I am an official of the small business concern identified below and that I am empowered to act on behalf of said concern:

**NAME OF CONCERN:** TekSource, LC

**ADDRESS OF CONCERN:** 12577 South 265 West, Bldg. 3A  
Draper, Utah 84020

I hereby declare that the above identified small business concern qualifies as a small business concern as defined in 13 CFR 121.3-18, and reproduced in 37 CFR 1.9(d) for purposes of paying reduced fees under section 41(a) and (b) of Title 35, United States Code, to the Patent and Trademark Office in that the number of employees of the business concern does not exceed 500 persons. For purposes of this statement, (1) the number of employees of the business concern is the average over the previous fiscal year of the concern of the persons employed on a full-time, part-time or temporary basis during each of the pay periods of the fiscal year, and (2) concerns are affiliates of each other when either, directly or indirectly, one concern controls or has the power to control the other, or a third party controls or has the power to control both.

I hereby declare that rights under contract or law have been conveyed to and remain with the small business concern identified above with regard to the invention entitled **IMPROVED**



**CUSHIONING DEVICES, GELATINOUS ELASTOMER MATERIALS AND DEVICES  
MADE THEREFROM** by the inventor(s)

I acknowledge the duty of the small business concern to file, in this application or patent, notification of any change in status resulting in loss of entitlement to small entity status prior to paying, or at the time of paying, the earliest of the issue fee or any maintenance fee due after the due date on which status as a small entity is no longer appropriate. (37 CFR 1.28(b)).

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under section 1001 of Title 18 of the United States Code, and that such willful false statements may jeopardize the validity of the application, any patent issuing thereon, or any patent to which this verified statement is directed.

NAME OF PERSON SIGNING: Tony M. Pearce

TITLE OF PERSON SIGNING: President and Manager

ADDRESS: 12577 South 265 West  
Building 3A  
Draper, UT 84020

SIGNATURE: Tony M. Pearce

DATE: 5/3/99

1 SPECIFICATION

2 To all whom it may concern:

3 Be it known that Tony M. Pearce, a citizen of the United States of America, has  
4 invented a new and useful invention entitled "**IMPROVED CUSHIONING DEVICES,**  
5 **GELATINOUS ELASTOMER MATERIALS, AND DEVICES MADE THEREFROM**" of  
6 which the following comprises a complete specification.

1                   **IMPROVED CUSHIONING DEVICES, GELATINOUS**  
2                   **ELASTOMER MATERIALS, AND DEVICES MADE**  
3                   **THEREFROM**  
4

5   **PRIORITY:** Priority is hereby claimed to the following United States Patent Application Serial  
6   Nos.: 08/968,750, now U.S. Patent No. 5,749,111; Serial Nos. 08/601,374; 08/783,415;  
7   08/780,839; 08/783,414; 08/783,413; 08/780,838; and 08/783,412; 60/086,344; 60/096,976;  
8   60/084,002; 60/084,000; 60/084,004; 60/084,003.

9   **I.       Background of the Invention**

10   **A.       Field of the Invention**

11       This invention relates to the field of cushioning devices, gelatinous elastomers and  
12   devices made therefrom. More particularly, some embodiments of this invention relate to a  
13   cushion or cushioning device made in whole or in part of gelatinous elastomer, gelatinous visco-  
14   elastomer, and the elastomers themselves, methods for making any of the foregoing, and  
15   structures made from the foregoing and other cushioning structures and other devices including  
16   gelatinous elastomers.

17   **B.       The Background Art**

18       In the prior art, there have been numerous attempts to provide a cushion which achieves  
19   comfort by eliminating peak pressure areas and by evenly distributing the cushioning force over  
20   a broad surface area. Some of these attempts include foam cushions, fluid cushions, flowable  
21   heavy gel cushions, lubricated microsphere cushions, thermoplastic honeycomb film cushions,  
22   traditional spring mattresses, and gelatinous elastomers generally. Examples of prior art

1 gelatinous elastomers include the patents of John Y. Chen of Applied Elastomerics, Inc. of  
2 Pacifica, California. Some of Mr. Chen's patents include U.S. Patent Nos. 5,884,639; 5,868,587;  
3 5,760,117; 5,655,947; 5,633,286; 5,624,294; 5,508,334; 5,475,890; 5,336,708; 5,334,646;  
4 5,324,222; 5,262,468; 5,239,723; 5,153,254; 4,618,213; and 4,369,284. Mr. Chen's gel appears  
5 to be anticipated by two other prior art patents: United States Patent No. 3,827,999 issued to  
6 Crossland and United States Patent No. 5,618,882 issued to Hammond et al.

## 7 **II. Summary of the Invention**

8 It is an object of some embodiments of the invention to provide a cushion that distributes  
9 supporting pressure on an object being cushioned in a manner that is generally even and without  
10 pressure peaks. It is a feature of some embodiments of the invention that the cushion has a low  
11 surface tension and permits a cushioned object to sink deeply into it. This action is due to  
12 compressibility of the cushion. It is also a feature of some embodiments of the invented cushion  
13 that some of the columns present in the invented cushion tend to buckle under the weight of the  
14 object being cushioned. This buckling is especially useful in accommodating protrusions from  
15 the object being cushioned into the cushion. The ability to accommodate protrusions through  
16 buckling of the cushion columns eliminates pressure peaks. It is a consequent advantage of the  
17 invention that the invented cushion is comfortable and does not tend to constrict blood flow in  
18 the tissue of a human being on the cushion, thus being suitable for medical applications and other  
19 applications where the object being cushioned may be immobile for long periods of time, such as  
20 in footwear, automobile seats, furniture, mattresses, and other applications.

21 It is an object of some embodiments of the invention to provide a cushion that eliminates

1 the head pressure found in some fluid cushions. In fluid cushions, the flowable media may be  
2 drawn by gravity so that it exerts pressure on some portions of the cushioned object as the  
3 cushioning media attempts to flow in response to the gravitational force. This pressure is  
4 referred to as "head pressure." Head pressure can cause discomfort and tissue damage to a  
5 human using the cushion. The preferred embodiments of the invention do not develop head  
6 pressure.

7 It is an object of some preferred embodiments of the invention to provide a gelatinous  
8 elastomer from which cushioning devices may be made. Some preferred embodiments of the  
9 invention provide such a gelatinous elastomer with distinct strength advantages, elongatability,  
10 and bleed reduction compared to prior art gelatinous elastomers.

11 These and other objects, features and advantages of the invention will become apparent to  
12 persons of ordinary skill in the art upon reading the specification in conjunction with the  
13 accompanying drawings.

### 14 **III. Brief Description of the Drawings**

15 Figure 1 depicts one embodiment of the invented cushion as part of an office chair.

16 Figure 2 depicts one embodiment of the invented cushion including its cushioning  
17 element and cover.

18 Figure 3 depicts a cutaway of one embodiment of the invented cushion of Figure 1 at 3-3.

19 Figure 4 depicts a mold which may be used to manufacture one embodiment of the  
20 invented cushion.

21 Figure 5 depicts an alternative mold for manufacturing one embodiment of the invented

1 cushion.

2 Figure 6 depicts a cross sectional view of a cushion manufactured using the mold of  
3 Figure 5.

4 Figure 7 depicts an isometric view of an alternative embodiment of the invented cushion.

5 Figure 8 depicts a top view of an alternative embodiment of the invented cushion.

6 Figure 9 depicts an isometric view of an alternative embodiment of the invented cushion.

7 Figure 10 depicts a top view of an alternative embodiment of the invented cushion.

8 Figure 11 depicts a cross sectional view of a column of one preferred embodiment of the  
9 invention during one mode of buckling.

10 Figure 12 depicts a cross sectional view of a column of one preferred embodiment of the  
11 invention during another mode of buckling.

12 Figure 13 depicts forces in play as a column one preferred embodiment of the invention  
13 buckles.

14 Figure 14 depicts an alternative structure for a column and its walls.

15 Figure 15 depicts a cross section of a cushion using alternating stepped columns.

16 Figure 16 depicts an alternative embodiment of the invented cushioning element having  
17 gas bubbles within the cushioning media.

18 Figure 17 depicts a cushion of one preferred embodiment of the invention in use with a  
19 combination base and container.

20 Figure 18 depicts a cushion of one preferred embodiment of the invention having side  
21 wall reinforcements to support the cushioning element.

1           Figure 19 depicts a cushioning element of one preferred embodiment of the invention  
2           having a girdle or strap about its periphery to support the cushioning element.

3           Figure 20 depicts a cushioning element of one preferred embodiment of the invention  
4           with closed column tops and bottoms and fluid or other cushioning media contained within the  
5           column interiors.

6           Figure 21 depicts a cushioning element of one preferred embodiment of the invention  
7           with firmness protrusions placed within the column interiors.

8           Figure 22 is a frontal perspective view of an embodiment of the cushioning element of  
9           the invention which include multiple individual cushioning units.

10          Figure 23a is a frontal perspective view of an embodiment of the cushioning element of  
11          the invention in which a first cushioning medium is contained within a second cushioning  
12          medium.

13          Figure 23b is a cross section taken along line 23b—23b of Figure 23a.

14          Figure 23c is a frontal perspective view of an alternate configuration of the embodiment  
15          shown in Figure 23a.

16          Figure 23d is a cross section taken along line 23d—23d of Figure 23c.

17          Figure 24a is a frontal perspective view of an embodiment of the cushioning element of  
18          the invention in which the outer surfaces of the cushioning medium are covered with a coating.

19          Figure 24b is a cross section taken along line 24b—24b of Figure 24a.

20          Figure 25a is a perspective view of an embodiment of the cushioning element of the  
21          present invention, wherein the cushion includes multiple sets of parallel columns and wherein

1 each column intersects no columns of another parallel column set or columns of only one other  
2 set.

3 Figure 25b is a cross section taken along line 25b—25b of Figure 25a.

4 Figure 25c is a cross section taken along line 25c—25c of Figure 25a.

5 Figure 25d is a perspective view of an alternative configuration of the embodiment shown  
6 in Figure 25a, wherein each column may intersect columns of any number of the other parallel  
7 column sets.

8 Figure 25e is a cross section taken along line 25e—25e of Figure 25d.

9 Figure 25f is a cross section taken along line 25f—25f of Figure 25d.

10 Figure 26 is a frontal perspective view of an embodiment of the cushioning element of  
11 the present invention wherein the cushion has multiple sets of parallel narrow columns.

12 Figure 27a is a frontal perspective view of an embodiment of the cushioning element of  
13 the present invention which includes multiple sets of parallel columns and cavities formed in the  
14 column walls.

15 Figure 27b is a cross section taken along line 27b—27b of Figure 27a.

16 Figure 27c is a cross section taken along line 27c—27c of Figure 27a.

17 Figure 28 is a frontal perspective view of an embodiment of the cushioning element  
18 according to the present invention which has a contoured surface and includes columns of more  
19 than one height.

20 Figure 29 is a frontal perspective view of an embodiment of the cushioning element of  
21 the present invention wherein the cushioning medium is foamed.



1        Figure 30a is a frontal perspective view of an embodiment of the cushioning element of  
2        the present invention wherein the column walls are formed from numerous short tubular pieces,  
3        which create voids in the column walls.

4        Figure 30b is a frontal perspective view of an alternative configuration of the cushioning  
5        element shown in Figure 30a, wherein the column walls include voids created by extracting  
6        space consuming objects therefrom following molding of the cushioning medium.

7  
8  
9        Figure 31a depicts a carbon atom and its covalent bonding sites.

10       Figure 31b depicts a hydrogen atom and its covalent bonding site.

11       Figure 31c depicts a four carbon hydrocarbon molecule known as butane.

12  
13       Figure 32a depicts a triblock copolymer useful in the preferred cushioning medium.

14       Figure 32b depicts the triblock copolymer of Figure 32a in a relaxed state.

15       Figure 33a depicts the chemical structure of a styrene molecule.

16       Figure 33b depicts the chemical structure of a benzene molecule.

17       Figure 33c depicts the chemical structure of an aryl group.

18       Figure 33d depicts the chemical structure of an -enyl group.

19       Figure 33e depicts the chemical structure of an ethenyl group.

20       Figure 33f depicts the chemical structure of a propenyl group.

21       Figure 34a depicts a midblock (B) of the triblock copolymer of Figure 32a.

Figure 34b depicts an endblock (A) of the triblock copolymer of Figure 32a.

Figure 34c depicts the weak bonding between the monomer units of one or more midblocks (B) of the triblock copolymer of Figure 32a.

Figure 34d depicts an endblock (A) of the triblock copolymer of Figure 32a, showing the endblock (A) in a relaxed state.

Figure 35a depicts the chemical structure of hydrocarbon molecules known as alkanes.

Figure 35b depicts the chemical structure of hydrocarbon molecules known as alkenes.

Figure 35c depicts the chemical structure of hydrocarbon molecules known as alkynes.

Figure 35d depicts the chemical structure of a hydrocarbon molecule known as a conjugated diene.

Figure 35e depicts the chemical structure of a hydrocarbon molecule known as an isolated diene.

Figure 36a depicts the chemical structure of a poly(ethylene/butylene) molecule.

Figure 36b depicts the chemical structure of a poly(ethylene/propylene) molecule.

Figure 36c depicts the chemical structure of a 1,3-butadiene molecule.

Figure 36d depicts the chemical structure of an isoprene molecule.

Figure 37a depicts polystyrene-poly(ethylene/butylene)-polystyrene.

Figure 37b depicts polystyrene-poly(ethylene/propylene)-polystyrene.

Figure 37c depicts polystyrene-polybutadiene-polystyrene.

Figure 37d depicts polystyrene-polyisoprene-polystyrene.

Figure 37e depicts polystyrene-poly(isoprene + butadiene)-polystyrene.

1 Figure 37f depicts polystyrene-poly(ethylene/butylene + ethylene/propylene)-polystyrene.

2 Figure 38a depicts the chemical structure of polystyrene-poly(ethylene/butylene +  
3 ethylene/propylene)-polystyrene.

4  
5  
6 Figure 38b depicts the group of the triblock copolymers of Figure 321a, showing weak  
7 attraction of the endblocks to each other.

8 Figure 39a illustrates plasticizer association with the group of triblock copolymers of  
9 Figure 38b according to a preferred formulation of the preferred cushioning medium.

10 Figure 39b illustrates the lubricity theory of plasticization, showing two midblocks (B)  
11 moving away from each other.

12 Figure 39c illustrates the lubricity theory of plasticization, showing two midblocks (B)  
13 moving toward each other.

14 Figure 39d illustrates the lubricity theory of plasticization, showing two midblocks (B)  
15 moving across each other.

16 Figure 39e illustrates the gel theory of plasticization, showing a weak attraction between  
17 two midblocks (B) when plasticizer is not present.

18 Figure 39f illustrates the gel theory of plasticization, showing a plasticizer molecule  
19 breaking the weak attraction of Figure 39e.

20 Figure 39g illustrates the mechanistic theory of plasticization, showing an equilibrium of  
21 plasticizer breaking the weak attraction of midblocks (B) for each other.

Figure 39h illustrates the free volume theory of plasticization, showing the free space associated with a midblock (B).

Figure 39i illustrates the theory of Figure 39h, showing that as small plasticizer molecules are added, the free space in a given area increases.

Figure 39j illustrates the theory of Figure 39h, showing the even small plasticizers provide an even greater amount of free space.

Figure 40a depicts the use of an extruder to perform a preferred method for foaming the one preferred gel cushioning media.

Figure 40b depicts the use of an injection molding machine to perform a preferred method for foaming the preferred gel cushioning media.

Figure 41 depicts an embodiment of a cushioning element according to the present invention, wherein a plurality of tubes are bonded together to form the cushion.

Figure 42 depicts a method for bonding the individual tubes of Figure 41 together to form the cushioning element shown therein.

### **III. Description of the Preferred Embodiment**

#### **A. Configuration of the Cushions**

Figure 1 depicts a cushioned object 101, in this instance a human being, atop of a piece of furniture 102, in this instance a chair, which includes the invented cushion 103. Although in this

1 embodiment, the invented cushion 103 is depicted as part of an office chair, the invented cushion  
2 may be used with many types of products, including furniture such as sofas, love seats, kitchen  
3 chairs, mattresses, lawn furniture, automobile seats, theatre seats, padding found beneath carpet,  
4 padded walls for isolation rooms, padding for exercise equipment, wheelchair cushions, bed  
5 mattresses, and others.

6 Referring to Figure 2, the cushion 103 of Figure 1 is depicted in greater detail. The  
7 cushion 103 includes a cover 204. The preferred cover is a durable and attractive fabric, such as  
8 nylon, cotton, fleece, synthetic polyester or another suitable material which is preferably  
9 stretchable and elastic and which readily permits the flow of air through it to enhance ventilation  
10 of a cushioned object. Within the cover 204, a cushioning element 205 is to be found. As can be  
11 seen from Figure 2, the cushioning element 205 comprises a cushioning media of a desired  
12 shape. In the embodiment depicted, the cushioning element 205 includes gel cushioning media  
13 formed generally into a rectangle with four sides, a top and a bottom, with the top and bottom  
14 being oriented toward the top and bottom of the page, respectively. The cushioning element has  
15 within its structure a plurality of hollow columns 206. As depicted, the hollow columns 206  
16 contain only air. The hollow columns 206 are open to the atmosphere and therefore readily  
17 permit air circulation through them, through the cover 204 fabric, and to the cushioned object.  
18 The columns 206 have column walls 207 which in the embodiment depicted are hexagonal in  
19 configuration. It is preferred that the total volume of the cushioning element will be occupied by  
20 not more than about 50% gel cushioning media, and that the rest of the volume of the cushioning  
21 element will be gas or air. More preferably, the total volume of the cushioning element will be

1 occupied by as little as about 9% cushioning media, and the rest of the volume of the cushion  
2 will be gas or air. This yields a lightweight cushion with a low overall rate of thermal transfer  
3 and a low overall thermal mass. It is not necessary that this percentage be complied with in  
4 every instance that the inventive concept is practiced, however.

5 Referring to Figure 3, a cushioned object 101, in this instance a human being, is depicted  
6 being cushioned by the invented cushion 103 which includes cushioning element 205 within  
7 cover 204. Also visible is a cushion base 301 of a rigid material such as wood, metal, plastic on  
8 which the cushioning element 205 rests. The cushioning element 206 includes hollow columns  
9 206 with walls 207. It can be seen that beneath the most protruding portion of the cushioned  
10 object, in this instance a hip bone 302, the hollow columns 303 have walls 304 which have  
11 partially or completely buckled in order to accommodate the protuberance 302 and avoid creating  
12 a high pressure point below the protuberance 302 in response to the compressive force exerted by  
13 the cushioned object. Buckled columns offer little resistance to deformation, thus removing  
14 pressure from the hip bone area. It can also be seen that in portions of the cushioning element  
15 205 which are not under the protuberance 302, the cushioning media which forms the walls 304  
16 of the hollow columns 303 has compressed but the columns 303 have not buckled, thus loading  
17 the cushioned object across the broad surface area of its non-protruding portions. The cushion is  
18 yieldable as a result of the compressibility of the cushioning media and the bucklability of the  
19 columns (or column walls). The cushion 103 is depicted as having been manufactured using the  
20 mold depicted in Figure 4. It can be seen from this cushion's response to a compressive force  
21 exerted by the cushioned object that the cushion and the cushioning element are adapted to have

1 a cushioned object placed on top of them.

2 Referring to Figure 6, a cross section of an alternative embodiment of the invention is  
3 depicted. The cushioning element 601 includes cushioning media 604 (which is preferred to be a  
4 gel cushioning media) which form walls 605 for columns 602, 603. It can be seen that the  
5 columns 602 and 603 are oriented into a group protruding from the top of the cushioning element  
6 601 down into the cushioning media 604 but not reaching the bottom of the cushioning element  
7 of which column 602 is a member, and a group protruding from the bottom of the cushioning  
8 element 601 into the cushioning element 601 but not reaching the top of the cushioning element  
9 601 of which column 602 is a member. This yields a generally firmer cushion than that shown in  
10 some other figures. This cushion would be manufactured by the mold depicted in Figure 5.

11 Referring to Figure 7, an alternative embodiment of a cushioning element 701 is depicted.  
12 The cushioning element includes cushioning media 702, columns 703 and column walls 704.  
13 The columns depicted in Figure 7 are square in a cross section taken orthogonal to their  
14 longitudinal axis, in contrast to the columns of Figure 2 which are hexagonal in a cross section  
15 taken orthogonal to their longitudinal axis. It is also of note that in Figure 7, the columns 703 are  
16 arranged as an  $n \times m$  matrix with each row and each column of columns in the matrix being  
17 aligned perfectly adjacent to its neighbor, with no offsetting. Exemplary sizing and spacing of  
18 columns in the invention would include columns which have a cross sectional diameter taken  
19 orthogonal to the longitudinal axis of about 0.9 inch and a column wall thickness of about 0.1  
20 inch at the thinnest point on a column wall. Many other dimensions, shapes and spacing of  
21 columns and column walls may be employed while practicing the inventive concept.

1 Referring to Figure 8, a top view of an alternative cushioning element 801 is depicted.  
2 The cushioning element 801 includes cushioning media 802 which forms column walls 804,  
3 columns 803 and an exterior cushioning element periphery 805. It can be seen that the columns  
4 803 of Figure 8 are arranged in offset fashion with respect to some of the columns to which they  
5 are adjacent. A myriad of column arrangements are possible, from well-organized arrangements  
6 of the columns to a random columnar arrangement. It is preferred that the columns be arranged  
7 so that the total volume of gel cushioning media 802 within the volume of space occupied by the  
8 cushioning element 801 is minimized. This results in a lightweight cushion. To that end, the  
9 columns 803 may be arranged in close proximity to each other in order to minimize the thickness  
10 of the column walls 804. This will result in a lighter cushion and a cushion that will yield to a  
11 greater extent under a cushioned object of a given weight than a similar cushion with thicker  
12 column walls 804.

13 Referring to Figure 9, an alternative cushioning element 901 is depicted with cushioning  
14 media 902, columns 903, column walls 904 and outer periphery 905 of the cushioning element  
15 901 being shown. The columns 902 depicted are round in a cross section taken orthogonal to  
16 their longitudinal axes. The reader should note that it may be desirable to include a container or  
17 side walls which will contain the outer periphery 905 of the cushioning element. For example, in  
18 Figure 9, a rectangular box with interior dimensions just slightly larger than the exterior  
19 dimensions of the cushioning element 901 could be employed. Or, as shown in Figure 1, the side  
20 walls of the cover 204 could be rigid, such as by the use of plastic inserts. The effect of rigid  
21 side walls or a rigid container for a cushioning element is that when a cushioned object is placed



1 on the cushioning element, the cushioning media will not be permitted to bulge outward at the  
2 cushioning element outer periphery. By preventing such outward bulging, greater cushion  
3 stability is achieved and a more direct (i.e. in a direction parallel to the longitudinal axis of a  
4 column, which in most of the figures, such as Figure 3, is assumed to be in the direction of the  
5 Earth's gravity but which may not always be so) movement or descent of the cushioned object  
6 into the cushion is achieved. A direct movement or descent of a cushioned object into the  
7 cushion (i.e. parallel to the longitudinal axes of the columns) is desired because the column walls  
8 are configured to absorb weight and cushion the cushioned object, or, if the load under a  
9 protuberance gets high enough, by buckling of the columns. If a cushioned object travels a  
10 substantial distance sideways in the cushion, the hollow portion of the columns may be  
11 eliminated by opposing column walls collapsing to meet each other rather than either  
12 substantially compressing the cushioning media or by buckling as depicted in Figures 13 and 14.  
13 This would not provide the desired cushioning effect as it would result in collapsed columns  
14 within the cushion (rather than buckled columns), and the cushion would have little more  
15 cushioning effect than a solid block of the cushioning media without the columns.

16 Referring to Figure 10, an alternative embodiment of the invented cushion 1001 is  
17 depicted. The cushion 1001 includes gel cushioning media 1002 in the form of an outer cushion  
18 periphery 1003, and column walls 1004 which form triangular hollow columns 1005. The reader  
19 should note that the columns of the various figures are merely illustrative, and in practice, the  
20 columns could be triangular, rectangular, square, pentagonal, hexagonal, heptagonal, octagonal,  
21 round, oval, n-sided or any other shape in a cross section taken orthogonal to the longitudinal

1 axis of a column. The periphery of the cushioning element may also be triangular, rectangular,  
2 square, pentagonal, hexagonal, heptagonal, octagonal, round, oval, heart-shaped, kidney-shaped,  
3 elliptical, oval, egg-shaped, n-sided or any other shape.

4 Figure 11 depicts a column 1101 of the invention including column walls 1102 and 1103  
5 and column interior 1104. The column 1101 has a longitudinal axis 1105 which is preferred to  
6 be oriented in the invented cushion parallel to the direction of the longitudinal axis of a column  
7 which should be the direction that the cushioned object sinks into the cushion. Thus, the column  
8 top 1106 is at the side of the cushion that contacts the cushioned object, and the column bottom  
9 1107 is at the side of the cushion that typically faces the ground and will rest on some sort of a  
10 base. Another way of describing this with respect to the longitudinal axis of each column is that  
11 the column top is at one end of the longitudinal axis of a column and the column bottom is at the  
12 other end of the longitudinal axis of a column. When an object to be cushioned is placed onto a  
13 cushion which contains many such columns 1101, such as is shown in Figure 3, a depressive  
14 force 1108 is applied to the cushion and to the column 1101 by the cushioned object. Because  
15 the cushion is expected to rest on some type of supporting surface, such as a base, a reaction  
16 force 1109 is provided by the supporting surface. The cushion, including the column 1101,  
17 yields under the weight of the cushioned object. This yielding is a result of compression of the  
18 cushioning media and, if the load under a protruding portion of the cushioned object is high  
19 enough, by buckling or partial buckling of the columns 1101. From Figure 11, it can be seen that  
20 the depicted column 1101 buckles because the flexible cushion walls 1102 and 1103 buckle  
21 outward around the periphery of the column, as depicted by cross-sectional points 1110 and

1 1111. In other words, the column walls buckle radially outward orthogonally from the  
2 longitudinal axis of the column. This permits the column 1101 to decrease in total length along  
3 its longitudinal axis 1108 and thereby conform to the shape of protuberances on a cushioned  
4 object. Since buckled columns carry comparatively little load, this results in a cushion that  
5 avoids pressure peaks on the cushioned object.

6 Figure 12 depicts a column 1201 of the invention including column walls 1202 and 1203  
7 and column interior 1204. The column 1201 has a longitudinal axis 1205 which is preferred to  
8 be oriented in the invented cushion parallel to the direction of movement of a cushioned object  
9 sinking into the cushion. Thus, the column top end 1206 is at the side of the cushion that  
10 contacts the cushioned object, and the column bottom end 1207 is at the side of the cushion that  
11 typically will rest on some sort of a base. When an object to be cushioned is placed against a  
12 cushion which contains numerous columns 1201, such as is shown in Figure 3, a depressive force  
13 1208 is applied to the cushion and to the column 1201 by the cushioned object. Because the  
14 cushion is expected to rest on some type of supporting surface, such as a base, a reaction force  
15 1209 is provided by the supporting surface. The cushion, including the column 1201, yields  
16 under the weight of the cushioned object. This yielding is a result of compression of the  
17 cushioning media and, if the load under a protruding portion of the cushioned object is high  
18 enough, by buckling or partial buckling of the columns. From Figure 12, it can be seen that the  
19 depicted column 1201 buckles because the flexible cushion wall 1202 buckles outward from the  
20 column center or orthogonal away from the longitudinal axis of the column at point 1210, while  
21 cushion wall 1203 buckles inward toward the column center or orthogonal toward the

1 longitudinal axis of the column at points 1211. This buckling action causes the column 1201 to  
2 decrease in total length along its longitudinal axis 1208 and thereby conform to the shape of  
3 protuberances on a cushioned object. Point 1210 is depicted buckling outward (away from the  
4 center of the column) and point 1211 is depicted as buckling inward (toward the center of the  
5 column). Alternatively, both points 1210 and 1211 could buckle inward toward the center of the  
6 column or both could buckle outward. Since buckled columns carry comparatively little load,  
7 this results in a cushion that avoids pressure peaks on the cushioned object. Buckling of a  
8 column permits the column to decrease in total length along its longitudinal axis and thereby  
9 conform to the shape of protuberances on a cushioned object. This results in a cushion that  
10 avoids pressure peaks on the cushioned object. It should be noted by the reader that the columns  
11 1101 and 1201 depicted in Figures 11 and 12 are hollow columns which have interiors  
12 completely open to the atmosphere and which permit air to travel through the columns to  
13 enhance ventilation under the cushioned object. It is also of note that the column 1201 of Figure  
14 12 has column walls 1202 and 1203 that include fenestrations 1210 (which may be holes or  
15 apertures in the column walls) that permit the flow of air between adjacent columns, providing an  
16 enhanced ventilation effect. Fenestrations are also useful for reducing the weight of the  
17 cushioning element. The greater the size and/or number of fenestrations in column walls, the less  
18 the cushion weighs. The fenestrations or holes 1210 in the column walls could be formed by  
19 punching or drilling, or they could be formed during molding of the cushioning element.

20 Figure 13 depicts an alternative column 1301 of the invention including column walls  
21 1302 and 1303 and a column interior 1304. The column 1301 has a longitudinal axis 1305

1 which, in the invented cushion, is preferably oriented parallel to the direction in which the  
2 cushioned object is expected to sink into the cushion. Thus, the column top end 1306 is at the  
3 side of the cushion that contacts the cushioned object, and the column bottom end 1307 is at the  
4 side of the cushion that typically faces some sort of a base. When an object to be cushioned is  
5 placed onto a cushion which contains column 1301, such as is shown in Figure 3, a depressive  
6 force 1308 is applied to the cushion and to the column 1301 by the cushioned object. Because  
7 the cushion is expected to rest on some type of supporting surface, such as a base, a reaction  
8 force 1309 is provided by the supporting surface. The cushion, including the column 1301,  
9 yields under the weight of the cushioned object. This yielding is a result of compression of the  
10 cushioning media and, if the load under a protruding portion of the cushioned object is high  
11 enough, by buckling or partial buckling of the columns. From Figure 13, it can be seen that the  
12 depicted column 1301 buckles because the flexible cushion walls 1302 and 1303 buckle outward  
13 from the column center or orthogonal away from the longitudinal axis 1305 of the column at  
14 points 1311 and 1310. This buckling action allows the column 1301 to decrease in total length  
15 along its longitudinal axis 1305 and thereby conform to the shape of protuberances on a  
16 cushioned object.

17 In the embodiment depicted, the column 1301 is a sealed column containing air or an  
18 inert gas within its interior 1304. Thus, as the column 1301 decreases in length along its  
19 longitudinal axis, the gas within the column interior 1304 tends to support the column top end  
20 1306 and resist the downward movement of the cushioned object. This yields a firmer cushion.  
21 Alternatively, open or closed cell (or other) foam or fluid cushioning media could be provided

1 within the interior of the columns or within some of them in order to increase the firmness of the  
2 cushion.

3 Figure 14 depicts an alternative embodiment of the column of the invention. The column  
4 1401 depicted has column walls 1402 and 1403 and a column interior 1404. The column interior  
5 1404 is open at column top end 1405 and at column bottom end 1406 to permit air to pass  
6 through the column 1401. Column 1401 has walls 1402 and 1403 which are thicker at their  
7 bottom end 1406 than at their top end 1405, imparting cushions which include such columns  
8 with a soft cushioning effect when cushioning an object that sinks into the cushion to only a  
9 shallow depth, but progressively providing firmer cushioning the deeper the cushioned object  
10 sinks. This configuration of column 1401 permits the construction of a cushion which  
11 accommodates cushioned objects of a very wide variety of weight ranges. Alternatively, the  
12 column walls could be thicker at the top than at the bottom, the column walls could be stepped,  
13 or the column walls could have annular or helical grooves in them to facilitate buckling under the  
14 load of a cushioned object. Additionally, the column interior could be of a greater interior  
15 dimension orthogonal to its longitudinal axis at one end than at the other. Or the columns could  
16 be of varying dimension and shape along their longitudinal axes.

17 Figure 15 depicts a cross section of a cushioning element using alternating stepped  
18 columns. The cushioning element 1501 has a plurality of columns 1502 each having a  
19 longitudinal axis 1503, a column top 1504 and a column bottom 1505. The column top 1504 and  
20 column bottom 1505 are open in the embodiment depicted, and the column interior or column  
21 passage 1506 is unrestricted to permit air flow through the column 1502. The column 1502

1 depicted has side walls 1507 and 1508, each of which has three distinct steps 1509, 1510 and  
2 1511. The columns are arranged so that the internal taper of a column due to the step on its walls  
3 is opposite to the taper of the next adjacent column. This type of cushioning element could be  
4 made using a mold similar to that depicted in Figure 4.

5 Figure 16 depicts an alternative embodiment of a cushioning element 1601. The  
6 cushioning element 1601 has a plurality of columns 1602, 1603 and 1604, each having a column  
7 interior 1605, 1606 and 1607, and column walls 1608, 1609, 1610 and 1611. The column walls  
8 are made from cushioning media, such as the preferred soft gel. In the embodiment of the  
9 invented cushioning element 1601 depicted, the cushioning media 1612 has trapped within it a  
10 plurality of gas bubbles 1613, 1614 and 1615. When the preferred soft gel cushioning medium is  
11 used, since the gel is not flowable at the temperatures to which the cushion is expected to be  
12 exposed during use, the bubbles remain trapped within the cushioning medium. The use of  
13 bubbles within the cushioning medium reduces the weight of the cushion and softens the cushion  
14 to a degree which might not otherwise be available. Bubbles may be introduced into the  
15 cushioning medium by injecting air, another appropriate gas, or vapor into the cushioning  
16 medium before manufacturing the cushioning element, by vigorously stirring the heated,  
17 flowable cushioning medium before it is formed into the shape of a cushion, or by utilizing a  
18 cushioning medium of a composition that creates gas or boils at the temperatures to which it is  
19 subjected during the manufacture of a cushioning element. Blowing agents, some of the uses of  
20 which are described in detail below in connection with the disclosure of the preferred gel  
21 material, are also useful for introducing gas bubbles into the cushioning medium. Microspheres,

1 which are also discussed in greater detail below, are also useful for introducing gas pockets into  
2 the cushioning medium.

3 Figure 17 depicts an embodiment of the invented cushioning element which has  
4 cushioning medium, solid exterior walls 1703 and 1704, a plurality of columns 1705 and column  
5 walls 1706 forming the columns. Note that although Figure 17 shows a cushioning element 1701  
6 with solid walls 1703 and 1704, it is possible to make a cushioning element 1701 that has  
7 columns on its outer walls. The cushioning element is disposed within an optional cover 1707.  
8 A container 1708 with relatively stiff or rigid walls 1709 and 1710 of approximately the same  
9 size and shape as the cushioning element walls 1703 and 1704 is shown. The container 1708 has  
10 a bottom or base 1711 on which the cushioning element is expected to rest. The container 1708  
11 walls 1709 and 1710 serve to restrict the outward movement of the cushioning element 1701  
12 when a cushioned object is placed on it. When the preferred soft gel is used as a cushioning  
13 medium, the cushioning element 1701 would tend to be displaced by the object being cushioned  
14 were the side walls 1709 and 1710 of the container 1711 not provided. In lieu of a container, any  
15 type of appropriate restraining means may be used to prevent side displacement of the cushioning  
16 element in response to the deforming force of a cushioned object. For example, individual  
17 plastic plates could be placed against the side walls 1703 and 1704 of the cushioning element  
18 1701. Those plates could be held in place with any appropriate holder, such as the cover 1707.  
19 As another example, an appropriate strap or girdle could be wrapped around all exterior side  
20 walls 1703 and 1704 of the cushioning element 1701. Such a strap or girdle would serve to  
21 restrain the cushioning element 1701 against radial outward displacement in response to a



1 cushioned object resting on the cushioning element.

2       Figure 18 depicts an alternative embodiment of a cushion 1801 that includes a cushioning  
3 element 1802 and a cover 1803. The cushioning element 1802 has side walls 1808 and 1809  
4 about its periphery, the side walls 1808 and 1809 in this embodiment being generally parallel  
5 with the longitudinal axis 1810 of a hollow column 1811 of the cushioning element 1802. A gap  
6 1806 exists between the cover 1803 and the side wall 1809 of the cushioning element. This gap  
7 1806 accommodates the insertion of a stiff or rigid reinforcing side wall support 1804 which may  
8 be made of a suitable material such as plastic, wood, metal or composite material such as resin  
9 and a reinforcing fiber. Similarly, gap 1807 between side wall 1808 and the cover 1803 may  
10 have side wall support 1805 inserted into it. The side wall supports are configured to restrict the  
11 cushioning element from being substantially displaced in an outward or radial direction (a  
12 direction orthogonal to the longitudinal axis of one of the columns of the cushioning element) so  
13 that the cushioning element's columns will buckle to accommodate the shape of a cushioned  
14 object, rather than permitting the cushioning element to squirm out from under the cushioned  
15 object.

16       Figure 19 depicts an alternative embodiment of a cushioning element 1901 including  
17 square columns 1908. The cushioning element has outer side walls 1902 and 1903 about its  
18 periphery. The reader should note that although the outer periphery of the cushioning element in  
19 Figure 19 is depicted as rectangular, the outer periphery could be of any desired configuration,  
20 such as triangular, square, pentagonal, hexagonal, heptagonal, octagonal, any n-sided polygon  
21 shape, round, oval, elliptical, heart-shaped, kidney-shaped, quarter moon shaped, n-sided

1 polygonal where n is an integer, or of any other desired shape. The side walls 1902 and 1903 of  
2 the cushioning element 1901 have a peripheral strap or girdle 1904 about them. The girdle 1904  
3 has reinforcing side walls 1905 and 1906 which reinforce the structural stability of side walls  
4 1902 and 1903 respectively of the cushioning element 1901. The embodiment of the girdle 1904  
5 depicted in Figure 19 has a fastening mechanism 1907 so that it may be fastened about the  
6 periphery of the cushioning element 1901 much as a person puts on a belt. The girdle 1904  
7 serves to confine the cushioning element 1901 so that when a cushioned object is placed on the  
8 cushioning element 1901, the cushioning element will not tend to squirm out from beneath the  
9 girdle 1904. Thus, the cushioning element 1901 will tend to yield and conform to the cushioned  
10 object as needed by having its cushioning medium compress and its columns buckle.

11 Figure 20 depicts an alternative embodiment of a cushioning element 2001. The  
12 cushioning element 2001 includes cushioning medium 2002 such as the preferred gel formed into  
13 column walls 2003 and 2004 to form a column 2005. The column 2005 depicted has a sealed  
14 column top 2006 and a sealed column bottom 2007 in order to contain a column filler 2008. The  
15 column filler 2008 could be open or closed cell foam, any known fluid cushioning medium such  
16 as lubricated spherical objects, or any other desired column filler. The cushioning element 2001  
17 depicted has an advantage of greater firmness compared to similar cushioning elements which  
18 either omit the sealed column top and column bottom or which omit the column filler.

19 Figure 21 depicts an alternative embodiment of a cushioning element 2101 of the  
20 invention. The cushioning element 2101 has cushioning medium 2102 formed into column walls  
21 2103 and 2104. The column walls 2103 and 2104 form a column interior 2105. The column

1 2106 has an open column top 2107 and a closed column bottom 2108. In the embodiment  
2 depicted, the column 2107 has a firmness protrusion 2109 protruding into the column interior  
3 2105 from the column bottom 2108. The firmness protrusion 2109 depicted is wedge or cone  
4 shaped, but a firmness protrusion could be of an desired shape, such as cylindrical, square, or  
5 otherwise in cross section along its longitudinal axis. The purpose of the firmness protrusion  
6 2109 is to provide additional support within a buckled column for the portion of a cushioned  
7 object that is causing the buckling. When a column of this embodiment of the invention buckles,  
8 the cushioning element will readily yield until the cushioned object begins to compress the  
9 firmness protrusion. At that point, further movement of the cushioned object into the cushion is  
10 slowed, as the cushioning medium of the firmness support needs to be compressed or the  
11 firmness support itself needs to be caused to buckle in order to achieve further movement of the  
12 cushioned object into the cushioning medium.

13 Referring now to Figure 22, in another embodiment of the cushion, multiple individual  
14 cushioning elements 2201a, 2201b, 2201c, etc. are provided within a single cushion 2200. In  
15 such embodiments, the cushions of the present invention are positioned side-to-side, with or  
16 without other materials between the individual cushions, and with or without connecting the  
17 individual cushions to one another. For example, sixty-four cushions, each having a thickness of  
18 four inches, and four sides each two inches in length, can be placed in an eight-by-eight  
19 arrangement to form a four inch thick square cushion having sixteen inch sides. Such cushions  
20 may be useful where different cushioning characteristics are desired on different portions of a  
21 cushion. Different cushioning characteristics are achieved through varying the materials and/or

1 configurations of the individual cushions.

2 With reference to Figures 23a, 23b, 23c and 23d, another embodiment of a cushion 2301  
3 according to the present invention is shown. Embodiment 2301 includes a first cushioning  
4 medium 2302 which forms a cover and a second cushioning medium 2303 which fills the cover.  
5 First cushioning medium 2302 is preferably the preferred elastomeric gel material, which is  
6 disclosed in detail below. Preferably, second cushioning medium 2303 is the visco-elastomeric  
7 material that is disclosed in detail below.

8 Embodiment 2301 also includes columns 2304, column walls 2305 and an outer  
9 periphery 2306. Columns 2304 are formed through cover 2302 and lined with cushioning  
10 medium 2302. With reference to Figures 23a and 23b, where two adjacent columns 2304a and  
11 2304b are separated only by a thin column wall 2305a (e.g., a column wall having a thickness of  
12 only about 0.1 inch or less), the column wall is preferably made from cushioning medium 2302.  
13 Where two adjacent columns 2304c and 2304d are separated by a thicker column wall 2305c, the  
14 column wall preferably includes a cover 2302 of the first cushioning medium and is filled with  
15 second cushioning medium 2303.

16 The use of multiple cushioning media in cushion 2301 facilitates tailoring of the rebound,  
17 pressure absorption, and flow characteristics of the cushion. Compressibility of cushion 2301  
18 also depends upon the amount of spacing between columns and the formulations of the first  
19 second cushioning media 2302 and 2303, respectively.

20 Figures 24a and 24b illustrate another embodiment of the cushioning element 2401  
21 according to the present invention. Referring to Figure 24b, embodiment 2401 includes a

1 cushioning medium 2402, a coating 2403 adhered to the cushioning medium, columns 2404,  
2 column walls 2405 that separate the columns, and an outer periphery 2406. Preferably,  
3 cushioning medium 2402 of embodiment 2401 is tacky, which facilitates adhesion of coating  
4 2403 thereto. A preferred cushioning medium 2402 for use in embodiment 2401 is the preferred  
5 visco-elastomeric gel material, which is disclosed in detail below. Coating 2403 is preferably a  
6 particulate material, including without limitation lint, short fabric threads, talc, ground cork,  
7 microspheres, and others. However, coating 2403 may be made from any material that will  
8 form a thin, pliable layer over cushioning medium 2402, including but not limited to fabrics,  
9 stretchable fabrics, long fibers, papers, films, and others.

10       Figures 25a, 25b, 25c, 25d, 25e and 25f show another embodiment of a cushioning  
11 element 2501 according to the present invention. Embodiment 2501 includes cushioning  
12 medium 2502, a first set of columns 2503 which are oriented along a first axis x, a second set of  
13 columns 2504 which are oriented along a second axis y, a third set of columns 2505 which are  
14 oriented along a third axis z, column walls 2506 located between the columns, and an outer  
15 periphery 2507. Preferably, axis x is perpendicular to both axis y and axis z and axis y is  
16 perpendicular to axis z. Columns 2503 and 2504, 2503 and 2505, and/or 2504 and 2505 may  
17 intersect each other. Figures 25a, 25b and 25c illustrate a cushion 2501a wherein columns 2503a  
18 intersect columns 2504 and columns 2503b intersect columns 2505. Figures 25d, 25e and 25f  
19 depict a cushion 2501b wherein each of columns 2503 intersect both columns 2504 and columns  
20 2505. Alternatively, none of the columns may intersect any other columns. Other variations of  
21 intersection and/or non-intersecting columns are also within the scope of the present invention.

1           The spacing and pattern with which each set of columns is positioned determines the total  
2 volume of cushioning medium 2502 within the volume of space occupied by the cushioning  
3 element 2501. As the volume of cushioning medium 2502 within the volume of space occupied  
4 by the cushioning element 2501 decreases, the cushion becomes lighter and easier to compress.  
5 Thus, the spacing and pattern of each set of columns may be varied to provide a cushion of  
6 desired weight and compressibility. Cushioning elements which have only two sets of columns  
7 or more than three sets of columns are also within the scope of embodiment 2501.

8           With reference to Figure 26, another embodiment of cushioning element 2601 is shown  
9 which includes a first set of columns 2603 which are oriented along a first axis x, a second set of  
10 columns 2604 which are oriented along a second axis y, and a third set of columns 2605 which  
11 are oriented along a third axis z. As can be seen in Figure 26, columns 2603, 2604 and 2605 are  
12 preferably thin. Column walls 2606, which are made from a cushioning medium 2602, surround  
13 each of the columns. The cushion 2601 shape is defined in part by an outer periphery 2607.

14 Preferably, axis x is perpendicular to both axis y and axis z and axis y is perpendicular to axis z.  
15 Similar to the cushion of embodiment 2501, columns 2603, 2604 and 2605 may or may not  
16 intersect any other columns. Likewise, the spacing between adjacent columns and the  
17 arrangement of each of the columns determine the total volume of cushioning medium 2602  
18 within the volume of space occupied by the cushioning element 2601. As the volume of  
19 cushioning medium 2602 within the volume of space occupied by the cushioning element 2601  
20 decreases, the cushion becomes lighter and easier to compress. Thus, the spacing and  
21 arrangement of columns may be varied to provide a cushion of desired weight and

1 compressibility. Cushions with only two sets of columns or more than three sets of columns are  
2 also within the scope of embodiment 2601.

3 Referring now to Figures 27a, 27b and 27c, another embodiment of a cushioning element  
4 2701 according to the present invention is shown. Embodiment 2701 includes cushioning  
5 medium 2702, a first set of columns 2703 which are oriented along a first axis x, a second set of  
6 columns 2704 which are oriented along a second axis y, a third set of columns 2705 which are  
7 oriented along a third axis z, column walls 2706 located between the columns, cavities 2707  
8 formed within the column walls and an outer periphery 2708. Preferably, axis x is perpendicular  
9 to both axis y and axis z and axis y is perpendicular to axis z. Columns 2703 and 2704, 2703 and  
10 2705, and/or 2704 and 2705 may intersect each other, as in embodiments 2501 and 2601.

11 Alternatively, none of the columns may intersect any other column. The spacing and pattern  
12 with which each set of columns is positioned and the number of cavities 2706 formed within the  
13 column walls 2707 determine the total volume of cushioning medium 2702 within the volume of  
14 space occupied by the cushioning element 2701. As the volume of cushioning medium 2702  
15 within the volume of space occupied by the cushioning element 2701 decreases, the cushion  
16 becomes lighter and easier to compress. Thus, the spacing and pattern of each set of columns  
17 may be varied to provide a cushion of desired weight and compressibility. Similarly, the size  
18 and spacing of the cavities 2706 within the column walls 2707 may also be varied to provide a  
19 cushion of desired weight and compressibility. Cushioning elements which have only two sets of  
20 columns are also within the scope of embodiment 2701.

21 Figure 28 illustrates yet another embodiment of a cushioning element 2801 of the present

1 invention, which has a contoured upper surface. The cushion 2801 shown in Figure 28 has  
2 columns 2803 and 2804 of different heights and column walls 2805 and 2806 of different  
3 heights. However, a contoured cushion according to embodiment 2801 could include columns  
4 and column walls having any number of different heights. Embodiment 2801 also includes  
5 cushioning medium 2802 and an outer periphery 2807. The variability of column and column  
6 wall height in embodiment 2801 imparts the cushion with areas having different compressibility  
7 and firmness characteristics.

8 As seen in Figure 28, cushion 2801 has two distinct levels of columns. The adjacent  
9 longer columns 2803 are grouped together, referred to as a set of isolated columns 2808. The  
10 shorter columns 2804, which are located between sets 2808, tie cushion 2801 together and form a  
11 cushion base 2809.

12 As an example of the use of cushion 2801, a cushioned object which comes into contact  
13 with the top surface thereof will first compress columns 2803, causing the column walls 2805 to  
14 buckle. The free area between isolated column sets 2808 enhances the bucklability of columns  
15 2803. In other words, columns 2803 buckle more easily than would columns of the same size,  
16 separated by column walls of the same thickness and made from the same material in a cushion  
17 having columns of only one general height. If the load of the cushioned object causes complete  
18 buckling of columns 2803, columns 2804, which have a greater resistance to buckling than the  
19 long columns, provide a secondary cushioning effect, which is more like that of a cushion with  
20 columns of one general length.

21 Referring now to Figure 29, a cushion 2901 is shown which includes a cushioning



1 medium 2902, columns 2903, column walls 2904, and an outer periphery 2905. Cushioning  
2 medium includes a plurality of cells 2906a, 2906b, 2906c, etc. which are filled with gas or  
3 another cushioning medium. The cushion 2901 depicted in Figure 29 has open cells 2906.  
4 Alternatively, cushion 2901 may have only closed cells or a combination of open and closed  
5 cells. Cells 2906a, 2906b, 2906c, etc. may be of any size and may be dispersed throughout  
6 cushioning medium at any density or concentration that will provide the desired cushioning and  
7 weight characteristics.

8 Referring now to Figures 30a and 30b, alternative embodiments of the cushions 3001 and  
9 3001' of the present invention which have light weight column walls 3004 and 3004',  
10 respectively, are shown. Cushions 3001 and 3001' also include a cushioning medium 3002 and  
11 3002', columns 3003 and 3003' and an outer periphery 3005 and 3005', respectively. Column  
12 walls 3004 and 3004' each include a matrix 3006 and 3006', respectively, within which are  
13 located several voids 3007a, 3007b, 3007c, etc. and 3007a', 3007b', 3007c', etc. and 3008a,  
14 3008b, etc., respectively. Matrix 3006 is made from cushioning medium 3002, 3002'. Voids  
15 3007, 3007', 3008 are hollow areas formed within matrix 3006 which lighten column walls 3004,  
16 3004'. Preferably, voids 3007, 3007' are filled with gas or any other substance which has a  
17 density (i.e., specific gravity) less than that of cushioning medium 3002, 3002'. More preferably,  
18 voids 3007, 3007' are open celled (i.e., continuous with the outer surface of cushion 3001, 3001'  
19 and exposed to the atmosphere).

20 Figure 30a shows cushion 3001, the column walls 3004 of which include a matrix 3006  
21 which forms voids 3007a, 3007b, 3007c, etc. having a multi-sided irregular shape. Column walls

1 which have matrices and pits of other configurations are also within the scope of the cushioning  
2 elements of the present invention. Embodiment 3001 is preferably formed by removal or  
3 destruction of volume occupying objects which are dispersed throughout the cushioning medium  
4 as cushion 3001 is formed.

5 Figure 30b shows cushion 3001 having a matrix 3006 formed from randomly oriented  
6 short tubes 3009a, 3009b, 3009c, etc. which forms voids 3007 and 3008. Voids 3007a, 3007b',  
7 3007c', etc. are formed within short tubes 3009a, 3009b, 3009c, etc. and are generally cylindrical  
8 in shape. Matrix 3006' also includes irregularly shaped secondary voids 3008a, 3008b, 3008c,  
9 etc. which are formed by the exterior surfaces of tubes 3009 between adjacent tubes.

10 It is contemplated in the invention that the hollow portion of the column will typically be  
11 of uniform cross section throughout its length, but this is not necessary for all embodiments of  
12 the invention. For example, in a column having a circular cross section orthogonal to its  
13 longitudinal axis, the diameter of the circle could increase along its length, and adjacent columns  
14 could correspondingly decrease along their length (i.e. the columns would be formed as opposing  
15 cones). As another example, the column walls could all thicken from one cushion surface to  
16 another to facilitate the use of tapered cores (which create the hollow portion of the columns) in  
17 the manufacturing tool, which tapering facilitates the removal of the cores from the gel.

18 It is also preferred that the columns of the preferred cushioning element be open at their  
19 top and bottom. However, the columns can be bonded to or integral with a face sheet on the top  
20 or bottom or both, over all or a portion of the cushion. Or the columns can be interrupted by a  
21 sheet of gel or other material at their midsection which is like a face sheet except that it cuts

1 through the interior of a cushioning element.

2 In the preferred embodiment of the cushioning element the column walls are not  
3 perforated. However, perforated walls and/or face sheets are within the scope of this invention.  
4 The perforation size and density can be varied by design to control column stiffness, buckling  
5 resistance, and weight, as well as to enhance air circulation.

6 It is also preferred that the wall thickness of the columns be approximately equal  
7 throughout the cushioning element for uniformity, but in special applications of the invented  
8 cushion, wall thickness may be varied to facilitate manufacturing or to account for differing  
9 expected weight loads across the cushion or for other reasons.

10 Typical cushions in the art are ordinarily one piece, but the invented cushion can be  
11 constructed from more than one discontinuous cushioning element of the invention. For  
12 example, three one-inch thick cushions of this invention can be stacked to make a three-inch  
13 thick cushion of this invention, with or without other materials between the layers, and with or  
14 without connecting the three layers to one another.

15 The cushioning element of this invention can be used alone or with a cover. A cover can  
16 be desirable when used to cushion a human body to mask the small pressure peaks at the edges of  
17 the column walls. This is not necessary if the gel used is soft enough to eliminate these effects,  
18 but may be desirable if firmer gels are used. Covers can also be desirable to keep the gel (which  
19 can tend to be sticky) clean. If used, a cover should be pliable or stretchable so as not to overly  
20 reduce the gross cushioning effects of the columns compressing and/or buckling. The preferred  
21 cover would also permit air to pass through it to facilitate air circulation under the cushioned

1 object.

2 While it is envisioned that the immediate application of the invented cushion is to  
3 cushion human beings (e.g., seat cushions, mattresses, wheelchairs cushions, stadium seats,  
4 operating table pads, etc.), Applicant also anticipates that other objects, including without  
5 limitation, animals (e.g. between a saddle and a horse), manufactured products (e.g., padding  
6 between a manufactured product and a shipping container), and other objects may also be  
7 efficiently cushioned using the invention.

8 Preferably, the columns in the invented cushion are oriented with their longitudinal axis  
9 generally parallel to the direction of gravity so that they will buckle under load from a cushioned  
10 object rather than collapse from side pressure. It is also preferred that some type of wall or  
11 reinforcement be provided about the periphery of the cushioning element in order to add stability  
12 to the cushioning element and in order to ensure that the buckling occurs in order to decrease  
13 column length under a cushioned object.

14 The invented cushioning element may be described as a gelatinous elastomeric or  
15 gelatinous visco-elastomeric material (i.e. gel) configured as laterally connected hollow vertical  
16 columns which elastically sustain a load up to a limit, and then buckle beyond that limit. This  
17 produces localized buckling in a cushioning element beneath a cushioned object depending upon  
18 the force placed upon the cushioning element in a particular location. As a result, protruding  
19 portions of the cushioned object can protrude into the cushion without being subjected to  
20 pressure peaks. As a result, the cushioning element distributes its supportive pressure evenly  
21 across the contact area of the cushioned object. This also maximizes the percentage of the

1 surface area of the cushioned object that is in contact with the cushion.

2 In the preferred embodiments, each individual column wall can buckle, markedly  
3 reducing the load carried by that column and causing each column to be able to conform to  
4 protuberances of the cushioned object. Buckling may be described as the localized crumpling of  
5 a portion of a column, or the change in primary loading of a portion of a column from  
6 compression to bending. In designing structural columns, such as concrete or steel columns for  
7 buildings or bridges, the designer seeks to avoid buckling because once a column has buckled, it  
8 carries far less load than when not buckled. In the columns of this cushion, however, buckling  
9 works to advantage in accomplishing the objects of the invention. The most protruding parts of  
10 the cushioned object cause the load on the columns beneath those protruding parts to have a  
11 higher than average load as the object initially sinks into the cushion. This higher load causes  
12 the column walls immediately beneath the protruding portion of the cushioned object to buckle,  
13 which markedly reduces the load on the protruding portion. The surrounding columns, which  
14 have not exceeded the buckling threshold, take up the load which is no longer carried by the  
15 column(s) beneath the most protruding portion of the cushioned object.

16 As an example of the desirability of the buckling provided by the cushioning element of  
17 the invention, consider the dynamics of a seat cushion. The area of a seated person which  
18 experiences the highest level of discomfort when seated without a cushion (such as on a wooden  
19 bench) or on a foam cushion is the tissue that is compressed beneath the most protruding bones  
20 (typically the ischial tuberosities). When the invented cushioning element is employed, the area  
21 beneath the protruding portions will have columns that buckle, but the remainder of the

1 cushioning element should have columns (which are beneath the broad, fleshy non-bony portion  
2 of the person's posterior) which will withstand the load placed on them and not buckle. Since the  
3 broad fleshy area over which the pressure is substantially equal is approximately 95% of the  
4 portion of the person subjected to sitting pressure, and the area beneath the ischial tuberosity is  
5 subjected to less than average pressure due to the locally buckled gel columns (in approximately  
6 5% of that area), the person is well supported and the cushion is very comfortable to sit on.

As another example, the cushioning element of the invention is useful in a bed mattress.  
7 The shoulders and hips of a person lying on his/her side would buckle the columns in the  
8 cushioning element beneath them, allowing the load to be picked up in the less protruding areas  
9 of the person's body such as the legs and abdomen. A major problem in prior art mattress  
10 cushions is that the shoulders and hips experience too much pressure and the back is unsupported  
11 because the abdomen receives too little pressure. The cushion of this invention offers a solution  
12 to this problem by tending to equalize the pressure load through local buckling under protruding  
13 body parts.  
14

15 The square columns of Figures 7 or 8 in the invented cushion are believed by Applicant  
16 to have the best balance between lateral stability (resistance to collapse from side loads) and light  
17 weight (which also corresponds to good air circulation and low thermal transfer). Some other  
18 types of columns, such those depicted in the other figures or mentioned elsewhere herein, have  
19 more cushioning media (typically gel) per cubic inch of cushion for a given level of cushioning  
20 support. Thus, the resulting cushions are heavier and have a higher rate of thermal transfer.  
21 They are also more costly to manufacture due to the increased amount of cushioning media

1 required. However, columns with oval, circular or triangular cross sections are preferred for  
2 some cushioning applications because they have a greater degree of lateral stability than square  
3 or honeycomb columns since triangles form a braced structure and circles and ovals form  
4 structurally sound arches when considered from a lateral perspective. Honeycomb columns such  
5 as those shown in Figures 2, 4, 5, 7, 8, 9 and 10 generally have the least gel per cubic inch of  
6 cushion for a given level of support, but have little lateral stability. However, they can be the  
7 preferred embodiment in any cushioning application which has need for lightest weight and does  
8 not require substantial lateral stability.

9 The cushions of this invention differ from prior art gel cushions in that, while prior art gel  
10 cushions come in a variety of shapes, many are essentially a solid mass. When a cushioned  
11 object attempts to sink into a prior art gel cushion, the cushion either will not allow the sinking in  
12 because the non-contact portions of the cushion are constrained from expanding, or the cushion  
13 expands undesirably by pushing gel away from the most protruding parts of the cushioned object  
14 in a manner which tends to increase the reactive force exerted by the gel against areas of the  
15 cushioned object which surround the protrusions. In the cushion of this invention, the gel has  
16 enough hollow space to allow sinking in without expanding the borders of the cushion, so the  
17 problem is alleviated.

18 Another problem with many prior art gel cushions is their weight. For example, a  
19 wheelchair cushion made of prior art gel with dimensions of 18" x 16" x 3.5" would weigh 35-40  
20 pounds, which is unacceptable to many wheelchair users. A cushion according to this invention  
21 having the same dimensions would weigh approximately seven pounds or less. To be an

1 acceptable weight for wheelchairs, a typical prior art wheelchair gel cushion is made only 1"  
2 thick. To prevent bottoming out through such a thin cushion, the makers increase the rigidity of  
3 the gel, which decreases the gel's semi-hydrostatic characteristics, ruining the gel's ability to  
4 equalize pressure. Thus, many thin gel cushions relieve pressure no better than a foam cushion.  
5 The cushion of this invention can be the preferred full 3.5 inches thick needed to allow sinking in  
6 for a human user which is in turn needed to equalize pressure and increase the surface area under  
7 pressure, while still being light weight.

8 The cushions of this invention differ from prior art honeycomb cushions in part in that gel  
9 is used instead of thermoplastic film or thermoplastic elastomer film. Also, a comparatively  
10 thick gel is used for the walls of the columns, as compared to very thin films made of  
11 comparatively much more rigid thermoplastic film or thermoplastic elastomer film. If thick  
12 walls were used in prior art honeycomb cushions, the rigidity of available thermoplastics and  
13 available thermoplastic elastomers would cause the cushion to be far too stiff for typical  
14 applications. Also, the use of comparatively hard, thin walls puts the cushioned object at  
15 increased risk. When the load on a prior art honeycomb cushion exceeds the load carrying  
16 capability of virtually all of the columns (i.e., they all buckle), the cushioned object bottoms out  
17 onto a relatively hard, rigid, thin pile of thermoplastic film layers. In that condition, the  
18 cushioned object is subjected to pressures similar to the pressures it would experience with no  
19 cushion at all. The cushioned object is thus at risk of damaging pressures on its most protruding  
20 portions.

21 In comparison, if the same bottoming out occurs on the cushion of this invention, the



1 most protruding portions of the cushioned object would be pressed into a pile of relatively thick,  
2 soft gel layers, which would add up to typically 20% of the original thickness of the cushion.  
3 Thus, the risk of bottoming out is substantially lowered.

4 Another difference between prior art thermoplastic honeycomb cushions and the cushion  
5 of this invention is that the configuration of the invented cushion is not limited to honeycomb  
6 columns, but can take advantage of the varying properties offered by columns of virtually any  
7 cross sectional shape. The prior art thermoplastic honeycomb cushions are so laterally unstable  
8 that at least one face sheet must be bonded across the open cells. This restricts the air circulation,  
9 which is only somewhat restored if small perforations are made in the face sheet or cells. While  
10 face sheets and perforations are an option on the cushions of this invention, the alternative cross  
11 sectional shapes of the columns (e.g., squares or triangles) make face sheets unnecessary due to  
12 increased lateral stability and thus perforations are unnecessary since both ends of the preferred  
13 configuration of the column are open to the atmosphere.

14 The maximum thickness of the walls of the columns of the cushion of this invention  
15 should be such that the bulk density of the cushion is less than 50% of the bulk density if the  
16 cushion were completely solid gel. Thus, at least 50% of the volume of space occupied by the  
17 invented cushioning element is occupied by a gas such as air and the remainder is occupied by  
18 gel. The minimum thickness of the walls of the columns is controlled by three factors: (1)  
19 manufacturability; (2) the amount of gel needed for protection of the cushioned object in the  
20 event of all columns buckling; and (3) the ability to support the cushioned object without  
21 buckling the majority of the columns. The preferred thickness would be such that the columns

1 under the most protruding parts of the cushioned object are buckled, and the remaining columns  
2 are compressed in proportion to the degree of protrusion of the cushioned object immediately  
3 above them but are not buckled.

#### 4 **B. Cushion Materials**

5 It is preferred that the cushioning media used to manufacture the invented cushioning  
6 element be a soft gel. This assures that the invented cushion will yield under a cushioned object  
7 by having buckling columns and by the cushioning medium itself compressing under the weight  
8 of the cushioned object. The soft gel will provide additional cushioning and will accommodate  
9 uneven surfaces of the cushioned object. Nevertheless, firmer gels are also useful in the  
10 cushioning element of the invention, provided that the gel is soft enough to provide acceptable  
11 cushioning for the object in the event that all of the columns buckle. Since, with a given type of  
12 gel, there is typically a correlation between softness and Young's modulus (stiffness)(i.e., a  
13 softer gel is less stiff), and since there is a correlation between Young's modulus and the load  
14 carrying capability of a column before buckling, there is typically a need for firmer gels in  
15 cushions which will carry a higher load. However, there are other alternatives for increasing a  
16 cushion's load carrying capability, such as increasing the column wall thickness, so that the  
17 softness of the gel can be selected for its cushioning characteristics and not solely for its load  
18 bearing characteristics, particularly in cases where cushion weight is not a factor. Any gelatinous  
19 elastomer or gelatinous visco-elastomer with a hardness on the Shore A scale of less than about  
20 15 is useful in the cushioning element of the present invention. Preferably, the cushioning  
21 medium has a Shore A hardness of about 3 or less. More preferred are materials which have a

1 hardness of less than about 800 gram bloom. Such materials are too soft to measure on the Shore  
2 A scale. Gram Bloom is defined as the gram weight required to depress a gel a distance of four  
3 millimeters (4 mm) with a piston having a cross-sectional area of one square centimeter (1 cm<sup>2</sup>)  
4 at a temperature of about 23°C. The preferred gel is cohesive at the normal useable temperatures  
5 of a cushioning element. The preferred gel will not escape from the cushioning element if the  
6 cushioning element is punctured. The preferred gel has shape memory so that it tends to return  
7 to its original shape after deformation.

8 The cushioning media or preferred gel must also be strong enough to withstand the loads  
9 and deformations that are ordinarily expected during the use of a cushion. For a given type of  
10 gel, there is typically a correlation between softness and strength (i.e., softer gels are not as  
11 strong as harder gels).

12 Because of their high strength even in soft formulations, their low cost, their ease of  
13 manufacture, the variety of manufacturing methods which can be used, and the wide range of  
14 Young's modulus which can be formulated while maintaining the hydrostatic characteristics of a  
15 gel, the gel formulations which follow are the most preferred gels to be used in the cushions of  
16 this invention.

17 Applicant believes that the reader might benefit from a general background discussion of  
18 the chemistry underlying the preferred gels prior to reading about the preferred formulations of  
19 the preferred gels.

## 20 **1. Chemistry of Plasticizer-Extended Elastomers**

21 A basic discussion of the chemical principles underlying the characteristics and

1 performance of plasticizer-extended elastomers is provided below to orient the reader for the  
2 later discussion of the particular chemical aspects of the preferred material for use in the cushions  
3 of the present invention.

4 The preferred gel cushioning medium is a composition primarily of triblock copolymers  
5 and plasticizers, both of which are commonly referred to as hydrocarbons. Hydrocarbons are  
6 elements which are made up mainly of Carbon (C) and Hydrogen (H) atoms. Examples of  
7 hydrocarbons include gasoline, oil, plastic and other petroleum derivatives.

8 Referring to Figure 31a, it can be seen that a carbon atom 3110 typically has four  
9 covalent bonding sites "•". Figure 31b shows a hydrogen atom 3112, which has only one  
10 covalent bonding site •. With reference to Figure 31c, which represents a four-carbon molecule  
11 called butane, a "covalent" bond, represented at 3116 as "—", is basically a very strong attraction  
12 between adjacent atoms. More specifically, a covalent bond is the linkage of two atoms by the  
13 sharing of two electrons, one contributed by each of the atoms. For example, the first carbon  
14 atom 3118 of a butane molecule 3114 shares an electron with each of three hydrogen atoms  
15 3120, 3122 and 3124, represented as covalent bonds 3121, 3123 and 3125, respectively,  
16 accounting for three of carbon atom 3118's available electrons. The final electron is shared with  
17 the second carbon atom 3126, forming covalent bond 3127. When atoms are covalently bound to  
18 one another, the atom-to-atom covalent bond combination makes up a molecule such as butane  
19 3114. An understanding of hydrocarbons, the atoms that make hydrocarbons and the bonds that  
20 connect those atoms is important because it provides a basis for understanding the structure and  
21 interaction of each of the components of the preferred gel material.

As mentioned above, the preferred gel cushioning material utilizes triblock copolymers. With reference to Figures 32a and 32b, a triblock copolymer is shown. Triblock copolymers 3210 are so named because they each have three blocks—two endblocks 3212 and 3214 and a midblock 3216. If it were possible to grasp the ends of a triblock copolymer molecule and stretch them apart, each triblock copolymer would have a string-like appearance (as in Figure 32a), with an endblock being located at each end and the midblock between the two endblocks.

Figure 33a depicts the preferred endblocks of the copolymer most preferred for use in the preferred gel material, which are known as monoalkenylarene polymers 3310. Breaking the term “monoalkenylarene” into its component parts is helpful in understanding the structure and function of the endblocks. “Aryl” refers to what is known as an aromatic ring bonded to another hydrocarbon group. Referring now to Figure 33b, benzene 3312, one type of aromatic ring, is made up of six carbon molecules 3314, 3316, 3318, 3320, 3322 and 3324 bound together in a ring-like formation. Due to the ring structure, each of the carbon atoms is bound to two adjacent carbon atoms. This is possible because each carbon atom has four bonding sites. In addition, each carbon atom C of a benzene molecule is bound to only one hydrogen atom H. The remaining bonding site on each carbon atom C is used up in a double covalent bond 3326, 3327, which is referred to as a double bond. Because each carbon atom has only four bonding sites, double bonding in an aromatic ring occurs between a first carbon and only one of the two adjacent carbons. Thus, single bonds 3116 and double bonds 3326 alternate around the benzene molecule 3312. With reference to Figure 33c, in an aryl group 3328, one of the carbons 3330 is not bound to a hydrogen atom, which frees up a bonding site R for the aryl group to bond to an

1 atom or group other than a hydrogen atom.

2 Turning now to Figure 33d, “alkenyl” 3332 refers to a hydrocarbon group made up of  
3 only carbon and hydrogen atoms, wherein at least one of the carbon-to-carbon bonds is a double  
4 bond 3334 and the hydrocarbon group is connected to another group of atoms R', where R'  
5 represents the remainder of the hydrocarbon molecule and can include a single hydrogen atom.  
6 Specifically, the “en” signifies that a double bond is present between at least one pair of carbons.  
7 The “yl” means that the hydrocarbon is attached to another group of atoms. For example, Figure  
8 33e shows a two carbon group having a double bond between the carbons, which is called  
9 ethenyl 3336. Similarly, Figure 3f illustrates a three carbon group having a double bond between  
10 two of the carbons, which is called propenyl 3338. Referring again to Figure 33a, in a  
11 monoalkenylarene such as styrene, a carbon 3340 with a free bonding site of an alkenyl group  
12 3332 is bonded to the aryl group 3328 at carbon atom 3330, which also has a free bonding site.  
13 In reference to Figure 33c, aryl group 3328 is part of a monoalkenylarene molecule when R is an  
14 alkenyl group. The “mono” of monoalkenylarene explains that only one alkenyl group is bonded  
15 to the aryl group.

16 The monoalkenylarene end blocks of a triblock copolymer are polymerized.  
17 Polymerization is the process whereby monomers are connected in a chain-like fashion to form a  
18 polymer. Figure 34a depicts a polymer 3410, which is basically a large chain-like molecule  
19 formed from many repeating smaller molecules, called monomers, M1, M2, M3, etc., that are  
20 bonded together. P and P' represent the ends of the polymer, which are also made up of  
21 monomers Figure 34b illustrates a monoalkenylarene end block polymer 3414, which is a chain

1 of monoalkenylarene molecules 3416a, 3416b, 3416c, etc. The chain of Figure 34b is spiral, or  
2 helical, in shape due to the bonding angles between styrene molecules. P represents an extension  
3 of the endblock polymer helix in one direction, while P' represents an extension of the endblock  
4 polymer helix in the opposite direction.

5 As Figure 34c shows, monoalkenylarene molecules are attracted to one another by a force  
6 that is weaker than covalent bonding. The primary weak attraction between monoalkenylarene  
7 molecules is known as hydrophobic attraction. An example of hydrophobic attraction is the  
8 attraction of oil droplets to each other when dispersed in water. Therefore, in its natural, relaxed  
9 state at room temperature, a monoalkenylarene polymer resembles a mass of entangled string  
10 3414, as depicted in Figure 34d. The attraction of monoalkenylarene molecules to one another  
11 creates a tendency for the endblocks to remain in an entangled state. Similarly, different  
12 monoalkenylarene polymers are attracted to each other. The importance of this phenomenon will  
13 become apparent later in this discussion.

14 Like the end blocks of a triblock copolymer, the midblock is also a polymer. The  
15 preferred triblock copolymer for use in the elastomer component of the preferred cushioning  
16 medium includes is an aliphatic hydrocarbon midblock polymer. Traditionally, "aliphatic"  
17 meant that a hydrocarbon was "fat like" in its chemical behavior. Referring to Figures 35a  
18 through 35c, which, for simplicity, do not show the hydrogen atoms, an "aliphatic compound" is  
19 now defined as a hydrocarbon compound which reacts like an alkane 3510 (a hydrocarbon  
20 molecule having only single bonds between the carbon atoms), an alkene 3512 (a hydrocarbon  
21 molecule wherein at least one of the carbon-to-carbon bonds is a double bond) 3514, an alkyne (a

1 hydrocarbon molecule having a triple covalent bond 3515 between at least one pair of carbon  
2 atoms), or a derivative of one or a combination of the above.

3 Referring now to Figure 35d, which omits the bound hydrogen atoms for simplicity,  
4 aliphatic hydrocarbons known as conjugated dienes 3516 are depicted. These are the preferred  
5 midblock monomers used in the triblock copolymers of the preferred gel material for use in the  
6 present invention. A “diene” is a hydrocarbon molecule having two (“di”) double bonds (“ene”).  
7 “Conjugated” means that the double bonds 3518 and 3520 are separated by only one single  
8 carbon-to-carbon bond 3522. In comparison, Figure 35e shows a hydrocarbon molecule having  
9 two double carbon-to-carbon bonds that are separated by two or more single bonds, 3530, 3532,  
10 etc., which is referred to as an “isolated diene” 3524. When double bonds are conjugated, they  
11 interact with each other, providing greater stability to a hydrocarbon molecule than would the  
12 two double bonds of an isolated diene.

13 Figures 36a through 36d illustrate examples of various monomers useful in the midblock  
14 of the triblock copolymers preferred for use in the elastomer component of the preferred gel  
15 cushioning medium, including molecules (monomers) such as ethylene-butylene (EB) 3612,  
16 ethylene-propylene (EP) 3614, butadiene (B) 3616 (either hydrogenated or non-hydrogenated)  
17 and isoprene (I) 3618 (either hydrogenated or non-hydrogenated). The different structures of  
18 these molecules provide them with different physical characteristics, such as differing strengths  
19 of covalent bonds between adjacent monomers. The various structures of monomer molecules  
20 also provides for different types of interaction between distant monomers on the same chain  
21 (e.g., when the midblock chain folds back on itself, distant monomers may be attracted to one



1 another by a force weaker than covalent bonding, such as hydrophobic interaction, hydrophilic  
2 interaction, polar forces or Vander Waals forces).

3 Referring to Figures 36a and 36b, x, y and n each represent an integral number of each  
4 bracketed unit: "x" is the number of repeating ethylene ( $\text{—CH}_2\text{—CH}_2\text{—}$ ) units, "y" is the  
5 number of repeating butylene (in Figure 36a) or propylene (in Figure 36b) units, and "n" is the  
6 number of repeating poly(ethylene/butylene) units. Numerous configurations are possible.

7 As shown in Figures 37a through 37d, the midblock may contain (i) only one type of  
8 monomer, EB, EP, B or I or, as Figures 37e and 37f illustrate, (ii) a combination of monomer  
9 types EB and EP or B and I, providing for wide variability in the physical characteristics of  
10 different midblocks made from different types or combination of types of monomers. The  
11 interaction of physical characteristics of each molecule (monomer and block) determines the  
12 physical characteristics of the tangible, visible material. In other words, the type or types of  
13 monomer molecules which make up the midblock polymer play a role in determining various  
14 characteristics of the material of which the midblock is a part.

15 Attributes such as strength, elongation, elasticity or visco-elasticity, softness, tackiness  
16 and plasticizer retention are, in part, determined by the type or types of midblock monomers. For  
17 example, referring again to Figure 37a, the midblock polymer 3216 of a triblock copolymer-  
18 containing material may be made up primarily or solely of ethylene-butylene monomers EB,  
19 which contribute to that material's physical character. With reference to Figure 37e, in  
20 comparison to the material having a midblock made up solely of EB, a similar triblock-  
21 containing material, wherein the midblock polymer 3216 of the triblocks are made up of a

1 combination of butadiene B and isoprene I monomers, may have greatly increased strength and  
2 elongation, similar elasticity or visco-elasticity and softness, reduced tackiness and reduced  
3 plasticizer bleed.

4 The monomer units of the midblock have an affinity for each other. However, the  
5 hydrophobic attraction of the midblock monomers for each other is much weaker than the non-  
6 covalent attraction of the end block monomers for one another.

7 Referring now to Figure 38a, which shows a polystyrene-poly(butadiene + isoprene)-  
8 polystyrene triblock copolymer, in a complete triblock copolymer 3810, each end 3812 and 3814  
9 of midblock chain 3216 is covalently bound to an end block 3212 and 3214. P and P'' represent  
10 the remainder of the endblock polymers 3212 and 3214 respectively. P' represents the central  
11 portion of midblock polymer 3216. Many billions of triblock copolymers combine to form a  
12 tangible material. The triblock copolymers are held together by the high affinity (i.e.,  
13 hydrophobic attraction) that monoalkenylarene molecules have for one another. In other words,  
14 as Figure 38b illustrates, the endblocks of each triblock copolymer molecule, each of which  
15 resemble an entangled mass of string 3414, are attracted to the endblocks of another triblock  
16 copolymer. When several endblocks are attracted to each other, they form an accretion of  
17 endblocks, called a domain or a glassy center 3816. Agglomeration of the endblocks occurs in a  
18 random fashion, which results in a three-dimensional network 3818 of triblocks, the midblock  
19 3216 of each connecting endblocks 3212 and 3214 located at two different domains 3816a and  
20 3816b. In addition to holding the material together, the domains of triblock copolymers also  
21 provide it with strength and rigidity.

1 Plasticizers are generally incorporated into a material to increase the workability,  
2 pliability and flexibility of that material. Incorporation of plasticizers into a material is known as  
3 plasticization. Chemically, plasticizers are hydrocarbon molecules which associate with the  
4 material into which they are incorporated, as represented in Figure 39a. In the preferred gel  
5 material, plasticizer molecules 3910 associate with the triblock copolymer 3210, and increase its  
6 workability, softness, elongation and elasticity or visco-elasticity. Depending upon the type of  
7 plasticizer used, the plasticizer molecules associate with either the endblocks, the midblock, or  
8 both. In order to preserve the strength of the preferred gel materials, Applicant prefers the  
9 predominant use of plasticizers 3910 which associate primarily with midblock polymer 3216 of  
10 triblock copolymer 3818, rather than with the end blocks. However, plasticizers which associate  
11 with the end blocks may also be useful in some formulations of the preferred gel material.  
12 Plasticizers are also desired which associate with the principle thermoplastic polymer component  
13 of the gel material.

14 Chemists have proposed four general theories to explain the effects that plasticizers have  
15 on certain materials. These theories are known as the lubricity theory, the gel theory, the  
16 mechanistic theory and the free volume theory.

17 The lubricity theory, illustrated in Figures 39b through 39d, assumes that the rigidity of a  
18 material (i.e., its resistance to deformation) is caused by intermolecular friction. Under this  
19 theory, plasticizer molecules 3910 lubricate the large molecules, facilitating movement of the  
20 large molecules over each other. *See generally, Jacqueline I. Kroschwitz, ed., CONCISE*  
21 *ENCYCLOPEDIA OF POLYMER SCIENCE AND ENGINEERING* 734-44, *Plasticizers* (1990), which is

1 hereby incorporated by reference. In the case of triblock copolymers, lubrication of the  
2 endblocks should be avoided since the endblock domains are responsible for holding the triblock  
3 copolymers together and impart the material with strength (e.g., tensile strength during  
4 elongation). Thus, a plasticizer which associates with the midblocks is preferred. According to  
5 the lubricity theory, when manipulative force is exerted on the material, plasticizer 3910  
6 facilitates movement of midblocks 3216 past each other. *Id.* at 734-35. The arrows in Figures  
7 39b, 39c and 39d represent the motion of midblocks 3216 with respect to each other. Figure 39b  
8 represents adjacent midblocks being pulled away from each other. Figure 39c represents two  
9 midblocks being forced side-to-side. Figure 39d represents adjacent midblocks being pulled  
10 across one another.

11 Figures 39e and 39f depict a second plasticization theory, the gel theory, which reasons  
12 that the resistance of amorphous polymers to deformation results from an internal, three-  
13 dimensional honeycomb structure or gel. Loose attachments between adjacent polymer chains,  
14 which occur at intervals along the chains, called attachment points, form the gel. Closer  
15 attachment between adjacent chains creates a stiffer and more brittle material. Plasticizers 3910  
16 break, or solvate, the points of attachment 3914 between polymer chains, loosening the structure  
17 of the material. Thus, plasticizers produce about the same effect on a material as if there were  
18 fewer attachment points between polymer chains, making the material softer or less brittle. *See*  
19 *Id.* at 735. Since one of the purposes of the preferred gel is to provide a material which does not  
20 have significantly decreased tensile strength, which is provided by agglomeration of the  
21 endblocks, according to the gel theory plasticizer 3910 should associate with midblocks 3216

1 rather than with the endblocks. Further, a plasticizer which associates with the midblock  
2 polymers decreases the attachment of adjacent midblocks, which likely decreases the rigidity  
3 while increasing the pliability, elongation and elasticity or visco-elasticity of the material.  
4 Similar to the lubricity theory, under the gel theory, reduction of attachment points between  
5 adjacent midblocks facilitates movement of the midblocks past one another as force is applied to  
6 the material.

7 Referring now to Figure 39g, the mechanistic theory of plasticization assumes that  
8 different types of plasticizers 3910, 3912, etc. are attracted to polymer chains by forces of  
9 different magnitudes. In addition, the mechanistic theory supposes that, rather than attach  
10 permanently, a plasticizer molecule attaches to a given attachment point only to be later  
11 dislodged and replaced by another plasticizer molecule. This continuous exchange of plasticizers  
12 3910, 3912, etc., demonstrated by Figure 39g as different stages connected by arrows which  
13 represent an equilibrium between each stage, is known as a dynamic equilibrium between  
14 solvation and desolvation of the attachment points between adjacent polymer chains. The  
15 number or fraction of attachment points affected by a plasticizer depends upon various  
16 conditions, such as plasticizer concentration, temperature, and pressure. *See Id.* Accordingly, as  
17 applied to the preferred gel material for use in this invention, a large amount of plasticizer would  
18 be necessary to affect the majority of midblock attachment points and thus provide the desired  
19 amounts of rigidity, softness, pliability, elongation and elasticity or visco-elasticity.

20 With reference to Figures 39h through 39j, the fourth plasticization theory, known as the  
21 free volume theory, assumes that there is nothing but free space between molecules. As

1 molecular motion increases (e.g., due to heat), the free space between molecules increases. Thus,  
2 a disproportionate amount of that free volume is associated with the ends of the polymer chains.  
3 As Figures 39h through 39j demonstrate, free volume is increased by using polymers with  
4 shorter chain lengths. For example, the black rectangles of Figure 39h represent a material made  
5 up of long midblock polymers 3216. The white areas around each black rectangle represent a  
6 constant width of free space around the molecule. In Figure 39i, a molecule 3916, which is  
7 smaller than midblock 3216, is added to the material, creating more free space. In Figure 39j, an  
8 even smaller molecule 3918 has been added to the material. The increase in free space within the  
9 material is evident from the increased area of white space. The crux of the free volume theory is  
10 that the increase in free space or volume allows the molecules to more easily move past one  
11 another. In other words, the use of a small (or low molecular weight) plasticizer increases the  
12 ability of the midblock polymer chains to move past each other. While Figures 39h, 39i and 39j  
13 provide a fair representation of the free volume theory, in reality, the increase in free space would  
14 be much greater than a two-dimensional drawing illustrates since molecules are three-  
15 dimensional structures.

16 Similarly, the use of polymers with flexible side chains create additional free volume  
17 around the molecule, which produces a similar plasticization-like effect, called internal  
18 plasticization. Applicant believes that incorporation of monomers into the midblock, which  
19 create flexible side chains thereon, including but not limited to isoprene (either hydrogenated or  
20 non-hydrogenated) and ethylene/propylene monomers, creates internal plasticization. In  
21 comparison, the addition of an even smaller plasticizer molecule, described above, increases the

1 free space at a given location; this is external plasticization. The size and shape of plasticizing  
2 molecule and the nature of its atoms and groups of atoms (i.e., nonpolar, polar, hydrogen  
3 bonding or not, and dense or light) determines the plasticizer's plasticizing ability on a specific  
4 polymer. *See Id.*

5 With this general background in mind, Applicant will explain the formulation, chemical  
6 structure and performance of the preferred gel material for use in the present invention.

## 7 **2. Definitions**

8 For the reader's convenience, Applicant has defined several terms which are used  
9 throughout the description of the present gel. Additionally, other terms have been defined  
10 throughout the detailed description of the preferred gel material.

### 11 *a. Elasticity and Visco-Elasticity*

12 When finite strains are imposed upon visco-elastic materials, such as the preferred gel  
13 materials, the stress-strain relations are much more complicated than those ordinarily anticipated  
14 in accordance with the classical theory of elasticity (Hooke's law) or the classical theory of  
15 hydrodynamics (Newton's law). According to Hooke's law, stress is always directly  
16 proportional to strain in small deformations but independent of the rate of strain or the strain  
17 history. Newton's law of hydrodynamics, which deals with the properties of viscous liquids,  
18 states that stress is always directly proportional to the rate of strain but independent of the strain  
19 itself.

20 "Elastic," as defined herein, refers to a characteristic of materials which return  
21 substantially to their original shape following deformation and the subsequent cessation of

1 deforming force.

2 "Visco-," as defined herein, relates to both the rate of deformation and the rate of  
3 reformation. In reference to deformation rate, the faster a deforming force is applied to a visco-  
4 elastic material, the stiffer it is. The rate of reformation of a visco-elastic material is slower than  
5 that of a truly elastic material.

6 Even if both strain and rate of strain are infinitesimal, a visco-elastic material may exhibit  
7 behavior that combines liquid-like and solid-like characteristics. For example, materials that  
8 exhibit not-quite-solid-like characteristics do not maintain a constant deformation under constant  
9 stress but deform, or creep, gradually over time. Under constant deformation, the stress required  
10 to hold a visco-elastic material in the deformed state gradually diminishes until it reaches a  
11 relatively steady state. On the other hand, a visco-elastic material that exhibits not-quite-liquid-  
12 like characteristics may, while flowing under constant stress, store some of the energy input  
13 instead of dissipating it all as heat. The stored energy may then cause the material to at least  
14 partially recover from its deformation, known as elastic recoil, when the stress is removed.  
15 When viscoelastic materials are subjected to sinusoidally oscillating stress, the strain is neither  
16 exactly in phase with the stress (as it would be for a perfectly elastic solid) nor 90° out of phase  
17 (as it would be for a perfectly viscous liquid), but is somewhere in between. Visco-elastic  
18 materials store and recover some of the deforming energy during each cycle, and dissipate some  
19 of the energy as heat. If the strain and rate of strain on a visco-elastic material are infinitesimal,  
20 the behavior of that material is linear viscoelastic and the ratio of stress to strain is a function of  
21 time (or frequency) alone, not of stress magnitude. The gel material preferred for use in the



1 present invention is elastic in nature. Visco-elastic materials are also useful in the cushions of  
2 the present invention.

3 *b. Rebound Rate*

4 "Rebound rate", as defined herein, is the amount of time it takes a one inch long piece of  
5 material to rebound to within about five percent its original shape and size following the release  
6 of stress which elongates the material to a length of two inches. The preferred elastic (or  
7 elastomeric) gel material useful in the cushioning elements of the present invention has a  
8 rebound rate of less than about one second. The preferred visco-elastic (or visco-elastomeric) gel  
9 material useful in the cushioning elements of the present invention has a rebound rate of at least  
10 about one second. More preferably, the preferred visco-elastic gel has a rebound rate within the  
11 range of about one second to about ten minutes.

12 "Instantaneous Rebound," as defined herein, refers to a characteristic of a one inch long  
13 piece of an elastomeric material which returns substantially to its original size and shape in times  
14 of about one second or less following the release of stress which elongates the material to a  
15 length of two inches. "Elastomer," as used herein, refers to the gel materials that are useful in the  
16 cushioning element of this invention and which have instantaneous rebound.

17 "Delayed Rebound," as used herein, refers to a characteristic of the visco-elastic materials  
18 preferred for use in the cushions of this invention which have a rebound rate of at least about one  
19 second. More preferably, the preferred visco-elastomeric material has a rebound rate within the  
20 range of about one second to about ten minutes. "Visco-elastomer," as defined herein, refers to  
21 gel materials useful in the invented cushions which exhibit delayed rebound characteristics.

1                    *c. Resins*

2            The term "resin" is defined herein as a solid or semisolid fusible, organic substance that is  
3 usually transparent or translucent, is soluble in organic solvent but not in water, is an electrical  
4 nonconductor, and includes tackifiers. Resins are complex mixtures which associate together  
5 due to similar physical or chemical properties. Because of their complex nature, resins do not  
6 exhibit simple melting or boiling points.

7            "Resinous" as used herein refers to resins and resin-like materials.

8            "Resinous plasticizers" as used herein refers to plasticizers which include a majority, by  
9 weight, of a resin or resins.

10           "Tackifier" as used herein refers to resins that add tack to the resulting mixture. The  
11 primary function of a tackifier is to add tack. The secondary functions of tackifiers include  
12 modification of both melt viscosity and melt temperature.

13           Tackifiers are normally low molecular weight and high glass transition temperature ( $T_g$ )  
14 materials, and are sometimes characterized as highly condensed acrylic structures. The most  
15 commonly used tackifiers are rosin derivatives, terpene resins, and synthetic or naturally derived  
16 petroleum resins. A tackifier's effectiveness is largely determined by its compatibility with the  
17 rubber component and by its ability to improve the tackiness of a material.

18           "Low molecular weight," as defined herein with reference to resins, means resins having  
19 a weight average molecular weight of less than about 50,000.

20           Resins and tackifiers are used in some preferred formulations of the preferred gel  
21 cushioning medium.

1                    *d. Oils*

2            The term "oil" is defined herein as naturally occurring hydrocarbon liquids, the carbons  
3 of which are primarily saturated with hydrogen atoms. Oils preferred for use in the preferred gel  
4 are mineral oils.

5            "Paraffinic" oils have include straight-chain or branched-chain structures. "Naphthenic"  
6 oils include cyclic hydrocarbon structures. When an oil contains both paraffinic- and  
7 naphthenic-type structures, the relative concentrations of each type of structure determine  
8 whether the oil is identified as naphthenic or paraffinic.

9            "Oil viscosity" is defined herein as the measurement of time it takes a given volume of  
10 oil to pass through an orifice, such as a capillary tube. Viscosity measurements include the  
11 Saybolt universal second (SUS), stokes (s) and centistokes (cs).

12                    *e. Molecular Weight*

13            "Number Average Molecular Weight" ( $M_n$ ), as determined by gel permeation  
14 chromatography, provides information about the lower molecular weight parts of a substance  
15 which includes hydrocarbon molecules.

16            "Weight Average Molecular Weight" ( $M_w$ ), as determined by gel permeation  
17 chromatography, indicates the average molecular weight of hydrocarbon molecules in a  
18 substance. This is the value that is commonly used in reference to the molecular weight of a  
19 hydrocarbon molecule.

20            "Z-Average Molecular Weight" ( $M_z$ ), as determined by gel permeation chromatography,  
21 is used as an indication of the high-molecular-weight portion of a substance which includes

1 hydrocarbon molecules. When the substance is a resin, the Z-average molecular weight indicates  
2 the compatibility and adhesive properties of that resin.

3 Molecular weight values may also be determined by any of several other methods, such  
4 as the Flory viscosity method, the Staudinger viscosity method, light scattering in combination  
5 with high performance liquid chromatography (HPLC), and others.

#### 6 *f. Cloud Point Tests*

7 The following values, which are determined by cloud point tests, are useful in  
8 determining the compatibility of a resin with different types of materials.

9 "MMAp," as defined herein, is a measurement of aromatic solubility and determines the  
10 aliphatic/aromatic character of a resin. The MMAp value is obtained by dissolving a resin in a  
11 high temperature mixture of one part methylcyclohexane and two parts aniline, and cooling the  
12 solution while mixing to determine the temperature at which the mixture starts becoming cloudy,  
13 which is commonly referred to as the cloud point. The lower the MMAp value, the greater the  
14 aromaticity and lower the aliphaticity of the resin.

15 "DACP," as defined herein, is a value which determines the polarity of a resin due to the  
16 highly polar nature of the solvent system. In order to determine the DACP value of resin, the  
17 resin must first be dissolved in a heated 1:1 mixture of xylene and 4-hydroxy-4-methyl-2-  
18 pentanone. The solution is then cooled with mixing. The temperature at which the solution  
19 begins becoming opaque is the cloud point, which is the DACP value.

20 Since specific adhesion is related to the polarity of a resin, the DACP value can be used  
21 as a specific adhesion indicator. Lower DACP values indicate greater specific adhesion.

1           “OMSCP,” as defined herein, is a value which is related to the molecular weight and  
2 molecular weight distribution of a resin. OMSCP can determine the compatibility characteristics  
3 of a resin/polymer system. The higher the OMS cloud point, the greater the molecular weight  
4 and the molecular weight distribution of a resin. In particular, high OMSCP values can indicate  
5 the presence of high molecular weight materials (of Z-average molecular weight).

6           The term “OMSCP” is derived from the method for determining OMSCP values. A resin  
7 is first dissolved in a high temperature mixture of odorless mineral spirits (OMS). The solution  
8 is then cooled with mixing. The temperature at which the mixture starts becoming cloudy is  
9 referred to as the cloud point (CP), or OMSCP value.

### 10           **3. Material Formulations**

#### 11           *a. Elastomer Component*

12           Preferably, the compositions of the preferred gel materials for use in the present invention  
13 are low durometer (as defined below) thermoplastic elastomeric compounds and visco-  
14 elastomeric compounds which include a principle polymer component, an elastomeric block  
15 copolymer component and a plasticizer component.

16           The elastomer component of the preferred gel material includes a triblock polymer of the  
17 general configuration A-B-A, wherein the A represents a crystalline polymer such as a  
18 monoalkenylarene polymer, including but not limited to polystyrene and functionalized  
19 polystyrene, and the B is an elastomeric polymer such as polyethylene, polybutylene,  
20 poly(ethylene/butylene), hydrogenated poly(isoprene), hydrogenated poly(butadiene),  
21 hydrogenated poly(isoprene+butadiene), poly(ethylene/propylene) or hydrogenated

1 poly(ethylene/butylene + ethylene/propylene), or others. The A components of the material link  
2 to each other to provide strength, while the B components provide elasticity. Polymers of greater  
3 molecular weight are achieved by combining many of the A components in the A portions of  
4 each A-B-A structure and combining many of the B components in the B portion of the A-B-A  
5 structure, along with the networking of the A-B-A molecules into large polymer networks.

6 A preferred elastomer for making the preferred gel material is a very high to ultra high  
7 molecular weight elastomer and oil compound having an extremely high Brookfield Viscosity  
8 (hereinafter referred to as "solution viscosity"). Solution viscosity is generally indicative of  
9 molecular weight. "Solution viscosity" is defined as the viscosity of a solid when dissolved in  
10 toluene at 25-30°C., measured in centipoises (cps). "Very high molecular weight" is defined  
11 herein in reference to elastomers having a solution viscosity, 20 weight percent solids in 80  
12 weight percent toluene, the weight percentages being based upon the total weight of the solution,  
13 from greater than about 20,000 cps to about 50,000 cps. An "ultra high molecular weight  
14 elastomer" is defined herein as an elastomer having a solution viscosity, 20 weight percent solids  
15 in 80 weight percent toluene, of greater than about 50,000 cps. Ultra high molecular weight  
16 elastomers have a solution viscosity, 10 weight percent solids in 90 weight percent toluene, the  
17 weight percentages being based upon the total weight of the solution, of about 800 to about  
18 30,000 cps and greater. The solution viscosities, in 80 weight percent toluene, of the A-B-A  
19 block copolymers useful in the elastomer component of the preferred gel cushioning material are  
20 substantially greater than 30,000 cps. The solution viscosities, in 90 weight percent toluene, of  
21 the preferred A-B-A elastomers useful in the elastomer component of the preferred gel are in the

1 range of about 2,000 cps to about 20,000 cps. Thus, the preferred elastomer component of the  
2 preferred gel material has a very high to ultra high molecular weight.

3 Applicant has discovered that, after surpassing a certain optimum molecular weight  
4 range, some elastomers exhibit lower tensile strength than similar materials with optimum  
5 molecular weight copolymers. Thus, merely increasing the molecular weight of the elastomer  
6 will not always result in increased tensile strength.

7 The elastomeric B portion of the preferred A-B-A polymers has an exceptional affinity  
8 for most plasticizing agents, including but not limited to several types of oils, resins, and others.  
9 When the network of A-B-A molecules is denatured, plasticizers which have an affinity for the B  
10 block can readily associate with the B blocks. Upon renaturation of the network of A-B-A  
11 molecules, the plasticizer remains highly associated with the B portions, reducing or even  
12 eliminating plasticizer bleed from the material when compared with similar materials in the prior  
13 art, even at very high oil:elastomer ratios. The reason for this performance may be any of the  
14 plasticization theories explained above (i.e., lubricity theory, gel theory, mechanistic theory, and  
15 free volume theory).

16 The elastomer used in the preferred gel cushioning medium is preferably an ultra high  
17 molecular weight polystyrene-hydrogenated poly(isoprene+butadiene)-polystyrene, such as those  
18 sold under the brand names SEPTON 4045, SEPTON 4055 and SEPTON 4077 by Kuraray, an  
19 ultra high molecular weight polystyrene-hydrogenated polyisoprene-polystyrene such as the  
20 elastomers made by Kuraray and sold as SEPTON 2005 and SEPTON 2006, or an ultra high  
21 molecular weight polystyrene-hydrogenated polybutadiene-polystyrene, such as that sold as

1 SEPTON 8006 by Kuraray. High to very high molecular weight polystyrene-hydrogenated  
2 poly(isoprene+butadiene)-polystyrene elastomers, such as that sold under the trade name  
3 SEPTON 4033 by Kuraray, are also useful in some formulations of the preferred gel material  
4 because they are easier to process than the preferred ultra high molecular weight elastomers due  
5 to their effect on the melt viscosity of the material.

6 Following hydrogenation of the midblocks of each of SEPTON 4033, SEPTON 4045,  
7 SEPTON 4055, and SEPTON 4077, less than about five percent of the double bonds remain.  
8 Thus, substantially all of the double bonds are removed from the midblock by hydrogenation.

9 Applicant's most preferred elastomer for use in the preferred gel is SEPTON 4055 or  
10 another material that has similar chemical and physical characteristics. SEPTON 4055 has the  
11 optimum molecular weight (approximately 300,000, as determined by Applicant's gel  
12 permeation chromatography testing). SEPTON 4077 has a somewhat higher molecular weight,  
13 and SEPTON 4045 has a somewhat lower molecular weight than SEPTON 4055. Materials  
14 which include either SEPTON 4045 or SEPTON 4077 as the primary block copolymer typically  
15 have lower tensile strength than similar materials made with SEPTON 4055.

16 Kuraray Co. Ltd. of Tokyo, Japan has stated that the solution viscosity of SEPTON 4055,  
17 the most preferred A-B-A triblock copolymer for use in the preferred gel material, 10% solids in  
18 90% toluene at 25°C., is about 5,800 cps. Kuraray also said that the solution viscosity of  
19 SEPTON 4055, 5% solids in 95% toluene at 25°C, is about 90 cps. Although Kuraray has not  
20 provided a solution viscosity, 20% solids in 80% toluene at 25°C., an extrapolation of the two  
21 data points given shows that such a solution viscosity would be about 400,000 cps. Applicant



1 reads the prior art as consistently teaching away from such high solution viscosities.

2       Applicant confirmed Kuraray's data by having an independent laboratory, SGS U.S.  
3 Testing Company Inc. of Fairfield, New Jersey, test the solution viscosity of SEPTON 4055.  
4 When SGS attempted to dissolve 20% solids in 80% toluene at 25°C., the resulting material did  
5 not resemble a solution. Therefore, SGS determined the solution viscosity of SEPTON 4055  
6 using 10% solids in 90% toluene at 25°C., which resulted in a 3,040 cps solution.

7       Other materials with chemical and physical characteristics similar to those of SEPTON  
8 4055 include other A-B-A triblock copolymers which have a hydrogenated midblock polymer  
9 that is made up of at least about 30% isoprene monomers and at least about 30% butadiene  
10 monomers, the percentages being based on the total number of monomers that make up the  
11 midblock polymer. Similarly, other A-B-A triblock copolymers which have a hydrogenated  
12 midblock polymer that is made up of at least about 30% ethylene/propylene monomers and at  
13 least about 30% ethylene/butylene monomers, the percentages being based on the total number of  
14 monomers that make up the midblock polymer, are materials with chemical and physical  
15 characteristics similar to those of SEPTON 4055.

16       Mixtures of block copolymer elastomers are also useful as the elastomer component of  
17 some of the formulations of the preferred gel cushioning medium. In such mixtures, each type of  
18 block copolymer contributes different properties to the material. For example, high strength  
19 triblock copolymer elastomers are desired to improve the tensile strength and durability of a  
20 material. However, some high strength triblock copolymers are very difficult to process with  
21 some plasticizers. Thus, in such a case, block copolymer elastomers which improve the

1 processability of the materials are desirable.

2 In particular, the process of compounding SEPTON 4055 with plasticizers may be  
3 improved via a lower melt viscosity by using a small amount of more flowable elastomer such as  
4 SEPTON 8006, SEPTON 2005, SEPTON 2006, or SEPTON 4033, to name only a few, without  
5 significantly changing the physical characteristics of the material.

6 In a second example of the usefulness of block copolymer elastomer mixtures in the  
7 preferred gel materials, many block copolymers are not good compatibilizers. Other block  
8 copolymers readily form compatible mixtures, but have other undesirable properties. Thus, the  
9 use of small amount of elastomers which improve the uniformity with which a material mixes are  
10 desired. KRATON® G 1701, manufactured by Shell Chemical Company of Houston, Texas, is  
11 one such elastomer that improves the uniformity with which the components of the preferred gel  
12 material mix.

13 Many other elastomers, including but not limited to triblock copolymers and diblock  
14 copolymers are also useful in the preferred gel material. Applicant believes that elastomers  
15 having a significantly higher molecular weight than the ultra-high molecular weight elastomers  
16 useful in the preferred gel material increase the softness thereof, but decrease the strength of the  
17 gel. Thus, high to ultra high molecular weight elastomers, as defined above, are desired for use  
18 in the preferred gel material due to the strength of such elastomers when combined with a  
19 plasticizer.

20 *b. Additives*

21 *i. Polarizable Plasticizer Bleed-Reducing Additives*

1 Preferably, the gel materials used in the cushions of the present invention do not exhibit  
2 migration of plasticizers, even when placed against materials which readily exhibit a high degree  
3 of capillary action, such as paper, at room temperature.

4 A preferred plasticizer bleed-reducing additive that is useful in the preferred gel  
5 cushioning material includes hydrocarbon chains with readily polarizable groups thereon. Such  
6 polarizable groups include, without limitation, halogenated hydrocarbon groups, halogens,  
7 nitriles, and others. Applicant believes that the polarizability of such groups on the hydrocarbon  
8 molecule of the bleed-reducing additive have a tendency to form weak van der Waals bonding  
9 with the long hydrocarbon chains of the rubber portion of an elastomer and with the plasticizer  
10 molecules. Due to the great length of typical rubber polymers, several of the bleed-reducers will  
11 be attracted thereto, while fewer will be attracted to each plasticizer molecule. The bleed-  
12 reducing additives are believed to hold the plasticizer molecules and the elastomer molecules  
13 thereto, facilitating attraction between the elastomeric block and the plasticizer molecule. In  
14 other words, the preferred bleed-reducing additives are believed to attract a plasticizer molecule  
15 at one polarizable site, while attracting an elastomeric block at another polarizable site, thus  
16 maintaining the association of the plasticizer molecules with the elastomer molecules, which  
17 inhibits exudation of the plasticizer molecules from the elastomer-plasticizer compound. Thus,  
18 each of the plasticizer molecules is preferably attracted to an elastomeric block by means of a  
19 bleed-reducing additive.

20 The preferred bleed-reducing additives that are useful in the preferred gel material have a  
21 plurality of polarizable groups thereon, which facilitate bonding an additive molecule to a

1 plurality of elastomer molecules and/or plasticizer molecules. It is believed that an additive  
2 molecule with more polarizable sites thereon will bond to more plasticizer molecules.  
3 Preferably, the additive molecules remain in a liquid or a solid state during processing of the gel  
4 material.

5 The most preferred bleed-reducing additives for use in the preferred gel material are  
6 halogenated hydrocarbon additives such as those sold under the trade name DYNAMAR™ PPA-  
7 791, DYNAMAR™ PPA-790, DYNAMAR™ FX-9613, and FLUORAD® FC 10  
8 Fluorochemical Alcohol, each by 3M Company of St. Paul, Minnesota. Other additives are also  
9 useful to reduce plasticizer exudation from the preferred gel material. Such additives include,  
10 without limitation, other halogenated hydrocarbons sold under the trade name FLUORAD®,  
11 including without limitation FC-129, FC-135, FC-430, FC-722, FC-724, FC-740, FX-8, FX-13,  
12 FX-14 and FX-189; halogenated hydrocarbons such as those sold under the trade name  
13 ZONYL®, including without limitation FSN 100, FSO 100, PFBE, 8857A, ™, BA-L, BA-N,  
14 TBC and FTS, each of which are manufactured by du Pont of Wilmington, Delaware;  
15 halogenated hydrocarbons sold under the trade name EMCOL by Witco Corp of Houston, Texas,  
16 including without limitation 4500 and DOSS; other halogenated hydrocarbons sold by 3M under  
17 the trade name DYNAMAR™; chlorinated polyethylene elastomer (CPE), distributed by  
18 Harwick, Inc. of Akron, Ohio; chlorinated paraffin wax, distributed by Harwick, Inc.; and others.

19 *ii. Detackifiers*

20 The preferred material may include a detackifier. Tack is not a desirable feature in many  
21 potential uses for the cushions of the invention. However, some of the elastomeric copolymers

1 and plasticizers useful in the preferred cushioning media for the cushioning elements of the  
2 present invention may impart tack to the media.

3 Soaps, detergents and other surfactants have detackifying abilities and are useful in the  
4 preferred gel material. "Surfactants," as defined herein, refers to soluble surface active agents  
5 which contain groups that have opposite polarity and solubilizing tendencies. Surfactants form a  
6 monolayer at interfaces between hydrophobic and hydrophilic phases; when not located at a  
7 phase interface, surfactants form micelles. Surfactants have detergency, foaming, wetting,  
8 emulsifying and dispersing properties. **Sharp, D.W.A.**, DICTIONARY OF CHEMISTRY, 381-82  
9 (Penguin, 1990). For example, coco diethanolamide, a common ingredient in shampoos, is  
10 useful in the preferred gel material as a detackifying agent. Coco diethanolamide resists  
11 evaporation, is stable, relatively non-toxic, non-flammable and does not support microbial  
12 growth. Many different soap or detergent compositions could be used in the material as well.

13 Other known detackifiers include glycerin, epoxidized soybean oil, dimethicone, tributyl  
14 phosphate, block copolymer polyether, diethylene glycol mono oleate, tetraethyleneglycol  
15 dimethyl ether, and silicone, to name only a few. Glycerine is available from a wide variety of  
16 sources. Witco Corp. of Greenwich, Connecticut sells epoxidized soybean oil as DRAPEX 6.8.  
17 Dimethicone is available from a variety of vendors, including GE Specialty Chemicals of  
18 Parkersburg, West Virginia under the trade name GE SF 96-350. C.P. Hall Co. of Chicago,  
19 Illinois markets block copolymer polyether as PLURONIC L-61. C.P. Hall Co. also  
20 manufactures and markets diethylene glycol mono oleate under the name Diglycol Oleate—  
21 Hallco CPH-I-SE. Other emulsifiers and dispersants are also useful in the preferred gel material.

1 Tetraethyleneglycol dimethyl ether is available under the trade name TETRAGLYME from  
2 Ferro Corporation of Zachary, Louisiana. Applicant believes that TETRAGLYME also reduces  
3 plasticizer exudation from the preferred gel material.

4 *iii. Antioxidants*

5 The preferred gel material also includes additives such as an antioxidant. Antioxidants  
6 such as those sold under the trade names IRGANOX® 1010 and IRGAFOS® 168 by Ciba-Geigy  
7 Corp. of Tarrytown, New York are useful by themselves or in combination with other  
8 antioxidants in the preferred materials of the present invention.

9 Antioxidants protect the preferred gel materials against thermal degradation during  
10 processing, which requires or generates heat. In addition, antioxidants provide long term  
11 protection from free radicals. A preferred antioxidant inhibits thermo-oxidative degradation of  
12 the compound or material to which it is added, providing long term resistance to polymer  
13 degradation. Preferably, an antioxidant added to the preferred gel cushioning medium is useful  
14 in food packaging applications, subject to the provisions of 21 C.F.R. § 178.2010 and other laws.

15 Heat, light (in the form of high energy radiation), mechanical stress, catalyst residues, and  
16 reaction of a material with impurities all cause oxidation of the material. In the process of  
17 oxidation, highly reactive molecules known as free radicals are formed and react in the presence  
18 of oxygen to form peroxy free radicals, which further react with organic material (hydro-carbon  
19 molecules) to form hydroperoxides.

20 The two major classes of antioxidants are the primary antioxidants and the secondary  
21 antioxidants. Peroxy free radicals are more likely to react with primary antioxidants than with

1 most other hydrocarbons. In the absence of a primary antioxidant, a peroxy free radical would  
2 break a hydrocarbon chain. Thus, primary antioxidants deactivate a peroxy free radical before it  
3 has a chance to attack and oxidize an organic material.

4 Most primary antioxidants are known as sterically hindered phenols. One example of  
5 sterically hindered phenol is the  $C_{73}H_{108}O_{12}$  marketed by Ciba-Geigy as IRGANOX® 1010,  
6 which has the chemical name 3,5-bis(1,1-dimethylethyl)-4-hydroxybenzenepropanoic acid, 2,2-  
7 bis[[3-[3,5-bis(dimethylethyl)-4-hydroxyphenyl]-1-oxopropoxy]methyl]1,3-propanediyl ester.  
8 The FDA refers to IRGANOX® 1010 as tetrakis[methylene(3,5-di-tert-butyl-4-  
9 hydroxyhydrocinnamate)]methane. Other hindered phenols are also useful as primary  
10 antioxidants in the preferred material.

11 Similarly, secondary antioxidants react more rapidly with hydroperoxides than most other  
12 hydrocarbon molecules. Secondary antioxidants have been referred to as hydroperoxide  
13 decomposers. Thus, secondary antioxidants protect organic materials from oxidative degradation  
14 by hydroperoxides.

15 Commonly used secondary antioxidants include the chemical classes of  
16 phosphites/phosphonites and thioesters, many of which are useful in the preferred gel material.  
17 The hydroperoxide decomposer used by Applicant is a  $C_{42}H_{63}O_3P$  phosphite known as Tris(2,4-  
18 di-tert-butylphenyl)phosphite and marketed by Ciba-Geigy as IRGAFOS® 168.

19 It is known in the art that primary and secondary antioxidants form synergistic  
20 combinations to ward off attacks from both peroxy free radicals and hydroperoxides.

21 Other antioxidants, including but not limited to multi-functional antioxidants, are also

1 useful in the preferred material. Multifunctional antioxidants have the reactivity of both a  
2 primary and a secondary antioxidant. IRGANOX® 1520 D, manufactured by Ciba-Geigy is one  
3 example of a multifunctional antioxidant. Vitamin E antioxidants, such as that sold by Ciba-  
4 Geigy as IRGANOX® E17, are also useful in the preferred cushioning material for use in the  
5 cushions of the present invention.

6 Preferably, the preferred gel material includes up to about three weight percent  
7 antioxidant, based on the weight of the elastomer component, when only one type of antioxidant  
8 is used. The material may include as little as 0.1 weight percent of an antioxidant, or no  
9 antioxidant at all. When a combination of antioxidants is used, each may comprise up to about  
10 three weight percent, based on the weight of the elastomer component. Additional antioxidants  
11 may be added for severe processing conditions involving excessive heat or long duration at a  
12 high temperature.

13 Applicant believes that the use of excess antioxidants reduces or eliminates tack on the  
14 exterior surface of the preferred gel material. Excess antioxidants appear to migrate to the  
15 exterior surface of the material following compounding of the material. Such apparent migration  
16 occurs over substantial periods of time, from hours to days or even longer.

17 *iv. Flame retardants*

18 Flame retardants may also be added to the preferred gel materials. Flame retardants  
19 useful in the cushioning elements of the present invention include but are not limited to  
20 diatomaceous earth flame retardants sold as GREAT LAKES DE 83R and GREAT LAKES DE  
21 79 by Great Lakes Filter, Division of Acme Mills Co. of Detroit, Michigan. Most flame



1 retardants that are useful in elastomeric materials are also useful in the preferred gel material. In  
2 particular, Applicant prefers the use of food grade flame retardants which do not significantly  
3 diminish the physical properties of the preferred gel material.

4 Chemical blowing agents, such as SAFOAM® FP-40, manufactured by Reedy  
5 International Corporation of Keyport, New Jersey and others are useful for making a gel  
6 cushioning medium that is self-extinguishing.

#### 7 *v. Colorants*

8 Colorants may also be used in the preferred gel materials for use in the cushions of the  
9 present invention. Any colorant which is compatible with elastomeric materials may be used in  
10 the materials. In particular, Applicant prefers to use aluminum lake colorants such as those  
11 manufactured by Warner Jenkinson Corp. of St. Louis, Missouri; pigments manufactured by Day  
12 Glo Color Corp. of Cleveland, Ohio; Lamp Black, such as that sold by Spectrum Chemical  
13 Manufacturing Corp. of Gardena, California; and Titanium Dioxide (white). By using these  
14 colorants, the gel material takes on intense shades of colors, including but not limited to pink,  
15 red, orange, yellow, green, blue, violet, brown, flesh, white and black.

#### 16 *vi. Paint*

17 The preferred gel cushioning medium may also be painted.

#### 18 *vii. Other additives*

19 Other additives may also be added to the preferred gel material. Additives such as  
20 foaming facilitators, tack modifiers, plasticizer bleed modifiers, flame retardants, melt viscosity  
21 modifiers, melt temperature modifiers, tensile strength modifiers, and shrinkage inhibitors are

1 useful in specific formulations of the preferred gel material.

2 Melt temperature modifiers useful in the preferred gel include cross-linking agents,  
3 hydrocarbon resins, diblock copolymers of the general configuration A-B and triblock  
4 copolymers of the general configuration A-B-A wherein the end block A polymers include  
5 functionalized styrene monomers, and others.

6 Tack modifiers which tend to reduce tack and which are useful in the preferred gel  
7 include surfactants, dispersants, emulsifiers, and others. Tack modifiers which tend to increase  
8 the tack of the material and which are useful in the material include hydrocarbon resins,  
9 polyisobutylene, butyl rubber and others.

10 Foam facilitators that are useful in the gel material include polyisobutylene, butyl rubber,  
11 surfactants, emulsifiers, dispersants and others.

12 Plasticizer bleed modifiers which tend to reduce plasticizer exudation from the preferred  
13 material and which are useful therein include hydrocarbon resins, elastomeric diblock  
14 copolymers, polyisobutylene, butyl rubber, transpolyoctenylene rubber ("tor rubber"), and others.

15 Flame retardants useful in the preferred gel include halogenated flame retardants, non-  
16 halogenated flame retardants, and volatile, non-oxygen gas forming chemicals and compounds.

17 Melt viscosity modifiers that tend to reduce the melt viscosity of the pre-compounded  
18 component mixture of the preferred cushioning medium include hydrocarbon resins,  
19 transpolyoctenylene rubber, castor oil, linseed oil, non-ultra high molecular weight thermoplastic  
20 rubbers, surfactants, dispersants, emulsifiers, and others.

21 Melt viscosity modifiers that tend to increase the melt viscosity of the pre-compounded

1 component mixture of the preferred gel material include hydrocarbon resins, butyl rubber,  
2 polyisobutylene, additional triblock copolymers having the general configuration A-B-A and a  
3 molecular weight greater than that of each of the block copolymers in the elastomeric block  
4 copolymer component of the material, particulate fillers, microspheres, butadiene rubber,  
5 ethylene/propylene rubber, ethylene/butylene rubber, and others.

6 Tensile strength modifiers which tend to increase the tensile strength of the preferred gel  
7 material for use in the cushions of the present invention include mid block B-associating  
8 hydrocarbon resins, non-end-block solvating hydrocarbon resins which associate with the end  
9 blocks, particulate reinforcers, and others.

10 Shrinkage inhibitors, which tend to reduce shrinkage of the gel material following  
11 compounding, that are useful in the material include hydrocarbon resins, particulate fillers,  
12 microspheres, transpolyoctenylene rubber, and others.

### 13 *c. Microspheres*

14 Microspheres may also be added to the preferred gel material. The gel material may  
15 contain up to about 90% microspheres, by volume. In one preferred microsphere-containing  
16 formulation of the preferred gel material, microspheres make up at least about 30% of the total  
17 volume of the material. A second preferred microsphere-containing formulation of the preferred  
18 gel cushioning medium includes at least about 50% microspheres, by volume.

19 Different types of microspheres contribute various properties to the material. For  
20 example, hollow acrylic microspheres, such as those marketed under the brand name  
21 MICROPEARL, and generally in the 20 to 200 micron size range, by Matsumoto Yushi-Seiyaku

1 Co., Ltd. of Osaka, Japan, lower the specific gravity of the material. In other formulations of the  
2 gel, the microspheres may be unexpanded DU(091-80), which expand during processing of the  
3 preferred gel cushioning medium, or pre-expanded DE (091-80) acrylic microspheres from  
4 Expancel Inc. of Duluth, Georgia.

5 In formulations of the preferred material which include hollow acrylic microspheres, the  
6 microspheres preferably have substantially instantaneous rebound when subjected to a  
7 compression force which compresses the microspheres to a thickness of up to about 50% of their  
8 original diameter or less.

9 Hollow microspheres also decrease the specific gravity of the gel material by creating gas  
10 pockets therein. In many cushioning applications, very low specific gravities are preferred. The  
11 specific gravity of the preferred gel cushioning medium may range from about 0.06 to about  
12 1.30, depending in part upon the amount and specific gravity of fillers and additives, including  
13 microspheres and foaming agents. In many cushioning applications of the present invention, a  
14 gel material having a specific gravity of less than about 0.50 is preferred. When a gel material  
15 preferred for use in cushions according to the present invention includes the preferred  
16 microspheres, the microspheres must be dispersed, on average, at a distance of about one-and-a-  
17 half (1.5) times the average microsphere diameter or a lesser distance from one another in order  
18 to achieve a specific gravity of less than about 0.50. A specific gravity of less than about 0.30 is  
19 preferred for use in some cushions according to this invention. Other formulations of the  
20 preferred gel material have specific gravities of less than about 0.65, less than about 0.45, and  
21 less than about 0.25.

1 MICROPEARL and EXPANCEL acrylic microspheres are preferred because of their  
2 highly flexible nature, as explained above, which tend to not restrict deformation of the  
3 thermoplastic elastomer. Glass, ceramic, and other types of microspheres may also be used in  
4 the thermoplastic gel material, but are less preferred.

5 *d. Plasticizer Component*

6 As explained above, plasticizers allow the midblocks of a network of triblock copolymer  
7 molecules to move past one another. Thus, Applicant believes that plasticizers, when trapped  
8 within the three dimensional web of triblock copolymer molecules, facilitate the disentanglement  
9 and elongation of the elastomeric midblocks as a load is placed on the network. Similarly,  
10 Applicant believes that plasticizers facilitate recontraction of the elastomeric midblocks  
11 following release of the load. The plasticizer component of the preferred gel cushioning medium  
12 may include oil, resin, a mixture of oils, a mixture of resins, other lubricating materials, or any  
13 combination of the foregoing.

14 *i. Oils*

15 The plasticizer component of the preferred gel material may include a commercially  
16 available oil or mixture of oils. The plasticizer component may include other plasticizing agents,  
17 such as liquid oligomers and others, as well. Both naturally derived and synthetic oils are useful  
18 in the preferred gel material. Preferably, the oils have a viscosity of about 70 SUS to about 500  
19 SUS at about 100°F. Most preferred for use in the gel material are paraffinic white mineral oils  
20 having a viscosity in the range of about 90 SUS to about 200 SUS at about 100°F.

21 One embodiment of a plasticizer component of the preferred gel includes paraffinic white

1 mineral oils, such as those having the brand name DUOPRIME, by Lyondell Lubricants of  
2 Houston, Texas, and the oils sold under the brand name TUFFLO by Witco Corporation of  
3 Petrolia, Pennsylvania. For example, the plasticizer component of the preferred gel may include  
4 paraffinic white mineral oil such as that sold under the trade name LP-150 by Witco.

5 Paraffinic white mineral oils having an average viscosity of about 90 SUS, such as  
6 DUOPRIME 90, are preferred for use in other embodiments of the plasticizer component of the  
7 preferred gel cushioning medium. Applicant has found that DUOPRIME 90 and oils with  
8 similar physical properties can be used to impart the greatest strength to the preferred gel  
9 material.

10 Other oils are also useful as plasticizers in compounding the gel material. Examples of  
11 representative commercially available oils include processing oils such as paraffinic and  
12 naphthenic petroleum oils, highly refined aromatic-free or low aromaticity paraffinic and  
13 naphthenic food and technical grade white petroleum mineral oils, and synthetic liquid oligomers  
14 of polybutene, polypropene, polyterpene, etc., and others. The synthetic series process oils are  
15 oligomers which are permanently fluid liquid non-olefins, isoparaffins or paraffins. Many such  
16 oils are known and commercially available. Examples of representative commercially available  
17 oils include Amoco® polybutenes, hydrogenated polybutenes and polybutenes with epoxide  
18 functionality at one end of the polybutene polymer. Examples of such Amoco polybutenes  
19 include: L-14 (320 M<sub>n</sub>), L-50 (420 M<sub>n</sub>), L-100 (460 M<sub>n</sub>), H-15 (560 M<sub>n</sub>), H-25 (610 M<sub>n</sub>), H-35  
20 (660 M<sub>n</sub>), H-50 (750 M<sub>n</sub>), H-100 (920 M<sub>n</sub>), H-300 (1290 M<sub>n</sub>), L-14E (27-37 cst @ 100°F.  
21 Viscosity), L-300E (635-690 cst @ 210°F. Viscosity), Actipol E6 (365 M<sub>n</sub>), E16 (973 M<sub>n</sub>), E23

1 (1433  $M_n$ ) and the like. Examples of various commercially available oils include: Bayol, Bernol,  
2 American, Blandol, Drakeol, Ervol, Gloria, Kaydol, Litetek, Marcol, Parol, Penetec, Primol,  
3 Protol, Sontex, and the like.

4 *ii. Resins*

5 Resins useful in the plasticizer component of the preferred gel material include, but are  
6 not limited to, hydrocarbon-derived and rosin-derived resins having a ring and ball softening  
7 point of up to about 150°C., more preferably from about 0°C. to about 25°C., and a weight  
8 average molecular weight of at least about 300.

9 For use in many of the cushions according to the invention, Applicant prefers the use of  
10 resins or resin mixtures which are highly viscous flowable liquids at room temperature (about  
11 23°C.). Plasticizers which are fluid at room temperature impart softness to the gel material.  
12 Although room temperature flowable resins are preferred, resins which are not flowable liquids  
13 at room temperature are also useful in the material.

14 The resins most preferred for use in the preferred gel material have a ring and ball  
15 softening point of about 18°C.; melt viscosities of about 10 poises (ps) at about 61°C., about 100  
16 ps at about 42°C. and about 1,000 ps at about 32°C.; an onset  $T_g$  of about -20°C.; a MMAP value  
17 of 68°C.; a DACP value of 15°C.; an OMSCP value of less than -40°C.; a  $M_n$  of about 385; a  $M_w$   
18 of about 421; and a  $M_z$  of about 463. One such resin is marketed as REGALREZ® 1018 by  
19 Hercules Incorporated of Wilmington, Delaware. Variations of REGALREZ® 1018 which are  
20 useful in the preferred cushioning material have viscosities including, but not limited to, 1025  
21 stokes, 1018 stokes, 745 stokes, 114 stokes, and others.

1 Room temperature flowable resins that are derived from poly- $\beta$ -pinene and have  
2 softening points similar to that of REGALREZ® 1018 are also useful in the plasticizer  
3 component of the preferred cushioning medium. One such resin, sold as PICCOLYTE® S25 by  
4 Hercules Incorporated, has a softening point of about 25°C.; melt viscosities of about 10 ps at  
5 about 80°C., about 100 ps at about 56°C. and about 1,000 ps at about 41°C.; a MMAP value of  
6 about 88°C.; a DACP value of about 45°C.; an OMSCP value of less than about -50°C.; a  $M_z$  of  
7 about 4,800; a  $M_w$  of about 1,950; and a  $M_n$  of about 650. Other PICCOLYTE® resins may also  
8 be used in the preferred gel material.

9 Another room temperature flowable resin which is useful in the plasticizer component of  
10 the preferred material is marketed as ADTAC® LV by Hercules Incorporated. That resin has a  
11 ring and ball softening point of about 5°C.; melt viscosities of about 10 ps at about 62°C., about  
12 100 ps at about 36°C. and about 1,000 ps at about 20°C.; a MMAP value of about 93°C.; a  
13 DACP value of about 44°C.; an OMSCP value of less than about -40°C.; a  $M_z$  of about 2,600; a  
14  $M_w$  of about 1,380; and a  $M_n$  of about 800.

15 Resins such as the liquid aliphatic C-5 petroleum hydrocarbon resin sold as  
16 WINGTACK® 10 by the Goodyear Tire & Rubber Company of Akron, Ohio and other  
17 WINGTACK® resins are also useful in the gel material. WINGTACK® 10 has a ring and ball  
18 softening point of about 10°C.; a Brookfield Viscosity of about 30,000 cps at about 25°C.; melt  
19 viscosities of about 10 ps at about 53°C. and about 100 ps at about 34°C.; an onset  $T_g$  of about -  
20 37.7°C.; a  $M_n$  of about 660; a  $M_w$  of about 800; a 1:1 polyethylene-to-resin ratio cloud point of  
21 about 89°C.; a 1:1 microcrystalline wax-to-resin ratio cloud point of about 77°C.; and a 1:1



1 paraffin wax-to-resin ratio cloud point of about 64°C.

2 Resins that are not readily flowable at room temperature (i.e., are solid, semi-solid, or  
3 have an extremely high viscosity) or that are solid at room temperature are also useful in the  
4 preferred gel material. One such solid resin is an aliphatic C-5 petroleum hydrocarbon resin  
5 having a ring and ball softening point of about 98°C.; melt viscosities of about 100 ps at about  
6 156°C. and about 1000 ps at about 109°C.; an onset  $T_g$  of about 46.1°C.; a  $M_n$  of about 1,130; a  
7  $M_w$  of about 1,800; a 1:1 polyethylene-to-resin ratio cloud point of about 90°C.; a 1:1  
8 microcrystalline wax-to-resin ratio cloud point of about 77°C.; and a 1:1 paraffin wax-to-resin  
9 ratio cloud point of about 64°C. Such a resin is available as WINGTACK® 95 and is  
10 manufactured by Goodyear Chemical Co.

11 Polyisobutylene polymers are an example of resins which are not readily flowable at  
12 room temperature and that are useful in the preferred gel material. One such resin, sold as  
13 VISTANEX® LM-MS by Exxon Chemical Company of Houston, Texas, has a  $T_g$  of -60°C., a  
14 Brookfield Viscosity of about 250 cps to about 350 cps at about 350°F., a Flory molecular  
15 weight in the range of about 42,600 to about 46,100, and a Staudinger molecular weight in the  
16 range of about 10,400 to about 10,900. The Flory and Staudinger methods for determining  
17 molecular weight are based on the intrinsic viscosity of a material dissolved in diisobutylene at  
18 20°C.

19 Glycerol esters of polymerized rosin are also useful as plasticizers in the preferred gel  
20 material. One such ester, manufactured and sold by Hercules Incorporated as HERCULES®  
21 Ester Gum 10D Synthetic Resin, has a softening point of about 116°C.

1 Many other resins are also suitable for use in the gel material. In general, plasticizing  
2 resins are preferred which are compatible with the B block of the elastomer used in the material,  
3 and non-compatible with the A blocks.

4 In some embodiments of the cushion according to the present invention, tacky materials  
5 may be desirable. In such embodiments, the plasticizer component of the gel material may  
6 include about 20 weight percent or more, about 40 weight percent or more, about 60 weight  
7 percent or more, or up to about 100 weight percent, based upon the weight of the plasticizer  
8 component, of a tackifier or tackifier mixture.

### 9 *iii. Plasticizer Mixtures*

10 The use of plasticizer mixtures in the plasticizer component of the preferred gel material  
11 is useful for tailoring the physical characteristics of the preferred gel material. For example,  
12 characteristics such as durometer, tack, tensile strength, elongation, melt flow and others may be  
13 modified by combining various plasticizers.

14 For example, a plasticizer mixture which includes at least about 37.5 weight percent of a  
15 paraffinic white mineral oil having physical characteristics similar to those of LP-150 (a  
16 viscosity of about 150 SUS at about 100°F., a viscosity of about 30 centistokes (cSt) at about  
17 40°C, and maximum pour point of about -35°F.) and up to about 62.5 weight percent of a resin  
18 having physical characteristics similar to those of REGALREZ® 1018 (such as a softening point  
19 of about 20°C.; an onset  $T_g$  of about -20°C.; a MMAP value of about 70°C.; a DACP value of  
20 about 15°C.; an OMSCP value of less than about -40°C.; and  $M_w$  of about 400), all weight  
21 percentages being based upon the total weight of the plasticizer mixture, could be used in a gel

1 cushioning medium. When compared to a material plasticized with the same amount of an oil  
2 such as LP-150, the material which includes the plasticizer mixture has decreased oil bleed and  
3 increased tack.

4 Applicant believes that, when resin is included with oil in a plasticizer mixture of the  
5 preferred gel for use in cushions according to the present invention, the material exhibits reduced  
6 oil bleed. For example, a formulation of the material which includes a plasticizing component  
7 which has about three parts plasticizing oil (such as LP-150), and about five parts plasticizing  
8 resin (such as REGALREZ® 1018) exhibits infinitesimal oil bleed at room temperature, if any,  
9 even when placed against materials with high capillary action, such as paper. Prior art  
10 thermoplastic elastomers bleed noticeably under these circumstances.

11 The plasticizer:block copolymer elastomer ratio, by total combined weight of the  
12 plasticizer component and the block copolymer elastomer component, of the preferred gel  
13 cushioning material for use in the cushions of the present invention ranges from as low as about  
14 1:1 or less to higher than about 25:1. In applications where plasticizer bleed is acceptable, the  
15 ratio may as high as about 100:1 or more. Especially preferred are plasticizer:block copolymer  
16 ratios in the range of about 2.5:1 to about 8:1. A preferred ratio, such as 5:1 provides the desired  
17 amounts of rigidity, elasticity and strength for many typical applications. Another preferred  
18 plasticizer to block copolymer elastomer ratio of the preferred gel material is 2.5:1, which has an  
19 unexpectedly high amount of strength and elongation.

#### 20 **4. Compounding Methods**

21 As used herein, the term "liquification" refers to the placement of the block copolymer

1 elastomer and plasticizer components of the preferred gel cushioning medium in a liquid state,  
2 such as a molten state or a dissolved state.

3 *a. Melt Blending*

4 A preferred method for manufacturing the preferred gel material includes mixing the  
5 plasticizer, block copolymer elastomer and any additives and/or fillers (e.g., microspheres),  
6 heating the mixture to melting while agitating the mixture, and cooling the compound. This  
7 process is referred to as "melt blending."

8 Excessive heat is known to cause the degradation of the elastomeric B portion of A-B-A  
9 and A-B block copolymers which are the preferred elastomer component of the preferred gel  
10 material for use in the cushions of the present invention. Similarly, maintaining block  
11 copolymers at increased temperatures over prolonged periods of time often results in the  
12 degradation of the elastomeric B portion of A-B-A and A-B block copolymers. As the B  
13 molecules of an A-B-A triblock copolymer break, the triblock is separated into two diblock  
14 copolymers having the general configuration A-B. While it is believed by some in the art that  
15 the presence of A-B diblock copolymers in oil-containing plasticizer-extended A-B-A triblock  
16 copolymers reduces plasticizer bleed-out, high amounts of A-B copolymers significantly reduce  
17 the strength of the preferred gel material. Thus, Applicant believes that it is important to  
18 minimize the compounding temperatures and the amount of time to which the material is  
19 exposed to heat.

20 The plasticizers, any additives and/or fillers, and the A-B-A copolymers are premixed.

21 Preferably, if possible, hydrophobic additives are dissolved into the plasticizer prior to adding the

1 plasticizer component to the elastomer component. If possible, hydrophilic additives and  
2 particulate additives are preferably emulsified or mixed into the plasticizer of a preferred gel  
3 material prior to adding the elastomer components. The mixture is then quickly heated to  
4 melting. Preferably, the temperature of the mixture does not exceed the volatilization  
5 temperature of any component. For some of the preferred gel materials, Applicant prefers  
6 temperatures in the range of about 270°F. to about 290°F. For other gel materials, Applicant  
7 prefers temperatures in the range of about 360°F. to about 400°F. A melting time of about ten  
8 minutes or less is preferred. A melting time of about five minutes or less is more preferred.  
9 Even more preferred are melting times of about ninety seconds or less. Stirring, agitation, or,  
10 most preferably, high shearing forces are preferred to create a homogeneous mixture. The  
11 mixture is then cast, extruded, injection molded, etc.

12 Next, the mixture is cooled. When injection molding equipment and cast molds are used,  
13 the mixture may be cooled by running coolant through the mold, by the thermal mass of the mold  
14 itself, by room temperature, by a combination of the above methods, or other methods. Extruded  
15 mixtures are cooled by air or by passing the extruded mixture through coolant. Cooling times of  
16 about five minutes or less are preferred. A cooling time of less than one minute is most  
17 preferred.

18 Use of high shear facilitates short heating times. "High shear", for purposes of this  
19 disclosure, is defined in terms of the length over diameter (L/D) ratio of a properly designed  
20 injection molding single screw or extruder single screw. L/D ratios of about 20:1 and higher  
21 create high shear. Twin screws, Banbury mixers and the like also create high shear. High

1 shearing with heat mixes compounds at lower temperatures and faster rates than the use of heat  
2 alone or heat with relatively low-shear mixing. Thus, high shear forces expedite compounding of  
3 the mixture over a relatively short period of time by more readily forcing the molecules into  
4 close association with the B component of the A-B-A copolymer. Use of high shear also  
5 facilitates the decrease of equipment temperatures. Melt blending techniques which employ little  
6 or no shear require an external heat source. Thus, in order to avoid heat loss, the periphery of  
7 many types of melt blending equipment must be heated to a temperature higher than the melt  
8 temperature in order to transfer heat and melt a component mixture. In comparison, high  
9 shearing equipment can generate high material temperatures directly from the shear forces,  
10 substantially reducing or eliminating the need for external heating.

11 The inventor prefers the use of equipment that produces high shear, such as twin screw  
12 compounding extrusion machinery, to melt blend the preferred gel cushioning medium. Twin  
13 screw extruders such as the ZE25 TIEBAR AIR COOLED TWIN SCREW EXTRUDER, with a  
14 35:1 L/D ratio, manufactured by Berstorff Corporation of Charlotte, North Carolina, are useful  
15 for compounding the preferred gel material. Twin screw compounding extrusion machinery is  
16 desired for compounding the preferred gel material since it generates a very high level of shear  
17 and because compounding and molding, casting, extrusion, or foaming are performed in one  
18 continuous process. Alternatively, the preferred thermoplastic elastomeric may be compounded  
19 first, then later formed into a finished product by injection molding, extrusion, or some other  
20 method.

21 It was mentioned above that microspheres may be added to the gel material to reduce its

1 specific gravity and to increase its stiffness or durometer. Applicant has unexpectedly  
2 discovered that acrylic microspheres remain intact when subjected to the heat and shear of  
3 injection molding machines and extruders if the time at high temperature is kept to about five  
4 minutes or less.

5 Other equipment, such as batch mixers are also useful for melt blending the preferred gel  
6 materials for use in the cushions according to the present invention.

7 *b. Solvent Blending*

8 A second preferred method for making the preferred elastomeric compounds comprises  
9 dissolving the elastomeric component in a solvent, adding the plasticizer component and any  
10 additives and/or fillers, and removing the solvent from the mixture.

11 Aromatic hydrocarbon solvents such as toluene may be used for mixing the preferred gel  
12 compounds. Sufficient solvent is added to the elastomer component to dissolve the network of  
13 block copolymer molecules. Preferably, the amount of solvent is limited to an amount sufficient  
14 for dissolving the network of block copolymer molecules. The elastomers then dissolve in the  
15 solvent. Mixing is preferred since it speeds up the solvation process. Similarly, slightly  
16 elevating the mixture temperature is preferred since it speeds up the solvation process. Next,  
17 plasticizer, any additives and any fillers are mixed into the solvated elastomer. If possible,  
18 hydrophobic additives are preferably dissolved in the plasticizer prior to adding the plasticizer to  
19 the principle polymer, the block copolymer elastomer and the solvent. Preferably, if possible,  
20 hydrophilic additives and particulate additives are emulsified or mixed into the plasticizer prior  
21 to adding the elastomer components and solvent. The mixture is then cast into a desired shape

1 (accounting for later shrinkage due to solvent loss) and the solvent is evaporated from the  
2 mixture.

3 Other methods of compounding the preferred materials, including but not limited to other  
4 processes for compounding, modifying and extending elastomeric materials, are also useful for  
5 compounding the preferred gel cushioning medium.

6 *c. Foaming*

7 The preferred gel material may be foamed. "Foaming", as defined herein, refers to  
8 processes which form gas bubbles or gas pockets in the material. A preferred foamed gel  
9 material that is useful in the cushions of this invention includes gas bubbles dispersed throughout  
10 the material. Both open cell and closed cell foaming are useful in the preferred gel material.  
11 Foaming decreases the specific gravity of the preferred material. In many cushioning  
12 applications, very low specific gravities are preferred. The specific gravity of the gel material  
13 may range, after foaming, from about 0.06 to about 1.30.

14 A preferred foamed formulation of the gel material includes at least about 10% gas  
15 bubbles or gas pockets, by volume of the material. More preferably, when the material is  
16 foamed, gas bubbles or gas pockets make up at least about 20% of the volume of the material.  
17 Other foamed formulations of the preferred gel material contain at least about 40% gas bubbles  
18 or gas pockets, by volume, and at least about 70% gas bubbles or pockets, by volume.

19 Various methods for foaming the preferred gel material include, but are not limited to,  
20 whipping or injecting air bubbles into the material while it is in a molten state, adding  
21 compressed gas or air to the material while it is in the molten state and under pressure, adding



1 water to the material while it is in the molten state, use of sodium bicarbonate, and use of  
2 chemical blowing agents such as those marketed under the brand name SAFOAM® by Reedy  
3 International Corporation of Keyport, New Jersey and those manufactured by Boehringer  
4 Ingelheim of Ingelheim, Germany under the trade name HYDROCEROL®.

5 When blowing agents such as sodium bicarbonate and chemical blowing agents are used  
6 in the preferred gel material, the material temperature is preferably adjusted just prior to addition  
7 of the blowing agent so that the material temperature is just above the blowing temperature of the  
8 blowing agent. Following addition of the blowing agent to the material, the material is allowed  
9 to cool so that it will retain the gas bubbles or gas pockets formed by the release of gas from the  
10 blowing agent. Preferably, the material is quickly cooled to a temperature below its  $T_g$ . The  
11 material will retain more gas bubbles and the gas bubbles will be more consistently dispersed  
12 throughout the material the quicker the material temperature cools to a temperature below the  $T_g$ .

13 When a preferred gel material is injection molded in accordance with one preferred  
14 compounding method of the gel material, foaming is preferred just after the material has been  
15 injected into a mold. Thus, as the material passes through the injection molding machine nozzle,  
16 its temperature is preferably just higher than the blowing temperature of the blowing agent.  
17 Preferably, the material is then cooled to a temperature below its  $T_g$ .

18 Addition of polyisobutylene resin improves the ability of the preferred gel material to  
19 foam and retain cells during the foaming process. One such resin, known as VISTANEX® LM-  
20 MS, is manufactured by Exxon Chemical Company. Similarly, surfactants, dispersants and  
21 emulsifiers such as Laureth-23, available from Lonza of Fair Lawn, New Jersey under the trade

1 name ETHOSPERSE LA-23, and others may be used to facilitate foaming of the gel material. In  
2 formulations which include oil, certain foaming oils such as Hydraulic and Transmission Oil,  
3 such as that made by Spectrum Corp. of Selmer, Tennessee, may also be used in the material to  
4 facilitate foaming of the materials.

5 Additives which modify the gas permeability of the preferred gel material are preferred  
6 when the material is foamed. One such material, manufactured by Rohm & Haas Company of  
7 Philadelphia, Pennsylvania and marketed under the trade name PARALOID® K 400, modifies  
8 the gas permeability of the preferred gel material, facilitating the material's ability to hold gas  
9 bubbles.

10 When foaming is desired, additives which increase the melt viscosity or melt body of the  
11 material are also useful. One such additive, PARALOID® K 400, is believed to increase the  
12 melt viscosity of the material, making it more difficult for gas bubbles to escape from the  
13 material as it cools. Another additive, ACRYLOID® F-10, manufactured by Rohm & Haas, is  
14 also believed to improve the ability of the material to entrap bubbles.

15 Another additive, ethylene vinyl acetate (EVA) crosslinks with itself and/or other  
16 molecules to increase the internal structure of the material, while reducing the material's melt  
17 viscosity. Thus, EVA is also believed to improve the gas bubble retention of the material. EVA  
18 is available from a variety of sources. High viscosity plasticizers, including without limitation  
19 DUOPRIME 500, are also believed to facilitate gas bubble retention.

20 Additives which act as nucleating agents are also useful for foaming the preferred gel  
21 material. Such additives are helpful in initiating the formation of gas bubbles. Applicant

believes that antioxidants, including but not limited to IRGANOX® 1010 and IRGAFOS® 168, act as nucleating agents during foaming of the material. Blowing agents such as those sold under the trade name SAFOAM® by Reedy International are also believed to have a secondary function as nucleating agents. Examples of other nucleating agents include talc, carbon black, aluminum stearate, hydrated alumina, titanium dioxide, aluminum lake colorants, and others.

Referring now to Figures 40a and 40b, a preferred embodiment of a method for foaming the preferred gel cushioning material is shown. Figure 40a illustrates the preferred embodiment of the foaming method using an extruder 4001. Figure 10b shows the preferred embodiment of the foaming method in an injection molding machine 4001'. Preferably, the gel cushioning medium includes a blowing agent such as SAFOAM® FP-40, which is added to the non-liquid components of the cushioning medium prior to processing. About half of the plasticizer component is then added to the non-liquid components, which are then fed into extruder 4001 or injection molding machine 4001'. The remaining plasticizer is added to the mixture at 4003, 4003' as the mixture moves along the barrel 4004, 4004', which houses the screw or screws. Pressurized carbon dioxide (CO<sub>2</sub>), which is contained in a CO<sub>2</sub> source 4008, 4008' such as a pressurized cannister, is then injected into the barrel. The CO<sub>2</sub> is injected into the mixture near the end of the barrel 4004, 4004', after a seal 4006, 4006' and just before the nozzle 4007, 4007'. Preferably, a pumping mechanism 4009, 4009' such as a stepping pump, which are widely used in the industry, is used to increase the pressure in barrel 4004, 4004'. The material is then discharged through nozzle 4007, 4007'.

Referring to Figure 40a, when an extruder 4001 is used to compound and foam the

1 preferred gel cushioning medium, a gear pump 4010, which is preferably positioned at the end of  
2 nozzle 4007, controls the amount of pressure in barrel 4004 and inhibits a drop in pressure at the  
3 nozzle. As the material is discharged from pump 4010 at 4011, the CO<sub>2</sub> expands, which  
4 introduces gas bubbles into the material and foams the material.

5 With reference to Figure 40b, when an injection molding machine 4001' is used to  
6 compound and foam the preferred gel material, an accumulator positioned just before nozzle  
7 4007' increases the material pressure. Following discharge from nozzle 4007', the material  
8 passes through a heat exchanger 4012 and into the cavity (not shown) of a mold 4013.  
9 Preferably, the CO<sub>2</sub> begins to expand and form gas bubbles in the material as the material fills  
10 the mold cavity.

11 Preferably, the CO<sub>2</sub> and the material are maintained at a pressure of at least about 700 psi  
12 just prior to entering the gear pump at the extrusion end of the barrel. More preferably, the  
13 material and CO<sub>2</sub> reach a pressure of at least about 900 psi. Most preferably, the CO<sub>2</sub> and  
14 material are subjected to a pressure of at least about 1,700 psi. At pressures of about 1,700 psi  
15 and greater, CO<sub>2</sub> acts as a supercritical fluid.

16 At such high pressure, the liquid CO<sub>2</sub> solvates the block copolymer and principle  
17 polymer, which decreases the T<sub>g</sub> of the mixture. Thus, as pressure is released upon extrusion of  
18 the mixture from the nozzle, the CO<sub>2</sub> immediately becomes a gas and the mixture immediately  
19 crosses its T<sub>g</sub>. In other words, as gas bubbles are forming in the material, the material begins to  
20 solidify. Thus, the number of gas bubbles retained in the material is increased. CO<sub>2</sub> bubbles are  
21 believed to form around the SAFOAM®, which is believed to act as a nucleating agent.

1 The expansion rate of the CO<sub>2</sub> bubbles and the solidification rate of the mixture are  
2 varied, depending upon the particular formulation of the material. Various other factors also  
3 affect how a material will foam, including the rate at which material is fed into the barrel (the  
4 “feed rate”), the length of time the material is in the barrel (the “residence time”), the speed at  
5 which the screw or screws rotate (the “screw rpm”), the relative direction each screw rotates and  
6 others.

7 In addition, properties of the material affect the foaming process. The amount of  
8 plasticizer affects a material’s ability to foam. For example, when the plasticizer is an oil,  
9 materials which include increased amounts of plasticizer do not foam as readily as similar  
10 materials with less plasticizing oil. Applicant believes that as the amount of plasticizing oil in a  
11 material increases, gas bubbles tend to more readily escape from the material.

#### 12 *d. Lattice Structures*

13 Lattice structures may be made using the preferred gel material, which is incorporated  
14 into the cushion configurations according to the present invention. Such lattice structures  
15 include multiple overlaid streams of the gel material in a lattice-like arrangement. Preferably, the  
16 streams of material have a thickness of less than about one-tenth of an inch.

17 Formation of the gel material into lattice structures decreases the specific gravity of the  
18 material due to the free space created within the lattice structure. Preferably, lattice structures  
19 reduce the specific gravity of the material by at least about 50%.

20 One method of forming lattice structures includes heating the material to a molten state  
21 and spraying streams of the material to form a desired lattice structure. Preferably, a hot melt

1 adhesive spray gun, such as the FP-200 Gun System manufactured by Nordson Corporation of  
2 Amherst, Ohio, is used to spray streams of the preferred gel cushioning material to form a lattice  
3 structure.

4 *e. Premixing of Microspheres*

5 In formulations of the preferred material for use in the cushioning elements of this  
6 invention which include microspheres, premixing the microspheres with the plasticizer prior to  
7 adding the plasticizer to the elastomeric block copolymer and the polyolefin may result in a more  
8 uniform mixture (i.e., a better final product) and makes the microsphere-containing gel material  
9 easier to process. For example, the materials may be premixed by hand.

10 *f. Pre-manufacture of Pellets*

11 In some embodiments of the invention, it will be preferred to prepare pelletized  
12 gelatinous elastomer material for later use in manufacturing cushioning devices or other devices.  
13 The pelletized gelatinous elastomer could be of any formulation described herein or otherwise,  
14 and could contain any desired additives. The pellets could be produced by first compounding the  
15 material and forming it into pellets for later use in an appropriate manufacturing process.

16 **5. Representative Elastomeric Gel Physical Properties and Formulations**

17 When the preferred A-B-A triblock copolymer, plasticizer and additives are mixed, the  
18 resultant material is very strong, yet very elastic and easily stretched, having a Young's elasticity  
19 modulus of only up to about  $1 \times 10^6$  dyne/cm<sup>2</sup>. The preferred elastomeric gel material for use in  
20 the cushioning elements of this invention also has low tack and little or no oil bleed, both of  
21 which are believed to be related to the molecular weight of the uniquely preferred elastomers as

1 well as the molecular structure of the elastomer and its interaction with  
2 the plasticizing component. Finally, the preferred elastomeric gel cushioning medium is capable  
3 of elongation up to about 2400% and more.

#### 4 **EXAMPLES**

5 Examples 1 through 14 include various mixtures of SEPTON 4055 (available from  
6 Kuraray) ultra high molecular weight polystyrene-hydrogenated poly(isoprene + butadiene)-  
7 polystyrene triblock copolymer extended in a plasticizing oil. In addition, the materials of  
8 Examples 1 through 14 include very minor amounts of IRGANOX® 1010 (about 0.03%),  
9 IRGAFOS® 168 (about 0.03%), and colorant (about 0.04%).

10 The material of each of Examples 1 through 14 was compounded in an ISF 120VL  
11 injection molding machine, manufactured by Toshiba Machine Co. of Tokyo, Japan, with a 20:1  
12 (L/D) high mixing single screw manufactured by Atlantic Feed Screw, Inc. of Cayce, South  
13 Carolina. The temperature in the injection molding machine was increased stepwise from the  
14 point of insertion to the injection nozzle. At the point of insertion, the temperature was about  
15 270°F. Temperatures along the screw were about 275°F. and about 280°F., with the temperature  
16 increasing as the material approached the injection nozzle. The temperature at the injection  
17 nozzle was about 290°F. This gradual increase in temperature builds up pressure during feeding  
18 of the material through the injection molding machine, providing a more homogeneous mixture  
19 of the components of the material.

20 Each of the formulations of Examples 1 through 11 were then injected into an aluminum  
21 plaque mold and allowed to cure at room temperature for about 24 hours to about 48 hours.

1    Thereafter, various tests were performed on the materials, including percent elongation, tensile  
2    strength at break, and percent oil bleed.

3            Percent elongation and tensile strength testing were performed in accordance with  
4    American Society for Testing and Materials (ASTM) Standard Test Method D412, using a  
5    Model QC-II-30XS-B Electronic Tensile Tester manufactured by Thwing Albert Instrument Co.  
6    of Philadelphia, Pennsylvania. Each of samples were O-shaped rings with an outer diameter of  
7    about 0.500 inch, an inner diameter of about 0.375 inch, a gauge diameter of about 0.438 inch,  
8    and a mean circumference of about 1.374 inches. Five samples of each material were tested for  
9    elongation and tensile strength.

10           Percent oil bleed was measured by obtaining the combined weight of three disk-shaped  
11    samples of the material, each sample having diameter of about 3 cm and a thickness of about 6.5  
12    mm. Two pieces of 12.5 cm diameter qualitative filter paper having a medium filter speed and  
13    an ash content of about 0.15%, such as that sold under the trade name DOUBLE RINGS 102,  
14    and manufactured by Xinhua Paper Mill, were then weighed individually.

15           The three sample disks were then placed on one of the pieces of filter paper (which has  
16    high capillary action), and the other piece of filter paper was placed on top of the samples. The  
17    material and paper were then placed in a plastic bag and pressure-sandwiched between two flat  
18    steel plates, each weighing within about 0.5% of about 2285g. Next, the material samples, paper  
19    and steel plates were placed in a freezer at about -4°C. for about 4 hours.

20           Oil bleed testing was conducted at a low temperature because rubber molecules are  
21    known to constrict at low temperatures. Thus, in theory, when a plasticized material is subjected



1 to cooler temperatures, the attraction of plasticizer to Vander Waals binding sites on the rubber  
2 molecules decreases. Therefore, it has been theorized that plasticizer-extended materials tend to  
3 bleed more at lower temperatures. However, oil tends to flow more slowly at low temperatures,  
4 suggesting that this theory may not be accurate. Nevertheless, this theory has been widely  
5 accepted. The extreme condition of the pressure and the freezer was needed for quantitative  
6 evaluation since the preferred elastomeric gel materials have the advantage over prior art gel  
7 materials of not bleeding at all at room temperature without pressure, even when placed next to  
8 high capillary action paper. Although John Y. Chen did not report oil bleed in his patents or  
9 patent applications, Applicant's experience is that Chen's materials have a higher level of oil  
10 bleed than the preferred elastomeric gel cushioning medium.

11 Upon removal from the freezer, each piece of the filter paper and the samples were  
12 immediately weighed again. Percent oil bleed was then calculated by determining the combined  
13 weight increase of the filter papers, dividing that value by the original sample weight and  
14 multiplying the result by 100.

#### 15 EXAMPLE 1

16 The material of Example 1 includes eight parts LP 150 mineral oil to one part SEPTON  
17 4055.

8:1	Average	High Value
Percent Elongation	2375	2400
PSI at Failure	185	190

18  
19 In comparison, the material of Chen's patents that has an oil to elastomer ratio of 4:1,  
20 which should have higher strength than Applicant's 8:1 material of Example 1, instead exhibits

1 much lower elongation and PSI at failure (i.e., tensile strength) values. The material of Example  
2 1 elongates up to about 2,400%, which is 700% greater elongation than Chen's 4:1, which is  
3 capable of only 1700% elongation (*See, e.g.*, '213 Patent, Table I, col. 6, lines 18-38). Likewise,  
4 the tensile strength at break of Chen's 4:1 gel is only about  $4 \times 10^6$  dyne/cm<sup>2</sup>, or 58 psi. Thus,  
5 the 8:1 material of Example 1 is at least three times as strong as Chen's 4:1. This is an  
6 unexpectedly good result since the conventional wisdom concerning gels is that more oil results  
7 in less strength. Applicant doubled the amount of oil used (8:1 compared to 4:1) but achieved  
8 more than three times the tensile strength of Chen's material.

#### EXAMPLE 2

9 The material of Example 2 includes five parts LP 150 mineral oil to one part SEPTON  
10 4055.

5:1	Average	High Value
Percent Elongation	1975	2030
PSI at Failure	335	352

11  
12  
13 A comparison of the 5:1 material of Example 2 to the 4:1 material of Chen's patents  
14 shows that Chen's material exhibits much lower elongation and PSI at failure (i.e., tensile  
15 strength) values. The material of Example 2 elongates up to about 2,000%, which is about 300%  
16 more than Chen's 4:1, which is capable of only 1700% elongation (*See, e.g.*, '213 Patent, Table  
17 I, col. 6, lines 18-38). Likewise, the tensile strength at break of Chen's 4:1 gel is only about  $4 \times$   
18  $10^6$  dyne/cm<sup>2</sup>, which translates to only about 58 psi. Thus, the 5:1 material of Example 2, despite  
19 the presence of about 25% more oil than Chen's 4:1 material, is about five-and-a-half times as  
20 strong as Chen's 4:1.

1 EXAMPLE 3

2 The material of Example 3 includes three parts LP 150 mineral oil to one part SEPTON  
3 4055.

3:1	Average	High Value
Percent Elongation	1555	1620
PSI at Failure	404	492

4 A consideration of both Example 2, a material having a 5:1 oil to elastomer ratio, and  
5 Example 3, a material having a 3:1 oil to elastomer ratio, indicates that a material with a 4:1 oil  
6 to elastomer ratio would compare very favorably to the gel disclosed in U.S. Patent No.  
7 5,508,334, which issued in the name of John Y. Chen. According to Table I in the '334 patent,  
8 Chen's 4:1 KRATON® G-1651-containing material had a breaking strength (i.e., tensile  
9 strength) value of  $4 \times 10^6$  dyne/cm<sup>2</sup>, which translates to only about 58 psi.  
10

11 The elongation at break value was mysteriously omitted from Table I of the '334 patent  
12 and other Chen patents. However, reference to Table I of Chen's first two issued patents (the  
13 '284 and '213 patents) sets the percent elongation of Chen's 4:1 material at about 1700.  
14 Applicant suspects that Chen omitted this data in later patent applications because it was either  
15 inaccurate or Chen's improved materials failed to exhibit improved properties over his earlier  
16 materials.

17 In comparison, the percent elongation of a 4:1 preferred elastomeric gel material for use  
18 in the cushions of the present invention would be at least about 1800, exceeding the elongation of  
19 Chen's 4:1 material by about 100% or more. Similarly, the tensile strength of a 4:1 material  
20 preferred for use in the cushions of this invention would be at least about 350 psi, and probably

1 in the 370 to 375 psi range. Thus, a preferred elastomeric gel cushioning medium for use in the  
2 cushions of the present invention with an oil to elastomer ratio of about 4:1 would be about six  
3 times as strong as Chen's most preferred 4:1 gel.

4 The following Examples 4 through 11 have been included to demonstrate the usefulness  
5 of various plasticizing oils in the preferred elastomeric gel material.

#### 6 EXAMPLE 4

7 The material of Example 4 included eight parts of a plasticizer mixture to one part  
8 SEPTON 4055. The eight parts plasticizer mixture included about 5.3 parts REGALREZ® 1018  
9 and about 2.8 parts DUOPRIME® 90 mineral oil.

8:1	Average	High Value
Percent Elongation	2480	2520
PSI at Failure	187	195

#### 12 EXAMPLE 5

13 The material of Example 5 included eight parts of EDELEX® 27 oil to one part SEPTON  
14 4055. EDELEX® 27 has an aromatic content of about 1%, which would be expected to slightly  
15 decrease the tensile strength of the material.

8:1	Average	High Value
Percent Elongation	2105	2150
PSI at Failure	144	154
Percent oil bleed	0.34	

#### 18 EXAMPLE 6

19 The material of Example 6 included eight parts of DUOPRIME® 55 mineral oil to one  
20 part SEPTON 4055.

<b>8:1</b>	<b>Average</b>	<b>High Value</b>
Percent Elongation	1940	2055
PSI at Failure	280	298
Percent oil bleed	0.29	

#### EXAMPLE 7

The material of Example 7 included eight parts of DUOPRIME® 70 mineral oil to one part SEPTON 4055.

<b>8:1</b>	<b>Average</b>	<b>High Value</b>
Percent Elongation	2000	2030
PSI at Failure	250	275
Percent oil bleed	0.41	

#### EXAMPLE 8

The material of Example 8 included eight parts of DUOPRIME® 90 mineral oil to one part SEPTON 4055.

<b>8:1</b>	<b>Average</b>	<b>High Value</b>
Percent Elongation	2090	2125
PSI at Failure	306	311
Percent oil bleed	0.35	

#### EXAMPLE 9

The material of Example 9 included eight parts of DUOPRIME® 200 mineral oil to one part SEPTON 4055.

<b>8:1</b>	<b>Average</b>	<b>High Value</b>
Percent Elongation	1970	2040
PSI at Failure	200	228
Percent oil bleed	0.20	

#### EXAMPLE 10

1 The material of Example 10 included eight parts of DUOPRIME® 350 mineral oil to one  
2 part SEPTON 4055.

8:1	Average	High Value
Percent Elongation	2065	2080
PSI at Failure	267	270
Percent oil bleed	0.21	

#### EXAMPLE 11

3 The material of Example 11 included eight parts of DUOPRIME® 500 mineral oil to one  
4 part SEPTON 4055.

8:1	Average	High Value
Percent Elongation	1995	2075
PSI at Failure	194	223
Percent oil bleed	0.17	

#### EXAMPLE 12

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	227.0
Duoprime 500 oil	Plasticizing oil	2,722.0
Irganox 1010	Antioxidant	4.5
Irgafos 168	Antioxidant	4.5
Safoam FP-40	Foaming agent	14.0
Lamp Black	Colorant and Foam Bubble Nucleating Agent	1.5

5 Applicant began foaming the preferred elastomeric gel material to reduce its specific  
6 gravity by heating it until the SAFOAM began to degenerate and create CO<sub>2</sub> gas. DUOPRIME  
7 500 oil was selected for use in the example because of its high viscosity (i.e., it would help hold  
8 a bubble longer than a lower viscosity oil). The components were compounded in an injection  
9 molding machine according to one preferred melt blending method. The original mixture

1 included 3.40g SAFOAM. When half of the SAFOAM appeared to have been consumed, 3.40g  
2 more was added. Another 7.20g of SAFOAM was added when half of the SAFOAM again  
3 appeared to have been consumed. Temperatures along the injection molding screw ranged from  
4 about 280°F. at the point of insertion to about 240°F. at the nozzle. The material of Example 12  
5 had closed cells of fairly consistent density.

#### 6 EXAMPLE 13

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	227.0
Duoprim 500 oil	Plasticizing oil	2,722.0
Irganox 1010	Antioxidant	1.5
Irgafos 168	Antioxidant	1.5
Expacell DE-80	Microspheres	500.0
Orange	Colorant	2.0

7 Applicant has also used microspheres to reduce the specific gravity of the preferred  
8 elastomeric gel cushioning medium. Acrylic microspheres were used in the material of Example  
9 13. The components were premixed, then compounded in an injection molding machine screw.  
10 Temperatures along the injection molding screw ranged from about 260°F. at the point of  
11 insertion to about 220°F. at the nozzle. Surprisingly, the microspheres were not deformed by the  
12 high shear and high temperatures of the injection molding machine. The resulting material was  
13 very light, with microspheres consistently dispersed therethrough.  
14

#### 15 EXAMPLE 14

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	114.0
Kraton G-1701	A-B copolymer	5.8
Regalrez 1018	Plasticizing resin	340.0
Edelex 45	Plasticizing oil	225.0
Talc	Talc	20.4
Vestnamer 8012	Tor rubber	11.5
Expacell DU-80	Microspheres	0.5

Safoam FP-40	Foaming agent	10.0
Irganox 1010	Antioxidant	3.0
Irgafos 168	Antioxidant	3.0
Boiled Linseed Oil		8.0
Green	Colorant	2.0

In the material of Example 14, Applicant used KRATON® G-1701, manufactured by Shell Chemical Co., to reduce oil bleed. REGALREZ® 1018 was used as a plasticizer and to reduce oil bleed from the material. Talc was included in the material of Example 14 to act as a nucleating agent during foaming of the material. Since talc migrates to the surface of the material, it is also useful as a surface detackifier. Talc may also be used as a filler in the material. VESTENAMER 8012, sold by Hüls America Inc. of Piscataway, New Jersey, is a transpolyoctylene rubber (tor) which is useful for reducing oil bleed and reducing melt viscosity of the preferred elastomeric gel material. Boiled linseed oil is believed to reduce the melt viscosity and tackiness of the material and to accelerate the migration of particulate matter to the material's surface. Applicant used both microspheres and foaming agents in the material of Example 14. Although acrylic microspheres reduce the specific gravity of the preferred elastomeric gel material, they increase the stiffness of the material, though not as much as glass, ceramic, or other rigid microspheres would.

The closed cell foaming and the microsphere dispersion of the material of Example 14 were consistent. The material was soft and light-weight. The components were well compounded. In addition, the material of Example 14 did not have an oily feel and exhibited no plasticizer bleedout at room temperature.

Additives such as colorants, flame retardants, detackifiers and other additives may be



1 included in the preferred elastomeric gel cushioning medium. Various formulations of the  
2 preferred elastomeric gel material may be tailored to achieve differing levels of softness,  
3 strength, tackiness and specific gravity as desired. Examples 1 through 11 illustrate the  
4 surprisingly high elongation and tensile strength of the material. Many embodiments of the  
5 preferred elastomeric material, of which the preceding examples are representative, exhibit  
6 physical properties vastly superior to those of John Y. Chen's material, which Applicant believes  
7 to be the closest and best prior art. A chemical explanation for the superior results is provided  
8 below.

9 Examples 15 through 35 are other formulations of the preferred elastomeric gel  
10 cushioning medium for use in the cushions according to the present invention. The formulations  
11 of Examples 15 through 35 were compounded using a ZE25 TIEBAR AIR COOLED TWIN  
12 SCREW EXTRUDER with a 35:1 L/D ratio according to a preferred melt blending method.  
13 Temperatures along the screws were in the range of about 130°C to about 170°C at the hopper to  
14 about 100°C to about 130°C at the nozzle.

#### 15 EXAMPLE 15

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	50.04
LP-150	Plasticizing oil	250.0
Irganox 1010	Antioxidant	1.5
Irgafos 168	Antioxidant	1.5

#### 17 EXAMPLE 16

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	83.25
LP-150	Plasticizing oil	250.00
Irganox 1010	Antioxidant	1.5

Irgafos 168	Antioxidant	1.5
-------------	-------------	-----

#### EXAMPLE 17

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	50.04
Kadol	Plasticizing oil	250.00
E 17	Antioxidant (vitamin E)	6.26

#### EXAMPLE 18

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	250.00
Duoprime 90	Plasticizing oil	1,250.00
E 17	Antioxidant (vitamin E)	6.30

#### EXAMPLE 19

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	250.00
LP-150	Plasticizing oil	1,250.00
E 17	Antioxidant (vitamin E)	6.25

#### EXAMPLE 20

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	350.00
Regalrez 1018	Plasticizing resin	262.51
C23 to C27 Alkane Wax	Plasticizer	35.00
LP-150	Plasticizing oil	287.60
E 17	Antioxidant (vitamin E)	14.00
Ethospense		52.50
White	Colorant	10.50
Yellow	Colorant	0.70
Red	Colorant	0.03

#### EXAMPLE 21

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	11.89

KRATON® G 1701	Diblock copolymer	0.24
LP-150 mineral oil	Plasticizer	73.87
Astor Slack Wax 2050	Plasticizer	8.33
Alkane Wax C 25-27	Plasticizer	0.59
IRGANOX® 1010	Antioxidant	0.42
IRGAFOS® 168	Antioxidant	0.42
IRGANOX® E17	Antioxidant	0.42
TETRAGLYME	Anti-bleed, anti-tack additive	1.19
PQ 6546	Acrylic Microspheres	1.44
Rocket Red	Colorant	1.19

#### EXAMPLE 22

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	14.86
KRATON® G 1701	Diblock copolymer	0.30
LP-150 mineral oil	Plasticizer	71.01
Astor Slack Wax 2050	Plasticizer	6.69
Alkane Wax C 25-27	Plasticizer	0.58
IRGANOX® 1010	Antioxidant	0.52
IRGAFOS® 168	Antioxidant	0.52
IRGANOX® E17	Antioxidant	0.52
TETRAGLYME	Anti-bleed, anti-tack additive	1.34
PQ 6546	Acrylic Microspheres	1.44
Rocket Red	Colorant	2.23

#### EXAMPLE 23

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	16.66
KRATON® G 1701	Diblock copolymer	0.33
LP-150 mineral oil	Plasticizer	67.48
Astor Slack Wax 2050	Plasticizer	7.50
Alkane Wax C 25-27	Plasticizer	0.67
IRGANOX® 1010	Antioxidant	0.58
IRGAFOS® 168	Antioxidant	0.58
IRGANOX® E17	Antioxidant	0.58
TETRAGLYME	Anti-bleed, anti-tack additive	1.50
PQ 6546	Acrylic Microspheres	1.62
Rocket Red	Colorant	2.50

#### EXAMPLE 24

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	13.18
KRATON® G 1701	Diblock copolymer	0.26
LP-150 mineral oil	Plasticizer	75.12

Astor Slack Wax 2050	Plasticizer	5.27
Alkane Wax C 25-27	Plasticizer	0.33
IRGANOX® 1010	Antioxidant	0.46
IRGAFOS® 168	Antioxidant	0.46
IRGANOX® E17	Antioxidant	0.46
TETRAGLYME	Anti-bleed, anti-tack additive	1.19
PQ 6546	Acrylic Microspheres	1.62
Horizon Blue	Colorant	1.65

#### EXAMPLE 25

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	11.07
KRATON® G 1701	Diblock copolymer	0.22
LP-150 mineral oil	Plasticizer	76.89
Astor Slack Wax 2050	Plasticizer	5.54
Alkane Wax C 25-27	Plasticizer	0.55
IRGANOX® 1010	Antioxidant	0.39
IRGAFOS® 168	Antioxidant	0.39
IRGANOX® E17	Antioxidant	0.39
Amyl Formate (supplied by Aldrich)	Clarity enhancer	0.55
TETRAGLYME	Anti-bleed, anti-tack additive	1.66
PQ 6546	Acrylic Microspheres	0.97
Horizon Blue	Colorant	1.38

#### EXAMPLE 26

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	14.40
KRATON® G 1701	Diblock copolymer	0.29
LP-150 mineral oil	Plasticizer	74.50
Astor Slack Wax 2050	Plasticizer	4.80
Alkane Wax C 25-27	Plasticizer	0.50
IRGANOX® 1010	Antioxidant	0.50
IRGAFOS® 168	Antioxidant	0.50
IRGANOX® E17	Antioxidant	0.50
TETRAGLYME	Anti-bleed, anti-tack additive	1.44
PQ 6546	Acrylic Microspheres	0.97
Signal Green	Colorant	1.58

#### EXAMPLE 27

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	13.37
KRATON® G 1701	Diblock copolymer	0.27
LP-150 mineral oil	Plasticizer	74.88

Astor Slack Wax 2050	Plasticizer	5.35
Alkane Wax C 25-27	Plasticizer	3.34
IRGANOX® 1010	Antioxidant	0.47
IRGAFOS® 168	Antioxidant	0.47
IRGANOX® E17	Antioxidant	0.47
TETRAGLYME	Anti-bleed, anti-tack additive	1.34
Amyl Formate	Clarity Enhancer	0.40
PQ 6546	Acrylic Microspheres	0.99
Signal Green	Colorant	1.47

#### EXAMPLE 28

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	8.14
KRATON® G 1701	Diblock copolymer	0.16
LP-150 mineral oil	Plasticizer	80.76
Astor Slack Wax 2050	Plasticizer	6.51
Alkane Wax C 25-27	Plasticizer	0.49
IRGANOX® 1010	Antioxidant	0.28
IRGAFOS® 168	Antioxidant	0.28
IRGANOX® E17	Antioxidant	0.28
TETRAGLYME	Anti-bleed, anti-tack additive	1.22
PQ 6546	Acrylic Microspheres	0.97
Blaze Orange	Colorant	0.90

#### EXAMPLE 29

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	8.12
KRATON® G 1701	Diblock copolymer	0.16
LP-150 mineral oil	Plasticizer	80.60
Astor Slack Wax 2050	Plasticizer	6.50
Alkane Wax C 25-27	Plasticizer	0.49
IRGANOX® 1010	Antioxidant	0.28
IRGAFOS® 168	Antioxidant	0.28
IRGANOX® E17	Antioxidant	0.28
TETRAGLYME	Anti-bleed, anti-tack additive	1.22
Amyl Formate	Clarity Enhancer	0.20
PQ 6546	Acrylic Microspheres	0.97
Blaze Orange	Colorant	0.90

#### EXAMPLE 30

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	12.10
KRATON® G 1701	Diblock copolymer	0.30
LP-150 mineral oil	Plasticizer	84.47

IRGANOX® 1010	Antioxidant	0.18
IRGAFOS® 168	Antioxidant	0.18
FC-10 fluorochemical alcohol	Bleed-reducing additive	0.18
Strong Magenta	Colorant	0.36
Horizon Blue	Colorant	0.36
PQ 6545	Acrylic Microspheres	1.62

#### EXAMPLE 31

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	19.69
LP-150 mineral oil	Plasticizer	78.78
IRGANOX® 1010	Antioxidant	0.20
IRGAFOS® 168	Antioxidant	0.20
DYNAMAR® FX 9613	Bleed-reducing additive	0.15
091DU80	Acrylic Microspheres	0.98

#### EXAMPLE 32

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	19.60
LP-150 mineral oil	Plasticizer	78.39
IRGANOX® 1010	Antioxidant	0.19
IRGAFOS® 168	Antioxidant	0.20
DYNAMAR® FX 9613	Bleed-reducing additive	0.15
091DU80	Acrylic Microspheres	1.47

#### EXAMPLE 33

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	28.38
LP-150 mineral oil	Plasticizer	70.92
IRGANOX® 1010	Antioxidant	0.28
IRGAFOS® 168	Antioxidant	0.28
ZONYL® BA-N	Bleed-reducing additive	0.14

#### EXAMPLE 34

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	23.43
LP-150 mineral oil	Plasticizer	58.55
IRGANOX® 1010	Antioxidant	0.23
IRGAFOS® 168	Antioxidant	0.23
Carbowax	Plasticizer, includes polar molecules	17.56

### EXAMPLE 35

Component	Generic Class	Weight % of Total
SEPTON® 4055	Triblock copolymer	15.14
SEPTON® 4033	Triblock copolymer	3.79
LP-150 mineral oil	Plasticizer	80.45
IRGANOX® 1010	Antioxidant	0.19
IRGAFOS® 168	Antioxidant	0.19
ZONYL® BA-N	Bleed-reducing additive	0.15
Horizon Blue	Colorant	0.09

### 6. Representative Visco-Elastomeric Gel Formulations

The following examples have been prepared by Applicant.

### EXAMPLE 36

Component	Generic Class	Weight % of Total
Septon 4055	A-B-A copolymer	5.46
Kraton G1701	A-B copolymer	0.55
Irganox 1010	antioxidant	0.16
Irgafos 168	antioxidant	0.16
LP-150	plasticizing oil	32.77
Regalrez 1018	plasticizing resin	54.62
Kristalex 5140	strengthening resin	0.55
Regalite R101	plasticizing resin	2.73
Regalrez 1139	plasticizing resin	2.73
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.16
Bright orange aluminum lake	colorant	0.11

SEPTON® 4055 imparts form and strength to the visco-elastic material. KRATON® G-1701 is used to facilitate a more homogeneous blend of the elastomer (A-B-A copolymer) and plasticizer components. REGALREZ® 1018, a room temperature liquid plasticizer, is the primary plasticizer used in the material. REGALITE® R101 and REGALREZ® 1139 are also plasticizers and modify the tack of the visco-elastic material. KRISTALEX® 5140 is believed to impart strength to the styrene domains or centers of the A-B-A copolymer. It is also believed to

1 have some plasticizing abilities when used in combination with A-B-A copolymers.  
2 IRGANOX® 1010 and IRGAFOS® 168 are antioxidants. The material of Example 36 was  
3 made as an early experiment. Consequently, LP-150, a plasticizing oil, was used in combination  
4 with the resin plasticizers.

5 The material of Example 36 was prepared by premixing the components and melt  
6 blending them in an injection molding machine according to one preferred method for  
7 compounding the preferred gel cushioning medium. The material was very tacky and readily  
8 deformable, had very quick rebound and was very soft. Applicant believes that the very quick  
9 rebound rate is caused by the presence of plasticizing oil and microspheres. The specific gravity  
10 of the material was about 0.40.

#### 11 EXAMPLE 37

Component	Generic Class	Weight % of Total
Septon 8006	A-B-A copolymer	2.42
Septon 4055	A-B-A copolymer	2.42
Kraton G1701	A-B copolymer	0.48
Irganox 1010	antioxidant	0.15
Irgafos 168	antioxidant	0.15
Regalrez 1018	plasticizing resin	87.18
Kristalex 5140	strengthening resin	0.48
Regalite R101	plasticizing resin	2.42
Regalrez 1139	plasticizing resin	2.42
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	1.39
Bright orange aluminum lake	colorant	0.24
Dow Corning 200 silicone	rubber additive	0.24

12 In the material of Example 37, SEPTON® 8006 was used in combination with  
13 SEPTON® 4055 to provide some form, but a softer visco-elastic material. Silicone was added to  
14 detackify the material.  
15



The material of Example 37 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred method for compounding the preferred gel material. The material was slightly tacky and readily deformable, had slow rebound and moderate stiffness. The use of silicone seems to have decreased the tackiness of the material. The specific gravity of the material was about 0.30.

#### EXAMPLE 38

Component	Generic Class	Weight % of Total
Septon 8006	A-B-A copolymer	2.45
Septon 4055	A-B-A copolymer	2.45
Kraton G1701	A-B copolymer	0.49
Irganox 1010	antioxidant	0.15
Irgafos 168	antioxidant	0.15
Regalrez 1018	plasticizing resin	88.38
Kristalex 5140	strengthening resin	0.49
Regalite R101	plasticizing resin	2.46
Regalrez 1139	plasticizing resin	2.46
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.28
Bright orange aluminum lake	colorant	0.25

The material of Example 38 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred method for compounding the preferred gel material for use in the cushions of the present invention. The material was very tacky and readily deformable, had a slow to moderate rebound rate and was extremely soft. The specific gravity of the material was about 0.65.

#### EXAMPLE 39

Component	Generic Class	Weight % of Total
Septon 8006	A-B-A copolymer	2.45
Septon 4055	A-B-A copolymer	2.45
Kraton G1701	A-B copolymer	0.49

Irganox 1010	antioxidant	0.15
Irgafos 168	antioxidant	0.15
Regalrez 1018	plasticizing resin	88.06
Kristalex 5140	strengthening resin	0.49
Regalite R101	plasticizing resin	2.45
Regalrez 1139	plasticizing resin	2.45
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.64
Bright orange aluminum lake	colorant	0.24

The material of Example 39 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred compounding method. The material was very tacky and readily deformable, had moderate rebound and moderate softness. The specific gravity of the material was about 0.44.

#### EXAMPLE 40

Component	Generic Class	Weight % of Total
Septon 8006	A-B-A copolymer	2.43
Septon 4055	A-B-A copolymer	2.43
Kraton G1701	A-B copolymer	0.49
Irganox 1010	antioxidant	0.15
Irgafos 168	antioxidant	0.15
Regalrez 1018	plasticizing resin	87.51
Kristalex 5140	strengthening resin	0.49
Regalite R101	plasticizing resin	2.43
Regalrez 1139	plasticizing resin	2.43
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	1.26
Bright orange aluminum lake	colorant	0.24

The material of Example 40 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred compounding method. The material was tacky and readily deformable, had very quick rebound and moderate softness. The specific gravity of the material was about 0.28.

# EXAMPLE 41

Component	Generic Class	Weight % of Total
Septon 8006	A-B-A copolymer	2.44
Septon 4055	A-B-A copolymer	2.44
Kraton G1701	A-B copolymer	0.49
Irganox 1010	antioxidant	0.15
Irgafos 168	antioxidant	0.15
Regalrez 1018	plasticizing resin	87.78
Kristalex 5140	strengthening resin	0.49
Regalite R101	plasticizing resin	2.44
Regalrez 1139	plasticizing resin	2.44
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.95
Colorant—bright orange aluminum lake		0.24

The material of Example 41 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred compounding method. The material was very tacky and readily deformable, had slow rebound and little stiffness. The specific gravity of the material was about 0.37.

# EXAMPLE 42

Component	Generic Class	Weight % of Total
Septon 4033	A-B-A copolymer	0.29
Septon 8006	A-B-A copolymer	4.05
Kraton G1701	A-B copolymer	0.09
Irganox 1010	antioxidant	0.12
Irgafos 168	antioxidant	0.12
Regalrez 1018	plasticizing resin	86.73
Kristalex 5140	plasticizing resin	0.87
Regalite R101	plasticizing resin	2.02
Regalrez 1139	plasticizing resin	2.02
Vistanex LM-MS	plasticizing resin	2.89
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.37
Safoam FP-powder	blowing agent	0.43

In the material of Example 42, SEPTON® 4033 was used as a lower molecular weight polymer to help trap foam bubbles. A greater weight percentage of SEPTON® 8006 was used to

1 provide a visco-elastomeric material which was softer than the materials of the preceding  
2 examples. VISTANEX® LM-MS was also added to determine whether its presence improved  
3 the material's ability to retain foam bubbles.

4 In preparing the material of Example 42, the solid resins were first crushed and premixed.  
5 The VISTANEX® LM-MS was heated for thirty minutes in an oven at about 150 to 200°C. The  
6 REGALREZ® and VISTANEX® were then mixed together with heat until the VISTANEX®  
7 appeared to be completely solvated.

8 The components of the material of Example 42 were then melt blended in an injection  
9 molding machine according to a preferred compounding method. The material was very tacky  
10 and readily deformable, had very slow rebound and was very soft. The use of VISTANEX®  
11 LM-MS appears to have decreased the rebound rate of the material. The specific gravity of the  
12 material was about 0.61.

#### 13 EXAMPLE 43

14 Component	Generic Class	Weight % of Total
Septon 4033	A-B-A copolymer	0.29
Septon 8006	A-B-A copolymer	4.05
Kraton G1701	A-B copolymer	0.09
Irganox 1010	antioxidant	0.12
Irgafos 168	antioxidant	0.12
Vistanex LM-MS	plasticizing resin	2.90
Regalrez 1018	plasticizing resin	86.85
Kristalex 5140	strengthening resin	0.87
Regalite R101	plasticizing resin	2.03
Regalrez 1139	plasticizing resin	2.03
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.67

15 In preparing the material of Example 43, the crystallized (not readily flowable at room  
16

1 temperature) resins were first crushed and premixed. The VISTANEX® LM-MS was heated for  
2 thirty minutes in oven at about 150 to 200°C. The REGALREZ® and VISTANEX® were then  
3 mixed together with heat until the VISTANEX® appeared to be completely solvated.

4 The components of the material of Example 43 were then melt blended in an injection  
5 molding machine according to a preferred method for compounding the preferred gel cushioning  
6 media. The material was very tacky and readily deformable, had extremely slow, incomplete  
7 rebound and was very soft. The specific gravity of the material was about 0.47.

#### 8 EXAMPLE 44

Component		Weight % of Total
Septon 4077	A-B-A copolymer	4.67
Irganox 1010	antioxidant	0.30
Irgafos 168	antioxidant	0.30
Regalrez 1018	plasticizing resin	83.25
Vistanex LM-MS	plasticizing resin	1.81
Kristalex 5140	plasticizing resin	0.96
Regalite R101	plasticizing resin	1.93
Regalrez 1139	plasticizing resin	1.93
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.60
Glycerin	detackifying agent	4.25

10  
11 SEPTON® 4077 was included in the material of Example 44 to provide form and  
12 strength to the material, yet provide a softer material than that using SEPTON® 4055. The  
13 crystallized (not readily flowable at room temperature) resins of Example 44 were first crushed  
14 and premixed. The VISTANEX® LM-MS was heated for thirty minutes in oven at about 150 to  
15 200°C. The REGALREZ® and VISTANEX® were then mixed together with heat until the  
16 VISTANEX® appeared to be completely solvated.

17 The remaining components were then quickly mixed and melt blended in an injection

molding machine according to a preferred compounding method. The material was very tacky (but less than a comparable material without the glycerin), readily deformable, had extremely slow, incomplete rebound and moderate softness. Use of SEPTON® 4077 appears to have resulted in a material which is softer than those which include SEPTON® 4055 as the only plasticizer, but stiffer than materials of the previous examples which have a combination of copolymers. The specific gravity of the material was about 0.40.

#### EXAMPLE 45

Component	Generic Class	Weight % of Total
Septon 4077	A-B-A copolymer	4.67
Irganox 1010	antioxidant	0.30
Irgafos 168	antioxidant	0.30
Regalrez 1018	plasticizing resin	83.25
Vistanex LM-MS	plasticizing resin	1.81
Kristalex 5140	strengthening resin	0.96
Regalite R101	plasticizing resin	1.93
Regalrez 1139	plasticizing resin	1.93
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.60
Glycerin	detackifying agent	4.25

Glycerine was added to detackify the material of Example 45. In preparing the material of Example 45, the crystallized (not readily flowable at room temperature) resins were first crushed and premixed. The VISTANEX® LM-MS was heated for thirty minutes in oven at about 150 to 200°C. The REGALREZ® and VISTANEX® were then mixed together with heat until the VISTANEX® appeared to be completely solvated.

The remaining components were then mixed thoroughly and melt blended in an injection molding machine according to a preferred compounding method. The material was moderately tacky and readily deformable, had quick rebound and was soft. Glycerine appears to have

reduced the tackiness of the material. The specific gravity of the material was about 0.42.

#### EXAMPLE 46

Component	Generic Class	Weight % of Total
Septon 4055	A-B-A copolymer	2.47
Septon 8006	A-B-A copolymer	2.47
Kraton G1701	A-B copolymer	0.49
Irganox 1010	antioxidant	0.15
Irgafos 168	antioxidant	0.15
Regalrez 1018	plasticizing resin	88.85
Kristalex 5140	strengthening resin	0.49
Regalite R101	plasticizing resin	2.47
Regalrez 1139	plasticizing resin	2.47

The material of Example 46 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred compounding method. The material was extremely tacky and readily deformable, had slow rebound and was very soft. The specific gravity of the material was about 0.37.

#### EXAMPLE 47

Component	Generic Class	Weight % of Total
Septon 4055	A-B-A copolymer	2.35
Septon 8006	A-B-A copolymer	2.35
Kraton G 1701	A-B copolymer	0.47
Irganox 1010	antioxidant	0.14
Irgafos 168	antioxidant	0.14
Regalrez 1018	plasticizing resin	84.36
Kristalex 5140	strengthening resin	0.47
Regalite R101	plasticizing resin	2.34
Regalrez 1139	plasticizing resin	2.34
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	0.36
Glycerin	detackifying agent	4.69

The material of Example 47 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred method for compounding the preferred gel cushioning materials for use in the cushioning elements of this

invention. The material was very tacky and readily deformable, had slow rebound and little stiffness.

#### EXAMPLE 48

Component	Generic Class	Weight % of Total
Septon 4055	A-B-A copolymer	2.39
Septon 8006	A-B-A copolymer	2.39
Kraton G1701	A-B copolymer	0.48
Irganox 1010	antioxidant	0.14
Irgafos 168	antioxidant	0.14
Regalrez 1018	plasticizing resin	80.21+
		(see premix below)
Kristalex 5140	strengthening resin	0.48
Regalite R101	plasticizing resin	2.39
Regalrez 1139	plasticizing resin	2.39
Premixed microspheres		9.00
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	11.76% of premix (1.06)
Regalrez 1018		88.24% of premix (7.94)

The material of Example 48 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred compounding method. The material was extremely tacky and readily deformable, had slow rebound and little stiffness. The specific gravity of the Example 48 material was about 0.63.

Pre-blending the microspheres with REGALREZ® 1018 was, in part, advantageous because it reduced the amount of microspheres that were dispersed into the air during agitation, making the microspheres easier to handle.

#### EXAMPLE 49

A visco-elastic material was made which included four parts REGALREZ® 1018 (plasticizing resin), four parts HERCULES® Ester Gum 10D (plasticizing resin) and one part



SEPTON 4055 (A-B-A copolymer). The components were mixed, placed in an oven and heated to about 300°F. After all of the components became molten, they were mixed, poured onto a flat surface and cooled. The material had little tack, deformed under pressure, was very stiff but readily deformable with light sustained pressure, and had an extremely slow rate of rebound.

#### EXAMPLE 50

Component	Generic Class	Weight % of Total
Septon 4055	A-B-A copolymer	11.75
Ester Gum 10D	visco-elasticity enhancer	35.25
Regalrez 1018	plasticizing resin	29.38
Kristalex 5140	strengthening resin	1.18
Foral 85	strengthening resin	3.53
LP-150 oil	plasticizing oil	14.10
Ethospers LA-23	foaming facilitator	3.53
Irganox 1010	antioxidant	0.35
Irgafos 168	antioxidant	0.35
Aluminum Lake Colorant (Rocket red)		0.59

The material of Example 50 was prepared by premixing the components and melt blending them in an injection molding machine according to a preferred compounding method. The material was moderately tacky and deformable under slight, prolonged compressive force, had extremely slow rebound and was very stiff.

FORAL 85, manufactured by Hercules, is a glycerol ester of hydrogenated resin that is used primarily as a tackifier. In the preferred visco-elastic gel, FORAL 85 acts as a strengthening resin, and is believed to associate with and bind together the styrene domains. ETHOSPERSE LA-23, known generically in the art as Laureth-23, is used in the art as an emulsifier. Laureth-23 facilitates foaming in the gel materials preferred for use in the cushions of the present invention. The other components of Example 50 have been explained above.

## EXAMPLE 51

Component	Generic Class	Amount (grams)
Septon 4055	A-B-A copolymer	80.00
Septon 4077	A-B-A copolymer	80.00
Kraton G-1701	A-B copolymer	16.00
Regalrez 1018	plasticizing resin	2688.00+
		(see microsphere premix below)
Irganox 1010	antioxidant	4.80
Irgafos 168	antioxidant	4.80
Premixed microspheres		402.30
PQ 6545 microspheres	added to increase rebound rate and decrease specific gravity	11.76% of premix (47.31g)
Regalrez 1018		88.24% of premix (354.99g)

The material of Example 51 was prepared by preheating the REGALREZ® 1018, mixing all of the components except the microspheres together, and melt blending the components in a heated vessel at 295°F. under about one to about four pounds pressure for about two hours, according to a compounding method of the present invention. The mixture was then transferred to another vessel, which was heated to about 300°F., and the premixed microspheres and REGALREZ® 1018 were mixed in by hand.

The material was very tacky and readily deformable, had moderately slow rebound and was very soft. The specific gravity of the material of Example 51 was about 0.51.

Of the preceding sixteen examples (Examples 36-51), Applicant preferred the material of Example 51 because of its extreme softness and slow to moderate rebound rate. Applicant also liked the material of Example 50 because of its stiffness, but easy deformability under sustained pressure, and its extremely slow rate of reformation.

## EXAMPLE 52

1 A visco-elastic material which includes from about one to about 30 weight percent of a  
2 triblock copolymer and about 70 to about 99 weight percent of a plasticizer, said weight  
3 percentages being based upon the total weight of the visco-elastic material. The visco-elastic  
4 material may also include up to about 2.5 weight percent of a primary antioxidant and up to  
5 about 2.5 weight percent of a secondary antioxidant, said weight percentages based upon the  
6 weight of the triblock copolymer.

7 The following are additional examples of formulations that can be used to make  
8 gelatinous elastomers.

9 EXAMPLE 53

10 Component	Generic Class	weight % of total
11 SEEES	copolymer	75
12 Mineral oil	pasticizer	25

13 SEEES is used to designated styrene-ethyene-ethyene-ethyene-propylene-styrene.  
14  
15  
16

17 EXAMPLE 54

18 Component	Generic Class	weight % of total
19 SEEES	copolymer	80
20 Mineral oil	pasticizer	20

21 EXAMPLE 55

24 Component	Generic Class	weight % of total
25 SEEES	copolymer	83
26 Mineral oil	pasticizer	17

EXAMPLE 56

Component	Generic Class	weight % of total
SEES	copolymer	77
Mineral oil	pasticizer	23

EXAMPLE 57

Component	Generic Class	weight % of total
SEES	copolymer	75
Mineral oil	pasticizer	25

EXAMPLE 58

Component	Generic Class	weight % of total
SEES	copolymer	67
Mineral oil	pasticizer	33

EXAMPLE 59

Component	Generic Class	weight % of total
SEES	copolymer	60
Mineral oil	pasticizer	40

EXAMPLE 60

Component	Generic Class	weight % of total
SEPS	copolymer	90
Mineral oil	pasticizer	10

SEPS is used to designate styrene(ethylene/propylene-)styrene which preferably will have a weight average molecular weight of about 300,000 or more.

EXAMPLE 61

Component	Generic Class	weight % of total
SEPS	copolymer	80
Mineral oil	pasticizer	20

EXAMPLE 62

Component	Generic Class	weight % of total
SEPS	copolymer	70
Mineral oil	pasticizer	30

EXAMPLE 63

Component	Generic Class	weight % of total
SEPS	copolymer	67
Mineral oil	pasticizer	33

EXAMPLE 64

Component	Generic Class	weight % of total
SEPS	copolymer	60
Mineral oil	pasticizer	40

EXAMPLE 65

Component	Generic Class	weight % of total
SEPS	copolymer	50
Mineral oil	pasticizer	50

EXAMPLE 66

Component	Generic Class	parts by weight
SEPS (4055)	copolymer	80
Resin (Regalrez 1018)	pasticizer	10

1	Irganox 1010	antioxidant	0.15
2	Irgaphos 168	antioxidant	0.15

#### EXAMPLE 67

5	Component	Generic Class	parts by weight
7	SEPS (4055)	copolymer	10
8	Mineral oil	pasticizer	20
9	Irganox 1010	antioxidant	0.15
10	Irgaphos 168	antioxidant	0.15

#### EXAMPLE 69

13	Component	Generic Class	parts by weight
15	SEPS (4055)	copolymer	10
16	Mineral oil	pasticizer	120
17	Irganox 1010	antioxidant	0.15
18	Irganox 168	antioxidant	0.15

Each of examples 67-69, while having many uses, are preferred for use in causing standard prior art open cell foam, such as polyurethane foam and latex foam rubber, to become a viscoelastic foam. This is done by coating the open cells of the foam with a tacky substance such as that of the examples. The tacky substance should not be adhesive, however, or the foam will not return to its original shape after deformation. It is preferred that the tacky substance be a solid or a gel rather than a liquid to eliminate the need to contain the coated foam in a bladder. It is also preferred that the tacky substance be an elastomer so that it can flex and bend with the foam. Use of a resin as a plasticizer creates a delayed rebound viscoelastic foam. The tacky substance, such as that of examples 67-69, can be used to coat foam by any of a variety of methods. For example, solvating the gel in a liquid and soaking the foam will work. Or the gel may be heated

to become a liquid and then forced into the foam. If a foam is coated with a low stiffness gel, then a viscoelastic foam with excellent elastic properties is the result. Alternatively, the foam may be cut into small pieces, the small pieces saturated with a gel of the invention, the excess gel removed from the gel, and the mass of gel-coated foam allowed to dry or cool so that the gel will solidify. The gel then creates a structure holding the pieces of foam together. Such a cushioning material tends to have excellent elasticity and strength.

#### EXAMPLE 70

Component	Generic Class	parts by weight
SEPS (4055)	copolymer	1
Resin (Regalrez 1018)	pasticizer	10
Irganox 1010	antioxidant	0.15
Irganox 168	antioxidant	0.15

#### EXAMPLE 71

Component	Generic Class	parts by weight
SEPS (4055)	copolymer	1
Resin (Regalrez 1018)	pasticizer	18
Irganox 1010	antioxidant	0.25
Outer coating of short rayon fibers to eliminate tackiness.		

The above examples 70 and 71 provide a slow rebound viscoelastomer gel. Gel of the formula from Example 71 was formed into a rectangular shape of dimensions 2cm x 2cm x 7cm. The rebound of the material was then tested. When the rectangular shape was stretched along its length (from 7cm) to a length of 20cm, the following was found: in one second, the gel rebounded to a length of 13 cm; in two seconds (total) it rebounded to a length of 10 cm; in four

seconds (total) it rebounded to a length of 8 cm; and in nine seconds (total) it rebounded to substantially its original shape. These slow rebound times cause the inventor to classify it as a slow rebound viscoelastomer. Similarly slow rebound was found on compression. When the rectangular shape was compressed along its length (originally 7cm) to a length of 3cm, and released, after one second it rebounded to a length of 5cm; after two seconds (total) it rebounded to a length of 6 cm; after four seconds (total) it rebounded to a length of 6.5 cm, and after nine seconds (total) it returned to substantially its original shape. After five hundred alternate compression and elongation cycles, the rectangular shaped viscoelastomer of Example 71 had substantially the same dimensions and shape as before. All of these tests were run at 25 degrees Clesius.

#### EXAMPLE 72

Component	Generic Class	parts by weight
SEPS (4055)	copolymer	1.64
Resin (Regalrez 1018)	pasticizer	17.5
Mineral oil (Whitco LP-200)	plasticizer	10
Irganox 1010	antioxidant	0.073
Outer coating of pressed-on microspheres to eliminate tackiness.		

A viscoelastomer made according to the formula of Example 72 was formed into a rectangular cube of dimensions 7 cm (width) x 3 cm (height) x 14 cm (length). Elongation and compression testing was then performed at 25 degrees Celsius and the following was found. After elongation of the rectangular cube along its length to a total length of 30cm, after one second it rebounded to a length of 20cm; after two seconds (total) it rebounded to a length of 18cm; after four seconds (total) it rebounded to a length of 16cm; and after nine seconds (total) it rebounded to



1 substantially its original dimensions and shape. On compression along its length to a reduced  
2 total length of 7cm, rebound was found to be as follows: after one second, the cube rebounded to  
3 a length of 10cm; after two seconds (total) it rebounded to a length of 11.5cm; after four seconds  
4 (total) it rebounded to a length of 13 cm; after nine seconds (total) it rebounded to substantially  
5 its original dimensions and shape. After five hundred alternate elongation and compression tests  
6 as just described, the material returned to substantially its original size and shape.

7 The following are viscoelastomer formulations used to reduce oil bleed and tack that was  
8 very problematic in the prior art, including in the gels of John Y. Chen.

9 EXAMPLE 73

10 Component	Generic Class	parts by weight
11 SEPS (4055)	copolymer	1
12 Resin (Regalrez 1018)	pasticizer	18
13 Irganox 1010	antioxidant	0.25
14 Outer coating of short rayon or other fibers to eliminate tackiness.		

15  
16  
17 It is notable that the preferred bleed reducing additives of these preferred embodiments of the  
18 invention include a plurality of polarizable sites thereon, including halogen atoms, nitriles and  
19 others. Polarizable means an atom's ability to respond to a changing electrical field. Molecules  
20 with polarizable atoms are more likely to be attracted to other molecules by dynamic van der  
21 Waals forces, thus reducing bleed. The bleed reducing additives allow there to be an increase in  
22 the amount of plasticizer used in the material without an increase in oil bleed. Preferably, the  
23 elastomer will include hydrocarbon chains with polarizable groups thereon, such as hydrogenated

1 hydrocarbons, nitriles and others. The polarizable groups are believed to hold the plasticizer  
2 close to the copolymer to reduce bleed. This occurs by the polarizable group attracting a  
3 plasticizer at one end and an elastomer block at the other, thus maintaining association of  
4 plasticizer with elastomer. A plasticizer can be attached to an elastomer by use of a polarizable  
5 group. It is preferred that the additive will have a plurality of polarizable groups. The most  
6 preferred bleed reducing additives are halogenated hydrocarbon additives such as DYNAMAR  
7 PPA-791, DYNAMAR PPA-790, DYNAMAR FX-9613 and FLUOROAD FC10  
8 Fluorochemical alcohol from 3M Company of St. Paul, Minnesota. Other additives can be used  
9 to reduce plasticizer exudation. For example, FLUORORAD FC-129, FC-135, FC-430, FC-722,  
10 FC-724, FC-740, FX-8, FX-13, FX-14 and FX-189 are halogenated hydrocarbons that will serve  
11 this purpose. Others which may be used include XONLY FSN 100, FSO 100, PFBE 8857A,  
12 TM, BA-L, TBC and FTS from DuPont of Wilmington, Delaware. Witco Corp. of Houston,  
13 Texas sells halogenated hydrocarbons under the names EMCOL 4500 and DOSS. Hartwick, Inc.  
14 of Akron, Ohio sells chlorinated polyethylene elastomer (CPE) and chlorinated paraffin wax.  
15 None of these chemicals is marketed as a bleed reducing additive, however. It is preferred that  
16 processing temperatures just below the boiling point of the bleed reducing additive be used, as  
17 long as that temperature will not cause elastomer degradation.

18 Materials of the formulas shown have been used to measure oil bleed. Percent oil bleed  
19 was measured by obtaining the combined weight of three disk shaped samples of the material,  
20 each sample having a diameter of about 3cm and a thickness of about 6.5 mm. Two four inch  
21 square pieces of 20# bond paper were then weighed individually. The three sample disks were

placed on the paper (which has high capillary or wicking action), and the other piece of paper was placed on top of the sample. The material and paper were then placed in a plastic bag and pressure sandwiched between two flat steel plates, each weighting 2285 g. Next, the material samples, paper and steel plates were heated to 110 degrees F. for 4 hours. Alternatively, two pieces of 12.5 cm diameter qualitative filter paper having a medium filter speed and an ash content of 0.15%, such as that sold under the trade name DOBLE RINGS 102 from Xinhua Paper Mill may be used in place of the two four inch square pieces of 20# bond paper. The following are example formulations.

EXAMPLE 74

Component	Generic Class	weight percent
SEPS (4077)	copolymer	11.2
Mineral oil (LP-150)	pasticizer	87.4
FC-10 Fluorochemical alcohol	bleed reducer	0.3
Saturn Yellow	pigment	1.2

EXAMPLE 75

Component	Generic Class	weight percent
SEPS (4055)	copolymer	12.3
Mineral oil (LP-150)	pasticizer	86.1
Zonyl FSN-100	bleed reducer	0.4
Horizon blue	pigment	1.2

EXAMPLE 76

Component	Generic Class	weight percent
SEPS (4055)	copolymer	12.3
Mineral oil (LP-150)	pasticizer	86.1
FC-10 Fluorochemical alcohol	bleed reducer	0.4

1	Saturn Yellow	pigment	1.2
---	---------------	---------	-----

2 EXAMPLE 77

3	<b>Component</b>	<b>Generic Class</b>	<b>weight percent</b>
4			
5	SEPS (4077)	copolymer	17.9
6	Mineral oil (LP-150)	pasticizer	81.6
7	FC-10 Fluorochemical alcohol	bleed reducer	0.5
8	Neon red	pigment	0.9

9 EXAMPLE 78

10	<b>Component</b>	<b>Generic Class</b>	<b>weight percent</b>
11			
12	SEPS (4055)	copolymer	12.3
13	Mineral oil (LP-150)	pasticizer	86.1
14	Zonyl TA-N	bleed reducer	0.4
15	Blaze Orange	pigment	1.2

16 EXAMPLE 79

17	<b>Component</b>	<b>Generic Class</b>	<b>weight percent</b>
18			
19	SEPS (4055)	copolymer	14.1
20	Mineral oil (LP-150)	pasticizer	84.7
21	FC-10 Fluorochemical alcohol	bleed reducer	0.3
22	Magenta	pigment	0.9

23 EXAMPLE 80

24	<b>Component</b>	<b>Generic Class</b>	<b>weight percent</b>
25			
26	SEPS (4055)	copolymer	13.4
27	Mineral oil (LP-150)	pasticizer	80.2
28	Kraton G1701	processing additive	0.3
29	Irganox 1010	antioxidant	0.2
30	Irgafos 168	antioxidant	0.2
31	Dynamar PPA 791	bleed reducer	5.3
32	Magenta	pigment	0.4

Examples 74-80 exhibited little or no oil bleed when tested by the above method. The material of Example 80 lost only 0.009 percent of its weight during bleed testing.

A tackless formulation of the gelatinous elastomer may also be made according to the formula of Example 81 and variations thereof.

#### EXAMPLE 81

Component	Generic Class	weight percent
SEPS (4055)	copolymer	24.567
Mineral oil (LP-200)	plasticizer	73.701
Irganox 1076	antioxidant	0.246
Irgafos 168	antioxidant	0.246
KENEMIDE E ULTRA	grapeseed oil -detackifier	0.246
Horizon Blue	pigment	0.995

Grapeseed oil or other oils and materials may be used as a slip agent or detackifier to produce an elastomer with a non-tacky exterior.

#### EXAMPLE 82

Component	Generic Class	weight percent
SEPS (4055)	copolymer	16.50
Mineral oil (LP-150)	plasticizer	82.51
Irganox 17E	antioxidant	0.41
Zonyl BE-H	detackifier	0.17
Colorant	color	0.41

Example 83 below is a preferred formulation for making cushioning elements that may be used in mattresses.

#### EXAMPLE 83

Component	Generic Class	weight percent
-----------	---------------	----------------

1	SEPS (4055)	copolymer	10
2	Mineral oil (LP-200)	pasticizer	22.5
3	Irganox 1010	antioxidant	0.03
4	Irgaphos 168	antioxidant	0.03
5	Aluminum lake pigment	colorant	0.03
6	Zonyl BA-N fluorochemical alcohol	bleed reducer	0.05

7

8 Alternative preferred embodiments of the gelatinous elastomer for mattressing include changing  
9 the mineral oil weight percent from 22.5 to between 15 and 70, 15 weight percent being a firmer  
10 formulation and 70 being a softer formulation. The most preferred gel of the invention will have  
11 a durometer of less than about 25 on the Shore A scale.

12 Although the gel formulations referred to above are most preferred, there are numerous  
13 other preferred gels. For example, although they exhibit less desirable characteristics than the  
14 preferred gel cushioning media, the gel formulations of the following U.S. Patent Nos. are also  
15 useful in the cushions of the present invention: 5,334,646, issued in the name of John Y. Chen;  
16 4,369,284, issued in the name of John Y. Chen; 5,262,468, issued in the name of John Y. Chen;  
17 4,618,213, issued in the name of John Y. Chen; 5,336,708, issued in the name of John Y. Chen,  
18 each of which is incorporated by reference in its entirety. Other oil-extended polystyrene-  
19 poly(ethylene/butylene)-polystyrene gels can be used advantageously for the cushions of this  
20 invention. For example, the GLS Corporation of Cary, Illinois offers a gel in injection moldable  
21 pellet form under the designation G-6703 which is made with the ingredients of the gels  
22 mentioned above but with less plasticizing oil, and has a Shore A hardness of 3. Other preferred  
23 gels which may be used in the invention include PVC plastisol gels, silicone gels, and  
24 polyurethane gels.

1 PVC plastisol gels are well known in the art, and are exemplified by artificial worms and  
2 grubs used in fishing. A description of a typical PVC plastisol gel is given in United States  
3 Patent No. 5,330,249 issued in the name of Weber et al. on July 19, 1994, which is hereby  
4 incorporated by reference. PVC plastisol gels are not the most preferred because their strength is  
5 not as high for a given gel rigidity as the preferred gel media or even the gels of the Chen  
6 patents, but they are acceptable for use in the invention.

7 Silicone gels are also well known in the art, and are available from many sources  
8 including GE Silicones and Dow Corning. From a performance standpoint, silicone gels are  
9 excellent for use in this invention. However, the cost of silicone gels is many times higher than  
10 that of the most preferred gels.

11 Also in the most preferred gels, the ratio of plasticizer such as oil to triblock copolymer is  
12 3:1 or less (such as 2.5:1; 2.0:1; 1.5:1; and 1.0:1.0). At these ratios, the gel is not stirrable during  
13 the melting process and is not castable when melted. Thus this gel is not suitable for typical  
14 prior art manufacturing such as that proposed in the John Y. Chen patents. However, the  
15 inventor has found that these low ratios of plasticizer to copolymer have very high strength,  
16 superior shape retention, lower tack, and lower bleed-out properties than the prior art. They also  
17 have a higher durometer than the prior art. Cushioning devices, such as hollow column gel  
18 cushions, can be made much lighter if the walls are thin and of a high durometer. Such cushions  
19 are also cheaper to make than thicker walled lower durometer cushions. And if the gel is used as  
20 a shoe insert, then the preferred gels just described will be superior because the gel will not tend  
21 to flow out from under the foot being cushioned (or other object being cushioned) as it would

1 with prior art gels such as those of John Y. Chen. Finally, gels of these formulations exhibit  
2 much better processability through screws, such as the compounding screws of extruders and  
3 injection molding machines. The prior art Chen gels do not feed through screws well because  
4 they are too slippery in the pre-mix state and are not driven well by screws because their  
5 viscosity is too low. The invented gels have a higher viscosity and perform much better when  
6 pushed by a screw such as in an injection molding machine or in an extruder.

7 Polyurethane gels are also well known in the art, and are available from a number of  
8 companies including Bayer Aktiengesellschaft in Europe. For reference, the reader is directed to  
9 United States Patent No. 5,362,834 issued in the name of Schapel et al. on November 8, 1994,  
10 which is hereby incorporated by reference, for more information concerning polyurethane gels.  
11 Like silicone gels, polyurethane gels are excellent from a performance standpoint, but are many  
12 times more expensive than the most preferred gels.

13 Foam rubber and polyurethane foams may also be useful as cushioning media in the  
14 cushioning elements of the present invention, so long as they exhibit gel-like buckling behavior.  
15 Preferably, in order to exhibit desired buckling and elastomeric or visco-elastomeric gel-like  
16 behavior, column walls formed from polyurethane foams and foam rubbers are very thin.  
17 Alternatively, thicker column walls formed from polyurethane foams and foam rubbers may also  
18 exhibit the desired buckling and gel-like characteristics with appropriate column shapes and  
19 column pattern configurations. Foam rubbers and polyurethane foams are useful in the  
20 cushioning element of the present invention if columns occupy about one-half or more of the  
21 cushion volume. Cushion volume is defined by the top and bottom surfaces and the perimeter of



1 the cushion.

## 2 **C. Method for Making the Cushions**

3 There are several ways in which the cushion can be manufactured.

### 4 **1. Injection Molding**

5 The invented cushions can be injection molded by standard injection molding techniques.

6 For example, a cavity mold is created with cores inside the cavity. The gel ingredients are  
7 heated while stirring, which turns the gel into a liquid. The liquid is injected into the cavity and  
8 flows around the cores. The material is allowed to cool, which causes it to solidify. When the  
9 mold is parted, the cores pull out of the solidified gel and leave the hollow columns. The  
10 cushion is removed from the cavity, the mold is closed, and liquid is injected to form the next  
11 cushion, this process being repeated to manufacture the desired quantity of cushioning elements.

12 This results in very inexpensive cushioning elements because the preferred gel is inexpensive  
13 and the manufacturing process is quick and requires very little labor.

14 Referring to Figure 4, an example mold in use is depicted. The mold assembly 401 has a  
15 first mold half 401 and a second mold half 404. The second mold half 404 has a cavity 408 and a  
16 base plate 405 at the bottom of the cavity 408. It also has side walls 414 and 415. The first mold  
17 half 402 has a core mounting plate 409 and a plurality of cores 403 mounted on it in any desired  
18 spacing and arrangement. The cores 403 may be of any desired shape, such as triangular, square,  
19 pentagonal, n-sided (where n is any integer), round, oval or of any other configuration in cross  
20 section in order to yield a molded cushioning element 406 of the desired configuration. The  
21 cores 403 could also be tapered from a more narrow dimension (reference numeral 410) at their

1 end distal from the core mounting plate 409 to a wider dimension (reference numeral 411) at  
2 their end proximal the core mounting plate. This would create a tapered column or tapered  
3 column walls so that the radial measurement of a column orthogonal to its longitudinal axis  
4 would be different at two selected different points on the longitudinal axis.

5 Alternatively, the cores 403 could be tapered from 410 to 411, stepped from 410 to 411 or  
6 configured otherwise to create a column of desired shape. Use of the hexagonal cores 403  
7 depicted yields a cushioning element 406 with cushioning media 412 molded so that the column  
8 walls 413 form the hollow columns 407 in a hexagonal configuration.

9 When the first mold half 402 and second mold half 404 are brought together, core distal  
10 ends 410 abut the second mold half base plate 405. This prevents liquid cushioning media from  
11 flowing between the base plate 405 and the core distal ends 410 in order to achieve a cushioning  
12 element 406 which has hollow columns through which air can circulate. If the core distal ends  
13 410 did not reach all the way to the base plate 408, then the columns 407 would be open at one  
14 end and closed at the other.

15 Figure 5 depicts an alternative mold configuration. The mold assembly 501 includes first  
16 mold half 502 that includes a first core mounting plate 509 onto which a plurality of cores 503  
17 are mounted in a desired configuration. The cores 503 each have a core proximal end proximal  
18 to the core mounting plate 509 and a core distal end 511 distal to the core mounting plate 509.  
19 The mold assembly 501 also includes a mold second half 504 which has a core mounting plate  
20 505, side walls 512, and cores 508 each having a core proximal end 513 proximal to the core  
21 mounting plate 505 and a core distal end 514 distal to the core mounting plate. The second core

1 half 504 also has a cavity 514 in which its cores 508 are found. The mold assembly 501 may be  
2 designed so that when the two mold halves are brought together the core distal ends abut the  
3 surface of their opposing core mounting plates. This produces a cushioning element 506 with  
4 hollow columns 507 that are open from one end to the other in order to maximize air circulation  
5 through the columns 507 and yieldability of the cushioning element 506. Alternatively, the mold  
6 assembly 501 may be designed so that the core distal ends do not contact the core mounting  
7 plates. This will result in a cushion having a cross sectional appearance like that depicted in  
8 Figure 6, where the columns are shorter in length than the thickness of the cushioning element,  
9 so the columns are closed at one end.

10 In the prior art, such the John Y. Chen gel patents and in U.S. Patent No. 5,618,882, the  
11 preferred method for manufacturing gel articles was casting, and the preferred method for  
12 making the gel was melt blending. These prior art manufacturing methods are slow, expensive,  
13 messy and inefficient.

14 The applicant has learned how to manufacture gel articles using gels of the preferred  
15 formulations and other formulations by filling a hollow cavity in a mold with the gel. A mold  
16 with a hollow cavity of appropriate shape for the article to be made is first obtained. Then a  
17 quantity of gelatinous elastomer or viscoelastomer is obtained, or the ingredients for making it  
18 are obtained. Then the gelatinous elastomer or viscoelastomer or the ingredients are fed into a  
19 compounding screw (such as a single screw or a twin screw) of an appropriate machine such as  
20 an injection molding machine or an extruder. Then the screw moves the gel along its length  
21 under temperature and pressure. Then the screw moves the gel into a cavity of a mold in order to

1 fill the cavity of the mold and create a molded gel article. With this manufacturing method, the  
2 materials of the gel are exposed to heat for a much shorter time than prior art manufacturing  
3 methods, resulting in less elastomer degradation. The materials of the gel are also exposed to  
4 heat for a shorter period of time. And because the gel can be forced into the mold under pressure  
5 rather than relying on gravity flow for casting, articles of a wide variety of shapes can be made  
6 and articles can be made with the use of little plasticizer, resulting in much stronger gels.  
7 Alternatively, instead of injecting the gel material into the mold, it can be allowed to flow into  
8 the mold under its own weight.

## 9 **2. Extrusion**

10 The invented cushioning elements may also be manufactured by typical extrusion  
11 processes. If extrusion is used, hot liquid gel is forced through an extrusion die. The die has  
12 metal rods situated to obstruct the path of the gel in some locations so that the gel is forced  
13 through the die in a pattern resembling the desired shape of the finished cushioning element.

14 Thus the die, having an aperture, an aperture periphery, and forming rods within the aperture has  
15 an appearance similar to that of the desired cushioning element except that the portions of the die  
16 that are solid will be represented by empty air in the finished cushion, and the portions of the die  
17 in the aperture that are unobstructed will represent gel in the finished cushioning element. Thus  
18 the rods of the die should be of the shape and size that the desired cushioning element is intended  
19 to be; the spacing of the rods should approximate the spacing of the columns that is desired in the  
20 finished cushioning element; and the shape and size of the aperture periphery should  
21 approximate the shape and size of the periphery of the desired cushioning element.

1           When gel is forced through the die, the liquid gel is cooled during its traverse through the  
2 die, causing it to solidify as it leaves the die. The gel is then cut at desired length intervals to  
3 form cushioning elements. Of course, cushioning elements so formed have hollow columns  
4 throughout their length, although the ends of the columns could be sealed as mentioned  
5 elsewhere herein. It is not expected, however, that extrusion is a practical method for  
6 manufacturing cushions with columns that vary in dimension along their length. The extruded  
7 cushioning element is very inexpensive because the both the cushioning media (i.e. the preferred  
8 gel) is inexpensive and the manufacturing process is highly automated so that labor requirements  
9 are very low.

10           Alternatively, a single tube may be extruded, then cut to a length that will form the  
11 appropriate cushion thickness. The tubes are then bonded together to form a cushioning element  
12 according to the present invention. Referring to Figure 41, a preferred embodiment of a cushion  
13 4101 which is made from bonded tubes 4102a, 4102b, 4102c, etc. is shown. Each tube includes  
14 a hollow column 4103 formed by a column wall 4104. Preferably, column wall 4104 is made  
15 from a gel cushioning medium 4105, such as the preferred elastomeric or visco-elastomeric  
16 materials for use in the cushions of the present invention.

17           Figure 42 illustrates an example of a preferred method for bonding two tubes 4102a and  
18 4102b together. Heating cores 4201 and 4203, which preferably include a heating edge 4202 and  
19 4204, respectively, are positioned in tubes 4102a and 4102b within corners 4110a and 4110b,  
20 respectively, such that edges 4202 and 4204 abut the inner surface of the corners. Preferably,  
21 cores 4201 and 4203 hold the outer surface of corners 4110a and 4110b against one another.

1 Preferably, securing cores 4205 and 4206 are positioned in each of the two inner corners formed  
2 by tubes 4102a and 4102b to secure corners 4110a and 4110b from sliding side-to-side in  
3 relation to one another. Preferably, heating edges 4202 and 4204 are heated to a temperature  
4 sufficient to melt cushioning medium 4105, but not to a temperature which would burn the  
5 material. As heating edges 4202 and 4204 are heated to a desirable temperature, the cushioning  
6 medium located in corners 4110a and 4110b melts. Preferably, heating edges 4202 and 4204  
7 remain heated until all of the material located at corners 4110a and 4110b becomes molten and  
8 fuses tubes 4102a and 4102b together. Heating edges 4202 and 4204 and corners 4110a and  
9 4110b are then cooled. Preferably, heating edges 4202 and 4204 are each covered with a non-  
10 stick surface 4207 and 4208, respectively. Similarly, securing cores 4205 and 4206 also have  
11 non-stick surfaces 4211 and 4212. The non-stick surfaces prevent the securing cores 4205 and  
12 4206 and heating edges 4202 and 4204 of heating cores 4201 and 4203 from sticking to the  
13 cushioning medium located at corners 4110a and 4110b as the medium becomes molten. A  
14 preferred non-stick surface is teflon paper. Cores 4201, 4203, 4205 and 4206 are then removed  
15 from tubes 4102a and 4102b.

16 In the preferred extrusion method, the elastomer gel is pre-compounded at a temperature  
17 of about 470 degrees Fahrenheit. Then the gel is run through an extrusion die at a preferred  
18 temperature of about 425 degrees Fahrenheit. The pressure in the extrusion die may be from 200  
19 to 4000 pounds per square inch, depending on the gel being extruded and the die dimensions and  
20 characteristics. The formulation of the gel will affect desired temperature. The part may be  
21 extruded from a die into water to aid in cooling and solidifying the gel. The gel may be extruded

1 upwards through a die and into water of necessary to maintain the shape of the extruded part.

2 The same advantages and techniques for using a screw to compound or simply melt gel  
3 material and force it into a mold from an injection molding machine can be applied to an  
4 extruder, using the extruder screw to compound the gelatinous material and force it through a  
5 die. Thus larger, more complex and stronger parts can be made when the extrusion method of  
6 the invention is used than if prior art casting is used.

### 7 **3. Casting**

8 Another manufacturing process by which the invented cushioning element can be made is  
9 by generally known casting technology. In order to cast the invented cushioning element, hot  
10 liquid gel (or other cushioning media) is poured into an open cavity, and an assembly of metal  
11 rods is pushed into the liquid. The rods will form the columns of the finished product. The  
12 liquid flows between the metal rods, cools and solidifies. The metal rods are then removed,  
13 leaving the hollow portions of the columns, and the cushion is removed from the cavity. A  
14 vibrator may be used to vibrate the cavity to facilitate the flow of the liquid between the rods if  
15 needed.

16 With reference to Figure 42, in an alternative casting process, about half of the column-  
17 forming rods have a plurality of protrusions extending therefrom. Preferably, each of the rods  
18 which are adjacent to a rod which has protrusions extending therefrom do not include protrusions  
19 therefrom. The preferred protrusions extend toward each of the adjacent rods and substantially  
20 across the distance between the adjacent rods. As cushioning medium is cast using this process,  
21 the rods with protrusions preferably create fenestrations in the column wall which surrounds the

1 column created thereby, each of the fenestrations preferably passing substantially through the  
2 column wall to an adjacent column. Figure 42 shows one preferred configuration of  
3 fenestrations 4200, having a circular shape. Other shapes such as diamonds, squares, triangles,  
4 or others are also useful as fenestrations. After the cushioning medium has solidified, the rods  
5 which lack protrusions are preferably removed from the cushioning element first. The rods with  
6 protrusions are then removed from the cushioning medium, which, due to its softness and  
7 elastomeric or visco-elastomeric properties, gives easily without tearing or breaking as the rods  
8 are removed.

9 Casting is a more labor intensive manufacturing method than injection molding or  
10 extrusion, but the tooling is generally less expensive, especially for large cushions. This is the  
11 preferred method of making very large cushions, such as king-size bed mattresses, since the size  
12 of such cushions is greater than that which can be manufactured using injection molding or  
13 extrusion methods.

#### 14 4. Two Step Manufacturing Process

15 In many instances it is advantage to prepare the gelatinous material in advance and  
16 manufacture a product from it at a later date. The inventor has implemented a process for doing  
17 this that has very beneficial qualities for the manufacture of gel products.

18 The first step is to manufacture the gelatinous elastomer. This is done by gathering  
19 appropriate ingredients, as described in detail above, and appropriate equipment for  
20 compounding the elastomer. While melt blending and solvent blending are possible, it is much  
21 preferred to use either a single screw or a twin screw compounder such as those found on



1 extruders and injection molding machines. The ingredients for the gel are fed into the screw at  
2 one end, and as the screw moves the ingredients along its length under pressure and temperature,  
3 compounding of the ingredients takes place (such as association of the plasticizer with the  
4 elastomer molecules and association of the bleed reducing additive with both the plasticizer and  
5 the elastomer molecules). As the compounded gel exits the screw, it may then be cut or chopped  
6 into small pieces or pellets.

7 The pellets can be stored (such as in bags or barrels), transported and later used. In the  
8 later use, the second step of the invention is performed. I it, the pellets are melted in order to  
9 injection mold, extrude, cast or spray a final product with the gel of the invention. It is preferred  
10 that the pellets will be melted again under pressure in a screw such as that found on an injection  
11 molding machine or extruder.

12 There are distinct advantages to this two step process. First, in the first process step the  
13 lower molecular weight fractions (volatiles) of the plasticizer (such as mineral oil) are boiled off.  
14 Thus, in the second step there is no boiling of the plasticizer and voids in the manufactured part  
15 are reduced. Quality of the finished product and strength of the finished product are thus greatly  
16 enhanced.

17 Another advantage is that some screws have difficulty grabbing and transporting the  
18 ingredients of the gel because they are slippery and coated with oil, but the screw can easily grab  
19 and push the preformed pellets. Thus, the use of pre-formed pellets allows the use of a much  
20 shorter screw and shorter processing times and shorter exposure to high temperatures. Although  
21 the preferred method for this embodiment of the invention includes running the gel through the

1 screw twice, any compounding method may be used twice on the same gel in order to achieve the  
2 invention. It desirable, the pellets can be extruded underwater or fall into water for instant  
3 cooling, or spread out on a stationary or moving surface for air cooling.

#### 4 **D. Other Cushioning Devices**

##### 5 **1. Cushions Comprising End-Supported Free-Standing Buckling Elastic** 6 **Members, and Methods for Manufacturing the Same**

7 As used herein, cushions are defined as pads of any shape which equalize or redistribute  
8 pressure over the surface of an item which bears on the pad, which soften the surface on which  
9 the load from the item bears, which absorb or attenuate vibration and/or shock to protect the  
10 item, and/or which provide a resilient action to separate the item from the movements of its  
11 surroundings. More specifically, this embodiment of the invention is for a cushion which  
12 achieves these cushioning features through the buckling action of end-supported free-standing  
13 buckling elastic members, and does so in a manner which provides advantages over prior art  
14 cushions.  
15

16 The inventor intends to obtain the advantages of buckling column performance with  
17 foam, which is lightweight and inexpensive and bonds readily to other materials. Unfortunately,  
18 sculpted foam compresses an a single unit rather than buckling under point load. The  
19 embodiment of the invention described below achieves advantages of gelatinous buckling  
20 columns but with light weight and low cost.

21 This embodiment of the invention is a cushion comprising one or more free-standing  
22 buckling members which are supported at or near the ends. These buckling members are

1 configured to sustain a given level of compression loading from the cushioned item resulting in  
2 compression deformation without buckling, and then if that given level of compression loading is  
3 exceed, to buckle and undergo further deformation with less than a linearly proportional increase  
4 in loading. A rail is supported at the ends in that it is tied into an overall supporting structure at  
5 each end of the buckling portion of the member. The rail is allowed to continue beyond the  
6 buckling portion. Free-standing indicates that a buckling portion of the member is not integrally  
7 connected to another member or to another support structure other than at or near the ends, thus  
8 allowing free buckling. One or more portions of the member can be connected non-free-  
9 standing, so long as at least one buckling portion is free standing. The buckling members can be  
10 solid or hollow.

11 The degrees of buckling freedom of the buckling members of the cushion of my invention  
12 can be one or more. For example, a round column can buckle in any lateral direction, so it has  
13 unlimited degrees of freedom. As a second example, a column of square cross-sectional shape  
14 buckles more easily in two orthogonal directions than in other directions, so it effectively has  
15 two degrees of freedom. As a third example, a rail which is 1 inch thick, 5 inches tall, and 30  
16 inches long and attached to a support at each end of the 30-inch length is most likely to buckle in  
17 a direction transverse to the length; thus it effectively has one degree of freedom. This  
18 embodiment of the invention is not limited to any particular member shape or configuration so  
19 long as it meets the criteria set forth above.

20 Neither is this embodiment of the invention limited to the specific material of  
21 construction. Any material which is elastic or visco-elastic in nature, meaning that when load is

1 removed it will quickly or at least eventually spring back to about the original shape and size,  
2 and which is durable enough to meet the operating conditions of the cushion, will work in the  
3 invention.

4 Steel meets this criteria, and is particularly useful in the invention in the form of coil  
5 springs. Compressible coil springs can form the buckling members of the invention. The spring  
6 should be sized (wire diameter, wrap diameter, wrap density, etc.) so that it's overall length-to-  
7 diameter ratio results in instability when loaded at less than or equal to the maximum desired  
8 localized cushioning load, and so that the compression of the spring in the pre-buckle loading is  
9 acceptable for the given cushioning requirement. For example, in a mattress or any other  
10 cushion for the human body, it is desirable that the cushion be able to support a pressure load of  
11 at least 20 mm of Hg, but never over 32 mm of Hg (the capillary shut-off pressure in at-risk  
12 individuals). The spring should then be designed so that when 20 mm of Hg is applied over the  
13 area of the cushion supported by that spring, the spring compresses without buckling, but when  
14 25 mm of Hg are applied over the same area, the spring buckles. The ends of the free-standing  
15 coil springs can be supported by being inter-laced in a network of criss-crossing lateral springs,  
16 much as is done in spring units of prior art mattresses. The difference between the springs of my  
17 invented cushion and the prior-art mattress spring units is that prior art springs are designed to be  
18 stable against buckling and only compress when loaded, whereas the springs of my invention are  
19 unstable and will buckle if overloaded.

20 Elastomers such as rubbers, oil gels, silicones, polyurethanes, plastisols and the like will  
21 also work with the invention. Unlike the gel hollow-column shared-wall cushions described

1 above, however, the buckling members of this invention must be free standing.

2 Flexible open-cell polyethene-based polyurethane foams, such as is widely and  
3 commonly used in the furniture and mattress industry, work well in the invention. One of the  
4 characteristics of the invention is that a foam cushion with buckling members is considerably  
5 softer overall than a cushion of the same dimension made of 'solid' foam. Thus, a much stiffer,  
6 denser foam can be used with the same overall cushion durometer, and since denser foams are  
7 much stronger and more durable than lighter foams, the overall durability of the cushion can be  
8 greater than the 'solid' foam cushion being replaced with the invented cushion. The invention  
9 includes a unique process for fabricating foam cushions with buckling members which has low  
10 labor requirements and minimal waste, thus keeping cost to a minimum. This process, along  
11 with the embodiment of the invention in two types of foam cushions, are illustrated by the  
12 following examples. These examples are by way of illustration, and should not be construed to  
13 limit my invention.

14 The first example is as follows. A bun (such as 30" high, 80" long, 60" wide) of high-  
15 resiliency polyether-based polyurethane flexible foam is purchased from a foam manufacturer,  
16 with an ILD of 50 and a density of 2.8 pounds per cubic foot (considered very durable). A solid  
17 foam mattress with an ILD of 50 would be much too firm for the typical consumer. However,  
18 the cushion of this example is much softer than a 'solid' slab of 50 ILD foam. Figure 43 shows a  
19 cutting pattern 4301. Each dashed line 4302 shows a cut all the way through the width of the  
20 bun (i.e., into the paper). These cuts are made by a CNC reciprocal saw such as is made by  
21 Baumer USA and is well known in the art. The bun is then turned 90 degrees and cut in a similar

1 fashion as shown in Figure 44 using its cutting pattern 4401. When the bun is disassembled as  
2 shown in Figure 45, and the thin disconnected sections are removed, the resulting foam pieces  
3 4501, 4502, 4503, 4504, 4505 and 4506 are bonded together with any of several common foam  
4 adhesives to result in the mattress core 4601 of Figure 46. Figure 47 depicts foam side support  
5 pieces 4701 having been inserted into receptacles 4702 in all four sides of the foam unit 4703. A  
6 cover can then be applied by methods well known in the art. The mattress core has one-piece  
7 foam skins which are integral with and which support the many square cross section free-  
8 standing columns of square cross section within the core.

9 Figure 48 shows half of the mattress core 4801 before bonding to the other half,  
10 illustrating the individual square half-columns. The half-columns become full columns when the  
11 piece is bonded to a like piece of opposite orientation. This mattress cushion is capable of high  
12 local deformations due to the buckling of the square columns within the cushion. A person lying  
13 on his side on this mattress has the feeling that there is no significant pressure on his hips or  
14 shoulders, but that his torso is receiving sufficient pressure that sagging of the back does not  
15 occur.

16 The second example is as follows. A bun (such as 30" high, 80" long, 60" wide) of high-  
17 resiliency polyether-based polyurethane flexible foam is purchased from a foam manufacturer,  
18 with an ILD of 50 and a density of 2.8 pounds per cubic foot (considered very durable). Figure  
19 51 shows a preferred cutting pattern 5101. Each dashed line shows a cut all the way through the  
20 width (into the paper). These cuts are made by a CNC reciprocal saw such as is made by Baumer  
21 USA and is well known in the art. This is a simpler pattern, and quicker to cut, than the

1 illustration of the previous example As a further contrast to the previous example, this bun is cut  
2 from only one direction rather than turned 90 degrees and cut a second time. When the bun is  
3 disassembled as shown in Figure 52, very little is discarded. The resulting foam pieces 5201-  
4 5212 are bonded together as shown in Figures 52 and 53 with rails 5201 and 5202 being bonded  
5 with any of several common foam adhesives to result in the mattress core of the previous  
6 example. A cover is then applied. The mattress core has one-piece foam skins which are integral  
7 with and which support the foam free-standing rectangular rail within the core. These are the  
8 type of rails described above as effectively having one degree of freedom. While this may  
9 reduce the overall effectiveness of the cushion compared to buckling members with multiple  
10 degrees of freedom, it is still effective and results in a less expensive mattress to produce because  
11 cutting time is reduced and waste is minimized.

12 This mattress cushion is capable of high local deformations due to the buckling of the  
13 rectangular rails within the cushion. A person lying on his side on this mattress has the feeling  
14 that there is no significant pressure on his hips or shoulders, but that his torso is receiving  
15 sufficient pressure that sagging of the back does not occur. Figure 54 shows how the rail  
16 members 5402 buckle 5401 under the more protruding parts of the body 5401.

17 Buckling members, because they do not support load effectively, also do not transmit  
18 vibration, shock, or movement effectively. Thus the cushions of the invention are effective in  
19 cushions which have such requirements. Further, the cushions of the invention are softer than  
20 cushions made from the same types of materials without buckling columns. In part, this is  
21 because material is missing around my free-standing buckling members. But more significantly,

1 the cushions are able to locally deform without dragging down the surrounding material to the  
2 extent that 'solid' cushions do.

3       The cushions of this invention, as illustrated but not limited to the examples above, create  
4 a cushion different from and superior to the prior art in several ways. The cushions are very  
5 effective at pressure redistribution and equalization because the buckling member are incapable  
6 of taking more than their area share of the load, and surrounding members pick up the load that is  
7 'refused' by the buckled members. The cushions are effective at absorption/attenuation of  
8 vibration, shock, and movement because buckled columns do not transmit these as well as 'solid'  
9 material or structurally sound members. The cushions are very soft because they allow local  
10 deformation with less dragging down of the surrounding material. Unlike elastomeric  
11 compression cushions, my cushions do push back in linear proportion to the deformation of the  
12 cushion; thus pressure hot-spots are minimized, and support is even (e.g., back doesn't sag on a  
13 mattress). Unlike bladderized flowable-medium cushions, the invented cushions cannot leak, are  
14 very light weight, are low cost, have less tendency to crush down over time (because higher  
15 density foams are usable), and has no hammocking and therefore none of the associated  
16 problems. Unlike cushions comprising hollow gel columns with shared walls, these cushions are  
17 very light weight, less expensive to produce, and bond well to other cushion components (e.g., a  
18 mattress cover or furniture cushion cover).

## 19                   2.       Methods and Apparatuses for Providing Border Stiffness Around a 20                   Cushion 21

22       This embodiment of the invention is in the area of methods of cushion borders. More



1 specifically, this embodiment of the invention includes methods and apparatuses for  
2 advantageously and economically stiffening the edges of hollow-columned low-durometer  
3 elastomer cushions (such as described above) while providing lateral tension on the elastomer  
4 structure.

5         Gelatinous hollow-columned low-durometer elastomer cushions such as those described  
6 above make very effective cushions by equalizing pressure across an uneven person or object.  
7 Unfortunately, these cushions are not very laterally stable especially when made with thin walled  
8 hollow columns. They are more stable when the column walls are at least one third of the  
9 column width, but the weight and cost are much too high for most practical applications. When a  
10 more practical thin-wall hollow column configuration is used, the cushion easily collapses  
11 sideways. A need thus exists for a border which will keep the hollow column from collapsing  
12 laterally. Practical experiments with hollow column have also shown that if a small degree of  
13 lateral bi-axial tension is applied to the hollow column (in other words, it is kept a bit stretched  
14 out so it is tight), it is more effective in providing good support and pressure equalization.

15         Another problem with thin-wall hollow column cushions, particularly in mattress  
16 applications, is that when the columns collapse, only a small portion of the original height  
17 remains. Sitting on the edge of a mattress thus leaves the sitter feeling unsupported and perhaps  
18 unstable. A need exists for a border for hollow column cushions including but not limited to  
19 mattresses which will be more substantial for needs including but not limited to sitting.

20         This discussion will focus on mattresses as typical, but this invention applies to all  
21 hollow-column cushions. The mattress industry has developed many borders. For example, a

1 classic waterbed has wooden sides. A “foundation” waterbed, which appears more like a  
2 traditional mattress, has a very stiff flexible open-cell polyurethane border several inches wide  
3 around the entire perimeter of the water bladder area, inside the cover. It must be stiff --  
4 unacceptably stiff -- because it is not attached mechanically to the inner water bladder(s), and  
5 even if it was they would provide little support. Spring mattresses are made of coil springs  
6 joined at their tops by smaller diameter lateral coil springs, and do not provide sufficient edge  
7 support by themselves. Manufacturers of spring mattresses thus use well known border systems  
8 which included edge wires and edge clips and other known devices to stiffen and strengthen the  
9 edges of the mattress. Manufacturers of latex foam rubber mattresses often put a border of  
10 polyurethane foam around the perimeter of the latex core before applying the cover, in a manner  
11 known as a “racetrack”. The foam is stiffer than the floppy latex, but not so stiff as to be  
12 uncomfortable as with the foundation waterbed mattresses.

13 An open-cell flexible foam border would be very acceptable on the perimeter of a hollow  
14 column mattress core within a mattress cover. Unfortunately, unlike with a latex foam rubber  
15 core, the foam cannot be glued to the hollow column gel because the oil component of the gel  
16 prevents reliable bonding with known practical adhesives. It would not be desirable to use a very  
17 stiff foam as with the foundation waterbed mattresses, because they are uncomfortable. Thus a  
18 method is needed to economically and reliably attach a foam border to a hollow column gel  
19 cushion perimeter. A further need exists for a method to provide sufficient stiffness to the border  
20 to pre-tension the hollow column laterally without ruining the sitting feel of the border.

21 This embodiment of the invention is to encapsulate one or more outer cell walls of a

1 hollow-column buckling cushion within a border material or group of materials so as to  
2 physically interlock the hollow column gel and the border. Added features of the invention are  
3 (1) means to prevent the border so formed from being taller than the hollow column gel by  
4 removing a portion of one or more exterior cell walls in the hollow column gel to allow the  
5 border material(s) to be continuous across what would otherwise be solid elastomer wall and (2)  
6 to reinforce the border with another member which would allow lateral pre-tensioning of the  
7 hollow column gel without putting so much lateral load on the border material(s) as to bend the  
8 border beyond desirable limits. The invention is best illustrated by means of examples, which  
9 are not to be interpreted as limiting the above invention description in any way.

10 Figure 55 shows a 6" tall hollow column gel mattress core 5501. The mattress core 5501  
11 includes foam pieces 5502 stuffed into each outer perimeter cell of the hollow column gel. They  
12 are adhesively bonded to an exterior piece of foam through holes 5503 punched in the hollow  
13 column gel outer walls. The inner and outer foam pieces are optionally further joined by a cap  
14 top and bottom 5504 and 5504, in this case made from foam felt. A fiberglass rod 5506 is  
15 inserted through holes punched in the interior walls of the hollow column gel and through the  
16 foam pieces stuffed into the outer cells. This rod does not overly interfere with the sitting  
17 comfort of the cushion because it is buried so deeply in the soft foam of the border. The rod is  
18 very stiff and thus allows lateral pre-tensioning of the hollow column gel. The rod is joined to  
19 other rods around the periphery by lugs at the four corners of the hollow column gel.

20 Another example is depicted in Figure 56. That figure shows the configuration of Figure  
21 55 but with an additional layer of softer "pillow-top" style hollow column gel atop the stiffened

1 hollow column gel mattress core. The encapsulation of the hollow column gel sides within the  
2 foam border 5602 involves several perimeter rows of cells, and keeps the hollow column gel  
3 pillow-top 5601 securely in place so that it cannot collapse laterally.

4 Figure 57 depicts a configuration similar to that of Figure 56 but with two "pillow-top"  
5 hollow column gel layers 5701 and 5702 encapsulated within the foam border.

6 Figure 58 shows a border configuration made from two pieces of foam per side of the  
7 mattress core. A hollow column gel cushioning element 5801 is provided with fiberglass rods  
8 5802 as discussed. A first foam border layer 5803 and a second foam border layer 5804 are  
9 provided for border stiffness. This is anticipated to require less labor input than the individual  
10 cell foam pieces of the prior examples because there are less pieces to handle. This requires that  
11 the pieces be continuous across the first hollow column gel cell wall. The cell walls were thus  
12 beveled 5805 as shown to allow this continuity.

13 Figure 59 shows the configuration of the previous example but with an additional layer of  
14 softer "pillow-top" style hollow column gel 5901 atop the mattress core 5801. The encapsulation  
15 of the core 5801 sides within the foam border 5903 and 5804 keeps the pillow top layer 5901  
16 securely in place so that it cannot collapse laterally, and does not increase the number of foam  
17 pieces needed.

18 Figure 60 shows a fixture 6000 which assists in installing the foam pieces of the previous  
19 two examples. Without such a fixture, it is difficult to get the adhesive-coated foam uniformly  
20 into the outer row of hollow column gel cells. Figures 60a and 60b show the fixture 6000 with  
21 the foam 6001 inserted and not inserted respectively. Figures 7, 8, and 9 show the method used

1 in conjunction with this fixture. Figure 61 depicts the fixture 6000 in use with the foam 6001  
2 being inserted into the fixture so that the slit foam is inserted into the hollow column gel 6003  
3 cells. The foam and the hollow column gel should be glued for assembly. When the fixture is  
4 removed, the foam will expand to fill the hollow columns of the hollow column gel, keeping the  
5 pieces assembled until the glue can dry.

6 Figure 62 shows a method for use in conjunction with the foam border of this invention  
7 to allow lateral pre-tensioning of the hollow column gel without a fiberglass rod. A layer of  
8 foam which spans the entire hollow column gel mattress core surface is bonded to the border  
9 form on the bottom of the mattress core, and optionally on the top as well. Thus, there is a  
10 hollow column gel core 6201 with a layer of foam on top and bottom 6205a and 6205b, and a  
11 layer of foam 6202 and 6203 around the outer periphery of the hollow column gel. This ensures  
12 that the user will not feel anything hard as may happen with the fiberglass rod. When the weight  
13 of the mattress core descends on this foam layer, it will gently force it to be straight, keeping the  
14 foam border, which is bonded to it, from bending in from the lateral tension on the hollow  
15 column gel. The foam layer(s) have the added advantage of making 'bottoming out' through the  
16 hollow column gel more comfortable experience when, for example, kneeling on the bed.

17 Figure 63 shows a hollow column gel 'pillow-top' 6301 that can be laid over any mattress  
18 regardless of construction. It uses a hollow column gel core 6302 and a foam border 6303 that  
19 consists of pieces of foam stuffed into the outer two rows of cells of the hollow column gel and  
20 bonded to an exterior piece of foam by means of a bridging member. This border assembly is  
21 then glued into a fabric cover 6304, which is hook-and-loop attached to the mattress below so

1 that the hollow column gel can be pretensioned.

2 Figure 64 shows a pillow-top of hollow column gel 6401 similar to that of the previous  
3 figure except that it has two layers of hollow column gel 6402 and 6403 pillow-top material.

4 The invention is not limited to any particular border material or hollow column gel  
5 material. The key features are to encapsulate one or more outer cell walls of a hollow-column  
6 buckling cushion within a border material or group of materials so as to physically interlock the  
7 hollow column gel and the border. Added features of the invention are (1) means to prevent the  
8 border so formed from being taller than the hollow column gel by removing a portion of one or  
9 more exterior cell walls in the hollow column gel to allow the border material(s) to be continuous  
10 across what would otherwise be solid elastomer wall and (2) to reinforce the border with another  
11 member which would allow lateral pre-tensioning of the hollow column gel without putting so  
12 much lateral load on the border material(s) as to bend the border beyond desirable limits. While  
13 open-cell flexible polyurethane foam is the preferred border material, other materials could be  
14 used, including wood, air bladders, metal, plastic, closed cell foams, latex foams, rubber,  
15 synthetic elastomers in solid or hollow configurations, etc. Rigid members of any type may be  
16 used in place of the preferred fiberglass rods, including metal, wood, plastic, etc. Flexible  
17 members of any type may be used in place of the preferred open-cell polyurethane foam layer  
18 that spans the mattress surface, including thermoplastic films, elastomer films, rubber sheets,  
19 closed cell elastomeric foam sheets, felt, reticulated foam, etc.

### 20 3. Rigid, Collapsible Mattress Foundations

21 This invention is in the area of foundations for conventional bed mattresses and other  
22

1 mattresses of similar construction. More specifically, this invention relates to a foundation, for  
2 use in supporting a conventional mattress such as an innerspring or foam mattress, which  
3 collapses to ship in a more compact fashion to save shipping costs, has exceptional durability and  
4 function, and provides a non-slip mattress interface surface, and for methods of making such  
5 foundations.

6 Mattresses and foundations are often bought in sets at retail furniture stores. The  
7 foundation (sometimes called a box spring) is generally to be set into a steel angle-iron frame or  
8 frame of other materials such as wood. The frame holds the foundation off the floor. The  
9 foundation in turn supports the mattress, which is usually a separate piece. The mattress's main  
10 function is to provide cushioning in a supportive manner, and typically contains springs, foam,  
11 fiber batting, and the like. The foundation's main function is to provide support for the relatively  
12 floppy mattress so that the mattress does not sag. Another function is to lift the mattress to a  
13 proper height for egress, ingress, and sitting.

14 Prior art foundations are made in a number of ways. Designers of foundations have  
15 several criteria. First is the structural stiffness necessary so that the mattress cannot sag overall  
16 nor have local bulk deformation. Second is the creation of space sufficient to lift the mattress to  
17 the proper height; foundations are often in the 7" to 8" high range. Third is aesthetics, wherein it  
18 is desired that the foundation has upholstery that matches the cover of the mattress. Fourth is to  
19 meet the first and second, and optionally the third, criteria at the absolutely lowest costs. This  
20 fourth criterion often compromises the first two or three. Foundations are often made which  
21 have inadequate structural support in the bulk and/or local sense, or which have fabrics over the

1 top or bottom which rip easily. Foundations are often made by attaching metal wire structures to  
2 a grid of stapled 1x2 lumber, then surrounding the assembly with a cover which consists of a  
3 mattress ticking around the sides (to match the mattress) and a light gauze-like fabric on the  
4 top/bottom. This gauze-like fabric rips easily and is the source of frustration for many mattress  
5 owners that attempt to move their foundation from one room or residence to another. The metal  
6 wire structures do not provide a uniform solid surface on which the mattress can rest, allowing  
7 local deformation of the mattress. To save cost, many mattress manufacturers put in too few  
8 metal wire structures, or structures with wire that is too thin. Manufacturers of high quality  
9 foundations must attach a price tag that limits the number of customers they will have. Another  
10 problem is that foundations are bulky and non-compressible and it is expensive to ship them  
11 from one place to another. This applies to over-the-road shipping as well as local delivery truck  
12 shipping. In addition to taking up too much room in an over-the-road semi-truck, a prior art  
13 foundation will not be shipped by such carriers as UPS because it exceeds their size limits. A  
14 mattress foundation which could be so compact as to ship by UPS, which has a 130-inch limit on  
15 height plus girth, would save shippers and thus consumer a lot of money, and enable products to  
16 become nationally distributed which are otherwise limited to being regional. Another problem  
17 with the prior art is that the gauze-like fabrics, or even higher-quality mattress tickings used by  
18 high-quality manufacturers, allow the mattress to slip and slide on the foundation, causing the  
19 need for constant positional adjustment by the accordingly frustrated end user.

20 There thus exists a need for a mattress foundation which ships in a more compact fashion,  
21 has exceptional durability, does not allow local or bulk deformation on even heavy mattresses,



1 provides a non-slip mattress interface surface, and achieves all of this at very low cost. A further  
2 need exists for such a mattress foundation which can be made so compact as to ship via local  
3 delivery truck in one or more packages and does not require complicated assembly by an end  
4 user.

5 This embodiment of the invention is a mattress foundation comprising a relatively rigid  
6 top and separate or separable sides and/or ends. The separate/separable sides and/or ends either  
7 easily disassemble from the top or fold into parallel with the top.

8 In one preferred embodiment of the invention, which is shown in Figures 65 and 66 and  
9 which is easily shippable, the foundation is divided into six segments . Each segment has a  $\frac{1}{4}$ -  
10 inch thick plywood top, under which is stapled a grid of 1x2 lumber on approximately 14-inch  
11 centers, with the 1.50" dimension of the (nominal) 1x2 lumber orthogonal to the plane of the  
12 plywood. The plywood overlaps the grid of 1x2's by  $\frac{1}{4}$ -inch. The total thickness of this "top" is  
13 1.75", so six of them can be stacked and shipped via UPS even in a king-size foundation, in  
14 which the dimensions of each top would be approximately 37 inches by 26 inches. In a separate  
15 container, the frame is shipped as separate boards in a narrow stack. The frame consists of  $\frac{1}{4}$ -  
16 inch thick plywood slats (seven, in the case of the foundation 6501 of Figure 65) which are  
17 joined by plastic extruded pieces which slip over slots machined into the slats (well known in the  
18 waterbed art as part of a much different type of foundation used in conjunction with a wooden  
19 waterbed). The center three slats are notched to allow them to all have their top surfaces at the  
20 same level. Figure 66 shows the six tops all set into the frame 6601. Attaching the tops to the  
21 frame is not necessary, since the angle-iron bed frame constrains the frame, as does each of the

1 six tops, from distorting in the plane of the mattress. The mattress weight keeps the tops from  
2 coming up out of the frame, while the 1/4-inch overhang on each top prevents the top from going  
3 down through the frame. Thus the foundation is constrained in all directions and the tops do not  
4 need to be attached by mechanical means. To move the foundation from one room or residence  
5 to another, one simply lifts out the six tops, removes the plastic connectors, and moves them  
6 independently, then reassembles them in the new room. All is done without any tools, and is  
7 very simple. The plywood top is continuous, is rigid and made even more rigid by the 1x2 grid,  
8 and the bulk stiffness of the foundation is ensured by the multi-board frame. The top of the  
9 plywood can be sprayed or rolled with a pigmented solvated rubber-like thermoplastic elastomer,  
10 such as any of the Kraton D elastomers from Shell Chemical mixed with toluene, and the solvent  
11 allowed to evaporate. Alternatively, the elastomer can be melted and applied in the molten state.  
12 The remaining thin layer of rubber-like material creates a non-slip mattress surface, and the  
13 pigment hides the plywood. The outer slats of the frame can be covered at the manufacturing  
14 stage with upholstery material to match the mattress, and when combined with the pigmented  
15 tops create a very aesthetically attractive look. The durability of the foundation is assured by the  
16 use of durable construction materials such as plywood; there are no gauze-like fabrics to be  
17 easily ripped or other non-durable materials. The cost is sufficiently low to be an attractive  
18 feature of my invention. The total direct labor and material cost of a queen-sized foundation is  
19 expected to be less than US \$20.00, which is on par with the cheapest gauze-covered foundations  
20 of the prior art. The weight of a queen-size foundation in accordance with this preferred  
21 embodiment is expected to be less than 50 pounds, on par with other poorer quality foundations.

1 Another preferred embodiment of the invention is geared toward shipping in conventional  
2 semi-trucks and local delivery trucks. Retail mattress sellers generally would find any assembly  
3 undesirable, even the small amount of assembly described in the above easily shippable  
4 embodiment. This alternate preferred embodiment is illustrated in Figures 67a-e. A ¼-inch  
5 thick plywood top which spans the entire mattress foundation is used, under which is stapled a  
6 grid of 1x2 lumber on approximately 14-inch centers, with the 1.50" dimension of the (nominal)  
7 1x2 lumber orthogonal to the plane of the plywood. The plywood is flush with the edge of the  
8 grid of 1x2's. ¼-inch thick plywood ends and sides are hinged to the top and fold in as shown in  
9 the previous figures. The overall assembly is only 2.3 inches thick when folded, so it ships in  
10 less than 1/3 the space of a prior art 7-inch thick foundation. Figure 67e shows the foundations  
11 of this preferred embodiment stacked compactly for shipment. The retailer will drive the still-  
12 compact foundation to the customer's home, unfold the sides and ends in a simple motion, and  
13 attach the sides and ends to each other at the four corners. This attachment involves only the  
14 lining up of the corners and the guiding in of a pre-installed attachment, such as a barbed male-  
15 in-female attachment which does not come out once installed. Instructions for fabricating this  
16 preferred embodiment are as follows:

- 17 1. Cut all plywood, 1x2 lumber, fabric, foam, and galvanized strips to size.
- 18 2. Staple (or nail) the width-wise continuous slats flush all around with the edges of  
19 the top plywood. Make sure any width-wise seam between two pieces of plywood  
20 is centered on a slat and that each piece of plywood is independently fastened to  
21 that slat.

3. Staple (or nail) the length-wise slats to the width-wise slats and to the top plywood. Use marking template as needed to ensure that the staples through the top plywood are centered on the slats. Make sure any length-wise seam between two pieces of plywood is centered on a slat and that each piece of plywood is independently fastened to that slat.
4. Using four screws per strip, screw one side of the 9" galvanized strips to the end and side panels. For twin size foundations, there will be two on each end panel and three on each side panel. For all other sizes, there will be three on each end panel and three on each side panel. They should be evenly spaced apart. Note that on the end panels, the outside strips should be 5.5" from the panel ends (so as not to interfere with the unfolding of the side panels), whereas for the side panels, the outside strips should be flush with the panel ends.
5. Place the foam (without adhesive) on a plywood side panel. Place the fabric over the foam and wrap around to the back under reasonable tension. It will overlap ½-inch on all four edges onto the back. Staple the fabric under tension to the back on all four edges. Note: These should be normal wood staples, not the kind coated with hot-melt adhesive that will be used for the top-to-slat stapling. Repeat for the other side panel and the two end panels.
6. Attach a plywood spacer to the 1x2's in every place where there is a galvanized strip on the corresponding end panel.
7. Keeping the side and end panels parallel to (but not even with) the top plywood,

1 attach the side and end panels to the perimeter 1x2's by screwing on the  
2 galvanized strips. Again use four screws per strip.

3 8. Fold in the side panels.

4 Another preferred embodiment is illustrated in Figures 68a and 68b. This foundation  
5 6801 consists of a ¼-inch thick plywood top 6802 but in this case has no 1x2 stiffener grid as in  
6 the previous two examples. It has a fold-down side as in the previous example. The fold-down  
7 ends of example 2 exist, and are accompanied by a series of internal panels similar to the ends  
8 except not upholstered. These interior panels act to stiffen the plywood top in lieu of the 1x2  
9 grid. The end and interior panels fold down an orthogonal angle to the top. The side panels do  
10 so also, and have slots machined in their sides to receive the edges of the side and interior panels.

11 This embodiment enjoys similar cost and weight and performance advantages of the previous  
12 examples, with similarly low assembly-on-site labor. However, this embodiment ships even  
13 more compactly, with a folded width of less than 1 inch. Thus more than seven foundations can  
14 be shipped in the space occupied by one prior art foundation.

15 Another preferred embodiment utilizes a plywood/grid top as in another example above  
16 but without the fold-down sides and ends. The top is built to have a ¼-inch overlap of the  
17 plywood from the 1x2 grid. The top is set into a border frame, consisting of integral sides and  
18 ends. The top may be attached or not as preferred. The sides and ends are angled from vertical  
19 slightly to allow stacking of the border frames. If the tops are attached, the foundations can still  
20 stack compactly. If the frames are unattached, it may be advantageous to stack the border frames  
21 and the tops separately for maximum overall compaction. The border frame can be made of

1 wood or wood composites. It can also be made by forming plastic sheet into a frame, such as  
2 1/8"-inch thick polyethylene.

3 In the examples above, the top of the plywood can be sprayed with a pigmented solvated  
4 rubber-like thermoplastic to create a non-slip mattress surface, with the pigment hiding the  
5 plywood.

6 The invention is not limited to any particular material or specific configuration so long as  
7 it comprises a relatively rigid top and separate/separable sides which either easily  
8 assemble/disassemble from the top or fold into parallel with the top. The materials can be any  
9 economical structurally sound material, including but not limited to plywood, oriented strand  
10 board (OSB), chipboard, pressboard, plastic, metal, masonite, or composite materials. The top is  
11 preferred to be continuous but can be perforated or discontinuous so long as it provides the  
12 needed overall rigidity and does not have gaps so large as to allow the mattress to have localized  
13 deformation. The size of the allowed gaps depends on the floppiness of the mattress; e.g., a firm  
14 innerspring mattress can sit atop larger gaps than a foam mattress.

15 The mattress foundations of this invention, as illustrated by but not limited to the  
16 examples shown, are different from and superior to the prior art in several ways:

- 17 1. Unlike prior art foundations for conventional mattresses, my foundations ship more  
18 compactly, saving considerable expense in shipping and expanding the market area in which a  
19 mattress manufacturer can compete.
- 20 2. Unlike prior art foundations for conventional mattresses, my foundations are more rigid  
21 and thus allow less deformation both in an overall and a local sense.

1 3. Unlike prior art foundations for conventional mattresses which are inexpensive to  
2 produce, my foundations are more durable because all of the materials of construction are  
3 durable (no thin fabrics, etc.).

4 4. Unlike prior art foundations for conventional mattresses that use quality fabrics and are  
5 thus durable and that use sufficient metal spacers to effect high rigidity, my foundations are  
6 inexpensive to produce because I use the rigidity and durability of inexpensive materials such  
7 as plywood rather than labor-intensive and costly heavy steel wire structures bridged with  
8 quality fabrics.

9 5. Unlike prior art foundations for conventional mattresses, my invention allows for  
10 foundations which collapse to the point that they can be shipped local delivery truck, and even  
11 these versions of the invention do not require labor intensive or tool intensive assembly by the  
12 end user.

13 6. Unlike all known prior art mattress foundations, my foundations have an anti-slip option.

14 The main feature of this invention is separate/separable sides/ends in conjunction with a  
15 relatively rigid top or tops which enable(s) compact shipping. Some of the additional features  
16 of the invention include but are not limited to:

17 a. The optional use of ductile thin metal as hinges, usable because the hinges will be  
18 actuated very few times and so metal fatigue failure does not come into play.

19 b. The optional pre-application of fabric and other upholstery materials (such as foam) to  
20 the individual sides and/or ends of a foundation. In prior art foundations, such  
21 upholstery is only applied to the assembled foundation, which prevents some of the

1 features of my invention.

2 c. The optional use of a solvated elastomer or melted elastomer to facilitate the spray or  
3 roller application of the elastomer to a foundation top.

4 d. The optional use in general of a non-skid top in a mattress foundation.

5 e. In a foundation, the optional use of a grid (1x2's in the examples) firmly attached to a  
6 relatively thin skin (1/4-inch plywood in the examples) to provide an overall very stiff  
7 top and/or side and/or end structure.

8 f. The use of a barbed fastener or other low-labor fasteners to locate one foundation  
9 component relative to another.

### 10 **3. Podalic Pads**

11 The invention includes the manufacture and use of elastomeric or viscoelastomeric  
12 podalic pads using materials and or structures described herein.

### 13 **4. Elastomer Chews**

14 The invention also includes an elastomeric or viscoelastomeric chews. The material of  
15 the invention may be shaped for chewing and may be impregnated with a substances that slowly  
16 releases into the mouth while being chewed, such as medications, drugs, flavors, sweeteners,  
17 herbs, vitamins, minerals, dietary supplements, homeopathic remedies, and any other substance  
18 that is desired to be slowly released into the mouth. Most rubbers and elastomers are non-polar  
19 and have a definable solubility factor. Most substances to be released into the mouth ar polar and  
20 have a solubility factor different from elastomers. When blended with an elastomer, the  
21 substance to be released does not chemically bond with the elastomer, so during chewing the



1 substance to be released immediately separates from the elastomer. But when the invented  
2 materials are used, a polar bond is formed between the substance to be released and the  
3 elastomer, so that the substance to be released works out of the elastomer matrix slowly during  
4 chewing. Chewing the elastomer chew of the invention does not fatigue the jaw and mouth of  
5 the chewer as chewing gum does because the elastomer rebounds to its original shape during  
6 chewing rather than sticking to the teeth and creating suction as chewing gum does.

7 Referring to Figures 69a, 69b and 69c, a top view, front view and end view  
8 (respectively) of an elastomer chew 6901 of the invention are shown.

#### 9 **5. Cushions That Include Hollow Column Gel and a Second Cushioning** 10 **Element**

11 Referring to Figures 70-85, embodiments of the invention which include both a hollow  
12 column gel as described herein and at least a second cushioning element are shown. The  
13 advantages of buckling columns are already described herein. Combining buckling column  
14 cushions with another cushioning element and at least 30% void space in stacked sequence is  
15 very advantageous. The invention applies to many products including beds, mattresses,  
16 operating table pads, stretcher cushions, sofas, chairs, wheelchair seat cushions, vehicle seats,  
17 bicycle seats, forklift seats, truck seats, car seats, lawnmower seats, motorcycle seats, tractor  
18 seats, boat seats, plane seats, train seat and others.

19 Figure 70 depicts a 2" high hollow column gel elastomer 7001 with 1" square columns  
20 and 0.125" wall thickness topped with a quilted fiber top 7002 as is commonly found in the  
21 mattressing art. This allows the user of the cushion to enjoy breathability between his body and

1 the gel, and to avoid the high friction of contact with the gel. Further, since the gel will not  
2 touch the user's skin, the user will not feel cold on touching the cushion.

3 Figure 71 depicts a first hollow column gel cushioning element 7101, a second hollow  
4 column gel cushioning element 7102 and a quilted fiber top 7103 in stacked sequence. The  
5 firmness of the hollow column gel cushioning elements may be varied to increase the surface  
6 area of the user being cushioned.

7 Figure 72 depicts a tall gel column 7002 topped with a quilted top 7003 that includes  
8 fiber 7001 and foam 7004. The foam creates extra thickness and a bridging effect over the  
9 hollow columns, allowing large columns to be used, such as 6" tall, with 1.8" square holes and  
10 0.10" wall thickness. Greater hole size reduces weight and cost of the hollow column gel.

11 Figure 73 depicts a first hollow column gel 7301 that is 6" high and has 1.8" square holes  
12 and 0.10" wall thickness. A second hollow column gel 7302 is stacked thereon using 2" hollow  
13 columns with 1" square holes and 0.125" wall thickness. That is topped with a quilted top with  
14 fiber 7303. The short columns provide a plush bridging effect for the deep-sinking tall columns.

15 Figure 74 depicts two short hollow column gel elements 7401 and 7402 atop a tall hollow  
16 column gel element 7403 with large holes, the entire combination topped with a quilted top 7404.  
17 Durometers of the cushioning elements may be varied.

18 Figure 75 depicts a short cushioning element 7501 atop a thick layer of polyurethane  
19 foam 7502, the entire assembly being topped with a quilted top 7503.

20 Figure 76 depicts a thick layer of polyurethane foam 7601 on top of which is found a first  
21 7602 and a second 7603 short hollow column gel cushioning element, followed by a quilted top

1 7604. This configuration has good side stability.

2 Figure 77 depicts a slab of high grade visco foam 7701 on top of which is found a short  
3 hollow column gel element 7702 and a quilted top. Visco foam is also called gel foam and T-  
4 foam. Visco-form easily forms to the shape of the object being cushioned, while still providing  
5 side stability.

6 Figure 78 depicts a prior art spring unit 7801 which is well known, followed by a short  
7 unit of hollow column gel 7802 and a quilted top 7803. The gel columns in this embodiment  
8 overcome the peak pressure problems of spring units.

9 Figure 79 depicts a spring unit 7901 topped with a first 7902 and a second 7903 hollow  
10 column gel cushion and a quilted top 7904.

11 Figure 80 depicts use of a shallow spring unit 8001 topped with a thick hollow column  
12 gel unit 8002 using large columns, and the top layer 8003 being a quilted top with foam 8004 for  
13 bridging across the large columns.

14 Figure 81 depicts a slab of latex foam 8101 topped with a short hollow column gel unit  
15 8102 and a quilted top 8103.

16 Figure 82 depicts another embodiment of the invention with a base of tall hollow column  
17 gel with large columns 8201, followed by a latex foam rubber topper 8202 and a quilted top  
18 8203.

19 Figure 83 depicts a tall column hollow column gel element 8301 followed by a layer of  
20 latex foam 8302 and a quilted top 8303.

21 Figure 84 depicts a tall hollow column gel element 8401 followed by a layer of

1 polyurethane foam 8402 and a quilted top 8403.

2 Figure 85 depicts a tall unit of hollow column gel 8501 topped with a layer of pillow soft  
3 polyurethane foam 8502 and a quilted top 8503.

#### 4 6. Method for Extruding Large Internally Complex Discontinuous 5 Structures

6 A method for extruding cushioning shapes of the invention is provided below. The  
7 method permits the extrusion of polymeric parts of complex geometry which are short in cut-off  
8 length but of large dimension in one or more dimensions transverse to the material flow.

9 A significant problem in extrusion is differential cooling between the exterior and interior  
10 of the part causing shrinkage and part deformation. Another problem is that air pressure  
11 differences in the part interior causes part blow up or collapse. The larger the extruded part, the  
12 greater these problems are. When hollow column gel parts of the invention are made, the parts  
13 will preferably be very large, such as at least 45 inches square. In the prior art it was not  
14 considered possible to manufacture large, low-durometer gel products, such as the hollow  
15 column gel cushioning elements of the invention, by extrusion, particularly if the part to be  
16 extruded is floppy and does not stand under its own weight.

17 Referring to Figure 86, a novel extrusion die is depicted. The die is useful in extruding a  
18 king sized mattress core in a single piece, the overall dimensions of which are 76 inches by 79.5  
19 inches by 6 inches thick. Internally, the preferred mattress core would include hollow square  
20 columns of about 2 inches by 2 inches with a wall thickness of about 0.10 inches. The gelatinous  
21 elastomer or viscoelastomer to be used is as described elsewhere herein, but is low durometer

1 and floppy.

2 The extrusion die 8601 is constructed as follows. Note that the figure depicts only a  
3 portion of the whole die, for simplicity. A steel base plate 8602 of about 80 x 84 inches is  
4 machined flat to a thickness of about 1 inch. Aluminum cores 8603 are provided attached to the  
5 base plate. The aluminum cores are machined to about 1.95" x 1.95" x 1.5". The cores are  
6 attached to the base plate with a spacing of 0.10" in order to create hollow column gel with 0.10"  
7 wall thickness. As molten elastomer floods through the space between the cores, the desired  
8 cushioning element shape is formed. A cap plate 8604 is attached to the base plate, of the same  
9 dimension as the base plate. Runners are machined into the base plate and the cap to permit  
10 molten elastomer to be forced therethrough by a press of sufficient strength. Small holes 8605  
11 are drilled between the runners and the spaces 8606 or runways between the cores 8603 to permit  
12 molten elastomer to flow from the runners through the holes and through the runways to form a  
13 cushioning element. The molten material can flow through the runners much more easily than  
14 through the small drilled holes, resulting in reasonably equalized pressure as the molten material  
15 moves through the runways 8605. Molten material enters the die 8601 at an input and exits the  
16 die 8601 at an output 8608. As the material exits the die at the output, it is immediately cooled  
17 in a water bath 8609 so that from the water bath exit 8610 a frozen finished part is produced.  
18 The use of a water bath stabilizes the part shape. As material exits the die and enters the water  
19 bath, at an appropriate dimension it will be cut according to a prior art cutting method. Air  
20 pressure is not needed within the part because the water bath provides even cooling and part  
21 shape stability. In the water bath, there is no tendency of gravity to cause sidewall collapse of

1 the part. The specific gravity of the preferred elastomer is 0.88, near enough the specific  
2 gravity of water (1.0) such that bouyancy will not deform the part.

3 It is preferred that the water bath be at or near boiling. This is because as the water inside  
4 of cells of the hollow column gel heats up from the cooling process, it would create a  
5 temperature differential with water outside of the cells which does not heat up as much. Transfer  
6 of heat from the elastomer to the water causes steam. Vent holes in the cores and plates are  
7 provided to accommodate release of this steam.

8 Although the preferred coolant is water, other flowable cooling mediums could be used,  
9 such as air, glycerin, propylene glycol, oil, plastic beads, hydraulic fluid, heat transfer fluid, and  
10 other materials that do not deform the elastomer part. If stiff parts are being made, air may be an  
11 appropriate coolant. In some instances, such as with a low specific gravity part, it is desired to  
12 cut the part off from the die before it enters the water to avoid deformation due to bouyancy.

13 The extrusion preferred in this invention is downward extrusion into water, but upward  
14 extrusion is also contemplated. In such a case, the coolant would be in direct contact with the die  
15 face and the die face would be in a tank of coolant. Parts would tend to buoy up in the coolant as  
16 they exit the die.

## 17 **7. Gel-Coated Fabrics**

18 Another embodiment of the invention is to coat fabrics etc. with a highly plasticized A-B-  
19 A tri-block co-polymer of the SEPS, SEEPS or SEEEPS variety (styrene-[ethylene-ethylene-  
20 propylene]-styrene or styrene-[ethylene-ethylene-ethylene-propylene]-styrene). The EEEP mid-  
21 block is preferably of very high molecular weight, such that the solution viscosity is so high as to

1 be essentially a solid when at 20% solids in toluene @ 25 degrees C. Preferably, the plasticizer  
2 is a white paraffinic mineral oil such as Witco LP-200. Preferably, an fluorochemical such as  
3 Dupont Zonyl BA-N is added to slow or completely prevent the wicking out of the plasticizer.  
4 My most preferred SEEPS tri-block co-polymer is Septon 4055 by Kuraray of Japan. Septon  
5 4055 is a solid elastomeric gel when combined with toluene at 20% solids @ 25 degrees C, and  
6 not a liquid at all, so that solution viscosity is a meaningless term for Septon 4055 Septon 4055  
7 exhibits less plasticizer wicking than other copolymers, and produces a stronger and more  
8 durable gel.

9 The most preferred plasticizer to copolymer ratio for fabric coatings is in the range of 4-  
10 to-1 to 2-to-1. More or less plasticizer is allowable within the scope of the invention. More  
11 plasticizer is not preferred for most applications because the tackiness of the gel is higher as  
12 plasticizer content increases. Less plasticizer is not preferred for most applications because the  
13 lower the plasticizer content, the more effect on suppleness will be noticed.

14 The need exists for an additive which substantially reduces and preferably completes  
15 stops wicking of the plasticizer. The fabric coating of my invention thus preferably includes an  
16 additive such as is fully described above. As stated above, my most preferred additive is  
17 Dupont's fluorochemical alcohol Zonyl BA-N, added at 0.05% to 0.75%, typically 0.20% to  
18 0.35%, of the total gel weight. Other fluorochemicals, particularly fluorochemical alcohols and  
19 surfactants, are also preferred anti-wicking additives in the coating of the invention.

20 The results of applying my preferred gel coating to a fabric are excellent. Because the  
21 durometer is so low (Shore A10 at the highest, but usually well below the Shore A scale

1 altogether), the suppleness of the fabric is virtually unaffected. Since it can stretch to as much as  
2 twenty times its original length without permanent set, and since it is of such low durometer, the  
3 stretchiness of fabrics such as Dupont's Lycra is virtually unaffected. It is essentially water-  
4 proof. It has a low degree of air permeability, so that in very thin coatings it allows some  
5 breathing of air and vapors, and with somewhat thicker coatings is for all practical purposes gas  
6 impermeable. It is very lightweight, with a density of 0.86 to 0.88 grams per cubic centimeter  
7 (as a comparison, silicone gel is about 0.98, polyurethane film is about 1.25, and rubber density  
8 varies depending on fillers used but is generally more than that of my preferred gel. It is  
9 relatively inexpensive, costing about 80% as much as Mr. Chen's preferred gels, 50% as much as  
10 neoprene, and 30% as much as polyurethane film. It does not wick plasticizer at all at room  
11 temperature when placed next to photocopier paper.

12 The preferred gel can be applied to fabrics in a variety of ways. One preferred method is  
13 to solvate the gel ingredients in toluene or another organic solvent, using enough toluene to  
14 produce the viscosity desired. The solvated gel is coated onto the fabric by coating means well  
15 known in the art, such as a roller and doctor blade, then the toluene is evaporated off, usually  
16 with heat, and usually recovered so as to prevent air pollution. Another preferred method is to  
17 heat and shear the gel ingredients at sufficient temperature (usually 350 to 400 degrees F is  
18 sufficient) that a thoroughly molten and mixed fluid is obtained. The molten fluid is then coated  
19 onto the fabric with similar means as in the solvated case, and the molten gel is allowed to cool  
20 and solidify. Other means are also feasible, including but not limited to extruding the molten gel  
21 into a film, cooling it, then heat-laminating the film to the fabric. Other methods might include



1 hot molten gel spray and solvated gel spray.

2 The invention is not to be limited by the foregoing preferences and examples. Any type  
3 of fabric or other pliable, porous material (including but not limited to paper and foam) coated  
4 with or laminated to the range of gels described above or coated with or laminated to any  
5 plasticized elastomer containing anti-wicking additives or bleed-reducing additives as described  
6 above also falls within the scope of my invention. Any method of applying the coating or  
laminated layer of the invention is acceptable.

## 8. Summary of Some Alternative Embodiments

Referring to Figures 87-97, various alternative embodiments of the invention are  
depicted. Each of these is a cushioning device which may be incorporated into any type of  
cushion desired.

Figure 87 depicts a base of a non-skid (high friction) fabric 8701 on which a cushioning  
element 8702 is found topped by a pearlized chintz quilt with foam and fiber 8703. The  
cushioning element 8702 has buckling foam rails.

Figure 88 depicts a base of non-skid fabric 8801 under a buckling foam rail cushioning  
element 8802 and topped with a pearlized chintz pillow top with foam, convoluted foam and  
fiber.

Figure 89 depicts a base of Belgian damask tick 8901 on which a cushioning element  
8902 of foam buckling rails is place. On top of that is found a layer of supersoft latex foam 8903  
followed by a top of Belgian damask quilt with foam and fiber 8904.

Figure 90 depicts a base of Belgian damask tick 9001 which has a buckling rail

1 cushioning element 9002 on top of it with buckling rails in only one direction, followed by a  
2 buckling rail cushioning element 9003 that has buckling roam rails in two directions, followed by  
3 a layer of supersoft latex foam 9004 and a top of Belgian damask quilt with foam and fiber.

4 Figure 91 depicts a base of Belgian damask tick 9101 on which is a cushioning element  
5 9102 with buckling roam rails in two directions, a second cushioning element 9103 with  
6 buckling foam latex rails in two directions, a layer of supersoft latex foam 9104 and a top of  
7 Belgian damask tick with supersoft fiber.

8 Figure 92 depicts a base of Belgian damask tick 9201 on top of which is a cushioning  
9 element 9202 of hollow column gel surrounded by border-stiffening foam and a foam base, and a  
10 top 9203 of Belgian damask quilt with foam and fiber.

11 Figure 93 depicts a base 9301 of Belgian damask tick followed by a cushioning element  
12 9302 of gel hollow columns bordered by foam and with a foam base, followed by two-dimension  
13 buckling rail foam 9303 and a top of Belgian damask quilt with foam and fiber 9304.

14 Figure 94 depicts a base of non-skid fabric 9401 followed by mattress inner springs 9402,  
15 then by buckling rail foam with rails in two directions 9403 and a top of pearlized chintz quilt  
16 with foam and fiber.

17 Figure 95 depicts a base of Belgian damask tick 9501 under metal mattress inner springs  
18 9502 followed by a cushioning element 9503 with foam latex buckling rails in two directions,  
19 and a top 9504 of Belgian damask quilt with supersoft fiber.

20 Figure 96 depicts a cushioning element 9601 of buckling foam rails in two directions  
21 with foam borders, a foam base and a foam top, a second unit of 2 inches of memory foam 9602

1 and a stretch knit cover 9603.

2 Figure 97 depicts a cushioning element 9701 of buckling latex foam rails in two  
3 directions, with a layer 9702 of latex foam on top followed by a stretch knit cover 9704.  
4

5 The reader should note that any other manufacturing method may be used which results  
6 in a cushioning element having the general configuration of or achieving the object of this  
7 invention. Such other methods may include but are not limited to rotational molding of a  
8 cushioning media such as a hot liquid gel, and vacuum forming of sheets of a cushioning media  
9 such as gel.

10 While the present invention has been described and illustrated in conjunction with a  
11 number of specific embodiments, those skilled in the art will appreciate that variations and  
12 modifications may be made without departing from the principles of the invention as herein  
13 illustrated, described, and claimed.

14 The present invention may be embodied in other specific forms without departing from  
15 its spirit or essential characteristics. The described embodiments are to be considered in all  
16 respects as only illustrative, and not restrictive. The scope of the invention is, therefore,  
17 indicated by the appended claims, rather than by the foregoing description. All changes which  
18 come within the meaning and range of equivalency of the claims are to be embraced within their  
19 scope.

## CLAIMS

What is claimed is:

1. A method for manufacturing a gelatinous elastomer article comprising the steps of:
  - selecting ingredients for making the gelatinous elastomer,
  - obtaining the ingredients for making the gelatinous elastomer,
  - premixing the ingredients for making the gelatinous elastomer,
  - placing the ingredients for making the gelatinous elastomer into an input end of a compounding screw,
  - turning said compounding screw and exposing the ingredients for making the gelatinous elastomer to heat and pressure as the ingredients travel along the length of the screw so that the gelatinous elastomer ingredients are compounded to form a gelatinous elastomer,
  - receiving the gelatinous elastomer at its output end,
  - permitting said gelatinous elastomer to lost heat,
  - cutting said gelatinous elastomer into pellets,
  - storing said gelatinous elastomer pellets for a period of time,
  - placing said gelatinous elastomer pellets into an input end of a compounding screw,
  - turning said compounding screw and exposing said pellets to heat and pressure so that the pellets melt to form a gelatinous elastomer composition,
  - turning said compounding screw so that said gelatinous elastomer composition travels along the length of the screw to its output end,



## ABSTRACT

A cushion that includes a cushioning element. The cushioning element has a number of substantially parallel elongate columns formed in a soft, easily deformable elastic or visco-elastic cushioning media. The columns are configured so that when a force is applied to the cushioning element in a direction that is generally parallel to the longitudinal axes of the columns, the cushioning element will yield by compressability or deformability of the cushioning media, bucklability of the walls of the columns, or a combination of both. In particular, the walls of columns which are located beneath a protruberance on an object being cushioned tend to buckle, permitting the cushioning element to conform to the shape of the cushioned object while evenly distributing a supporting force across the contact area of the cushioned object and avoiding pressure peaks. The preferred cushioning media is a gelatinous elastomer or gelatinous viscoelastomer. Various configurations of cushioning elements, including sidewall supports, are disclosed.




FIG. 1




FIG. 2




FIG. 3




FIG. 4



3 / 45




FIG. 5




FIG. 6




FIG. 7




FIG. 8





FIG. 9






FIG. 11




FIG. 12




FIG. 13




FIG. 14




FIG. 15






FIG. 16








FIG. 19




FIG. 20




FIG. 21




FIG. 22




FIG. 23a




FIG. 23b




FIG. 23c




FIG. 23d




FIG. 24a




FIG. 24b





FIG. 25a






FIG. 25b








FIG. 25e




FIG. 25f




FIG. 26




FIG. 27a




FIG. 27b




FIG. 27c




FIG. 28





FIG. 29










FIG. 31a




FIG. 31b




FIG. 31c




FIG. 32a




FIG. 32b




FIG. 33a




FIG. 33b




FIG. 33c




FIG. 33d




FIG. 33e




FIG. 33f




FIG. 34a




FIG. 34b




FIG. 34c




FIG. 34d




FIG. 35a




FIG. 35b




FIG. 35c




FIG. 35d




FIG. 35e






FIG. 36a




FIG. 36b




FIG. 36c




FIG. 36d




FIG. 37a




FIG. 37b




FIG. 37c




FIG. 37d




FIG. 37e




FIG. 37f




FIG. 38a




FIG. 38b




FIG. 39a




FIG. 39b




FIG. 39c




FIG. 39d




FIG. 39e




FIG. 39f




FIG. 39g

3216




FIG. 39h

3216





FIG. 39i

3216








FIG. 40a






FIG. 40b




66E050" 66E0E60

FIGURE ~~42~~ 43

4301  
4302

Step 1: Cut foam bun (along dashed lines) with CNC contour cutter




Sc. 38

602030 62623200

FIGURE ~~44~~ 44


Step 2: Without disturbing the now cut ~~run~~, rotate it 90 degrees  
and make the same type of cuts in the other direction



SECRET

# FIGURE 45

Step 3: Separate the pieces and discard the thin sections




SECRET 46


FIGURE

4601

Step 4: Bond with adhesive





Step 5: Insert side support foam pieces (do not bond) all four sides 4703



4702

4701




Dimension (inches)	Twin	XL	Double	Double XL	Queen	King	Cal King
A	1.50	1.50	1.50	1.50	1.50	1.50	1.50
B	0.53	0.53	0.53	0.53	0.50	0.50	0.51
C	1.50	1.50	1.50	1.50	1.50	1.50	1.50
D	3.50	3.50	3.50	3.50	3.50	3.50	3.50
E	2.50	2.50	2.50	2.50	2.50	2.50	2.50
F	74.50	79.50	74.50	79.50	79.50	79.50	84.00
G	38.00	38.00	53.00	53.00	60.00	75.00	72.00
H	36	39	36	39	39	39	41
I	1.50	1.50	1.50	1.50	1.50	1.50	1.50
J	0.53	0.53	0.48	0.48	0.52	0.51	0.51
K	1.50	1.50	1.50	1.50	1.50	1.50	1.50
L	3.50	3.50	3.50	3.50	3.50	3.50	3.50
M	2.50	2.50	2.50	2.50	2.50	2.50	2.50
N	18	18	26	26	29	37	35
P	5.00	5.00	5.00	5.00	5.00	5.00	5.00
Q	5.50	5.50	5.50	5.50	5.50	5.50	5.50
R	0.53	0.53	0.53	0.50	0.50	0.50	0.51
S	100	106	116	122	128	144	144
# of side support pieces	100	106	116	122	128	144	144




602020 62602020

FIGURE 5101

Step 1: Cut foam bun (along dashed lines) with X-Y programmable wire profile saw



Step 2: Separate (discard the small pieces from each end)



682030-6.6602  
Figure 52





Fig. 53

5201  
Step 4: Bond with adhesive (the original 5.00" thickness becomes 7.50")



662090 62620200


Figure ~~54~~ 54

compressed (but not  
buckled) foam rail


5401

5402


buckling foam rail 5403



**Figure 4**




**Figure 56** **2002000**




# Figure 3 S7

662030 626202.60



800-233-8888 **Figure 4**





**Figure 59**

Ultra-firm high tensile

strength polyurethane

foam 3/16" thick full

perimeter of core (or,

felt mat if it glues well;

or urethane film)

Water-based adhesive from ALFA

Adhesives or hot-melt EVA-based

adhesive from Hysol

Saw-cut

recesses for the

gellycomb cell

side walls

S901

1.75" thick gellycomb

Comfort Layer

S902

3/4" OD solid

fiberglass rod with

bent steel tubing as

fittings at corners

S901

6" tall gellycomb

mattress core

Gellycomb is beveled to

one inch below the

surface (top and bottom)

all around the perimeter

Approx 3.5"

(varies by bed size to

fill out the mattress to

standard width/length)

Approx 5.25"

0.10"

1.65"

Circular Blade

Zone Cut

S903

S904

Saw-cut

recesses for

the

gellycomb

Router-cut recess

for the fiber-glass

side support rod

Saw-cut recess

for the gellycomb


perimeter wall

Firm polyurethane

foam around entire


perimeter of core

Fig. 60a




6001

Fig. 60b



Construction: Thin-gauge sheet metal, riveted

# Figure 60



6000 →

~~Fig 60c~~






Figure 61




662337-6-0000  
**Figure 10-62**



**Figure # 63**

63050 63050 63050



**Figure # 64**




Figure 65




Figure 66






Figure 67


5:15

# Figure 67a

662050-62620E00



# Fig 67c



# Fig. 67d




Figure 4  
602030 62A, 67e







Figure # 67a

662050-62620260

✓ 6801 / 6802




Fig. 68b ✓ 6801 / 6802




See Figure 68b for drawing  
concerning this component the  
unpublished drawing

FIG. 69a



Top View

Fig 69b



Front View



End View

6901

Fig 69c

Figure 70

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

7001

7002

Figure 71

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

7101

7102

7103

Figure 72

Quilted Top with Fiber & Foam

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

7002

7004

7003

7001

Figure 73

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

7301

7302

7303

Figure ~~74~~ 74

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

Figure ~~75~~ 75

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

Polyurethane Foam

Figure ~~76~~ 76

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

Polyurethane Foam

Figure ~~77~~ 77

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

High-Grade Visco-Foam

Figure ~~78~~ 78

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

Spring Unit

Figure ~~79~~ 79

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

Spring Unit

Figure ~~80~~ 80

Quilted Top with Fiber & Foam

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

Shallow Spring Unit

Figure ~~81~~ 81

Quilted Top with Fiber

2"-high hollow column gel elastomer with 1" square holes and 0.125" wall thickness

Latex Foam



Figure ~~82~~ 82

Quilted Top with Fiber  
Latex Topper

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

8201 8202 8203

Figure ~~83~~ 83

Quilted Top with Fiber

Latex Foam

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

8301 8302 8303

Figure ~~84~~ 84

Quilted Top with Fiber

Polyurethane Foam

6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

8401 8402 8403

Figure ~~85~~ 85

Quilted Top with Fiber


Pillow-Soft Polyurethane Foam


6"-high hollow column gel elastomer with 1.8" square holes and 0.10" wall thickness

8501 8502 8503

26

Figure 1





Toll Free  
877-85-SLEEP

## Sweet Mornings 1




FIG. 92

## Sweet Mornings 2




FIG. 93

## Spring Science 1




FIG. 87




FIG. 94

## Spring Science 2




FIG. 89




FIG. 95

## Body & Soul 1




FIG. 90




FIG. 96

## Body & Soul 2




FIG. 91




FIG. 97



**IN THE UNITED STATES PATENT AND TRADEMARK OFFICE**

**INVENTOR:** Tony M. Pearce  
**ASSIGNEE:** TekSource, LC  
**DOCKET:** 5039 PRV  
**TITLE:** **IMPROVED CUSHIONING DEVICES, GELATINOUS  
ELASTOMER MATERIALS AND DEVICES MADE  
THEREFROM**

Assistant Commissioner for Patents  
Washington, DC 20231

**DECLARATION FOR PATENT APPLICATION**

As the below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name.

I believe I am the original, first and sole inventor of the subject matter which is claimed and for which a patent is sought on the invention entitled "**IMPROVED CUSHIONING DEVICES, GELATINOUS ELASTOMER MATERIALS AND DEVICES MADE THEREFROM**" filed herewith. I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims. I acknowledge the duty to disclose information which is material to the examination of this application in accordance with Title 37, Code of Federal Regulations, Section 1.56(a).

I hereby appoint Daniel P. McCarthy (Reg. No. 36,600) and Lloyd W. Sadler (Reg. No. 40,154) as my representatives and attorneys to prosecute this application and to transact all business in the Patent and Trademark Office connected therewith. All communications should be directed to Mr. McCarthy at the following address or telephone number:

Daniel P. McCarthy  
McCarthy & Sadler, LC  
39 Exchange Place  
Suite 100

Salt Lake City, Utah 84111  
(801) 323-9399

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

Full name of inventor: Tony M. Pearce

Residence of inventor:

Address: 231 So. Alpine Dr.  
City: Alpine  
State: Utah  
Zip Code: 84004  
Country: USA  
Citizenship: USA

Postal address of inventor:

Address: 231 So. Alpine Dr.  
City: Alpine  
State: Utah  
Zip Code: 84004

Inventor's Signature:

Tony M. Pearce

Date:

5/3/99